

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

INTEROFFICE COMMUNICATION

February 27, 1991

To: Benedict Okwumabua, Livonia, WMD

From: Jan Sealock, EQA, WMD *Jan*

Subject: Quanex Corporation, South Lyons, MI MID 082 767 591

Attached for your information are three copies of Quanex's FY 1991 O&M Inspection. Included with this package is a memo from Dave Slayton and myself with two additional attachments. These items are all being sent to you as outlined in Al Howard's January 25, 1990 Operational Memo 64-4. The steps needed to complete the process are outlined below for your information:

1. The inspection documents should be reviewed to familiarize yourself with the contents.
2. The draft "WMD/District Personnel Summary Letter for CME and O&M Inspections" should be completed, and the recommendations in Dave Slayton/Jan Sealock's memo attached for forwarding on to the facility.
3. The CMEL form accompanying the above two documents should also be completed, based upon your evaluation of the compliance status of the facility.
4. The inspection packets and forms should then be handled in the following manner:
  - a. One packet, with copies of the final District summary letter and the completed CMEL should be sent to US EPA, Region V.
  - b. One packet, with the original final District summary letter should be given to the facility.
  - c. One packet, with copies of the final District summary letter and CMEL should be maintained in the District files.
  - d. A copy of the final District summary letter and CMEL should be sent to HW Geotech Unit to update the Unit and WMD C&E files.

Please call Dave Slayton or myself if you have any questions.

cc: Ms. D. Montgomery ✓

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

INTEROFFICE COMMUNICATION

March 17, 1988

TO: Lynne King, Northville District Office, WMD  
FROM: Liz Browne, HW Permits, WMD *Liz*  
SUBJECT: Quanex Corp., Michigan Seamless Tube Division  
South Lyons, MID 082 767 591

On February 10, 1988 I conducted a sampling inspection at this facility as part of a Comprehensive Monitoring Evaluation (CME). Although no violations of 40 CFR 265.92 [as referenced in Act 64 R299.11003(m)] were found at this time, concerns were noted and are mentioned within the following inspection summary.

EDI Engineering and Science of Grand Rapids conducts all field and laboratory work for the facility. The Ground Water Quality Assessment Program, dated April, 1986, authored by EDI, contained the Sampling and Analysis Plan (SAP) that was used for this review.

Static water level readings are taken with a steel tape to the nearest 0.01 foot. The readings are taken to the top of the casing, and not to the top of the locking cap. Although this is stated in the plan, it should be emphasized to field staff should personnel change. Measurements compared reasonably well with those obtained with the DNR meter.

Purging is accomplished using either stainless steel or teflon bottom filling bailers and polypropylene rope. A new bailer, steam cleaned prior to the site visit, with new rope attached at the time of purging is used. Three casing volumes are purged prior to sampling. The purge water is directed into a graduated bucket to enable a volume measurement, and to facilitate the disposal of the water away from the well. The methods used to determine purge volume needed, method of measuring purge volume removed, and the disposal of the purge water should all be addressed in the plan.

Samples are obtained using the same equipment as, and immediately after, purging, where recovery allows. The plan states that the wells should be sampled within 24 hours of purging. Sampling immediately after purging is the preferable method. If this is not possible, recovery rates should be determined for each well, and sampling done as soon as sufficient volume exists.

Field measured parameters include pH and specific conductance. The meters are calibrated at the beginning of the day. The plan only mentions pH as a field parameter, and does not address the meter calibration. The plan should be updated to reflect field conditions. Other

field work includes the filtering of the metals sample immediately upon collection, prior to preservation. These are all excellent field methods to attempt to maintain the integrity of unstable parameters.

Field QA/QC procedures include the use of clean bailers and new line as already mentioned. Additionally, trip and equipment blanks and sample replicates are used to evaluate the sampling program. These are all good measures to help to assure that representative samples are taken. One item of concern noted during the sampling was the handling of the bailer during volatile organic sampling. The bailer should be lowered carefully for all sample collection, to reduce aeration, but especially for the volatile organics. A note to emphasize this may be appropriate in the plan. Other items of potential concern were not noted during this inspection. The sampling crew appeared to be familiar with the plan, worked carefully, and kept adequate field notes.

Chain of custody appears to be well documented. Field notes, bottle labels, a chain of custody form and an Analytical Services Project Sheet are used to track all samples. Copies of all forms have been included in the plan. Good control can be maintained since sample requests, bottle orders, sampling and analysis are all handled by EDI.

A list of sample parameters with sample container, preservation, holding time, minimum sample size and method references is included in the plan. A table indicating the detection limit attainable by EDI's laboratory is needed to complete this set of information. Also, the method references for some parameters appear to be in error. The Standard Methods reference should be 421, not 412 for dissolved oxygen. Nitrate-nitrite should be method 353 for reference 3, not 201. Reference 3 method 415 should be cited for organic carbon, not 236. All references should be rechecked. The latest editions of the references (SW-846 3rd edition and Standard Methods 16th edition) should be used. Specific methods should be cited, rather than items 200-289 for metals analysis.

A quality assurance/quality control program for EDI's laboratory is needed. Items such as the use of spikes, duplicate samples and standards should be included. The plan does indicate that lab notebooks are kept, and discusses some of the items to be included. This additional information is needed to assure that the careful practices that were evidenced in the field are maintained through the sample preparation and analysis steps.

In summary, both the written plan and the field work were acceptable in most areas. The plan needs to be updated to include details on purging and lab QA/QC. It should also be changed to better reflect the field measurement information, measuring both pH and specific conductance at the time of sampling, as well as the method and schedule of meter calibration. More information on the methods used to filter the samples, and to decontaminate this equipment should be included. Clarification on the time elapsed between purging and sampling should be made, and a note on the care needed for volatile organic sampling should be added. Finally, Table 13 should include detection limits, and the method references need to be checked and updated to reflect newer editions of the references, where applicable.

This concludes the sampling and analysis portion of the CME inspection. A final summary document (including a hydrogeo evaluation, statistical review, ground water contours, etc.) will be forthcoming.

Please call if you have any questions regarding this review.

cc Mr. D. Slayton  
Mr. J. Bohunsky  
Mr. D. Drake  
C&E File  
CME Reports ✓  
Ms. M. Sabadaszka, U.S. EPA-Region V

MID 082 767 591

NATURAL RESOURCES  
COMMISSION

JERRY C. BARTNIK  
LARRY DEVUYST  
PAUL EISELE  
JAMES HILL  
DAVID HOLLI  
JOEY M. SPANO  
JORDAN B. TATTER



JOHN ENGLER, Governor

DEPARTMENT OF NATURAL RESOURCES

John Hannah Building, P.O. Box 30241, Lansing, MI 48909

ROLAND HARMES, Director

March 23, 1994

*Reborel*

Mr. Donald Comfort  
Engineering Manager  
Quanex Corporation  
400 McMunn  
South Lyon, Michigan 48178

Dear Mr. Comfort:

Subject: Quanex 1993 O&M Report  
MID 082 767 591

An O&M inspection has been conducted at the Quanex Corporation, of South Lyon. The inspection included a field audit and split sampling of groundwater (September 27, 1993), O&M checklist, sampling and analysis inspection, monitor well data sheets, groundwater contour map, stiff\piper\pie diagram, and data comparison.

The latest sampling and analysis plan for groundwater monitoring is located within the Groundwater Quality Assessment Program dated April of 1986. This was then approved with revisions on May 20, 1992 by the Michigan Department of Natural Resources.

The attachment to this memo lists one area of concern identified during the field inspection on September 27, 1993. The concern was that depth or sounding measurements were not taken for some of the wells. It is common for sediments to accumulate at the bottom of the well thus changing the depths of the well and the amount of water evacuated for purging. It is therefore, good practice to take depth measurements at each sampling event.

If there are any questions, please contact the number listed below or Mr. David Slayton at 517-373-8012.

Sincerely,

*JAN SEALOCK*

Jan Sealock  
Environmental Quality Analyst  
Waste Management Division  
517-373-4740

cc/enc: Ms. De Montgomery/U.S. EPA Reporting  
Mr. Ben Okwumabua, DNR-Livonia  
Mr. Dave Slayton, DNR  
HWP/C&E File



**ATTACHMENT**


Quanex Corporation  
MID 082 767 591  
O&M Inspection-1993

- 1). Depth or sounding measurements were not taken at some of the wells. This measurement should be taken at each sampling event. [Area of Concern].

# *Operation and Maintenance Inspection*

*Conducted By  
Waste Management Division  
Michigan Department of Natural Resources*

# BASE MAP OF QUANEX MONITOR WELLS





**QUANEX CORPORATION**  
**SOUTH LYON, MICHIGAN**

**MID 082 767 591**

**OPERATION AND MAINTENANCE INSPECTION**

Field Inspection Guide

Sampling and Analysis Inspection

Monitor Well Data Sheets

Ground Water Contour Map

Additional Reviews

1. Stiff\Piper\Bar Diagrams
2. Data Comparison

Summary Letter

**Evaluated By:**

Mr. Dave Slayton  
Ms. Jan Sealock  
Waste Management Division  
Michigan Department of Natural Resources

September 27, 1993

*Field Inspection Guide*  
*Checklist*

# **APPENDIX B**

## **Part Two**

### **Field Inspection Guide**

## PART TWO

The field inspector will complete four tasks during the field inspection. They are:

1) review the operating record to identify evidence of deficiencies in the owner/operator's sampling and/or operation and maintenance programs; 2) visually inspect each well and piezometer for evidence of damage or deterioration; 3) obtain measurements from the operations record of depths of water levels and well depths for each well and piezometer, and 4) visually observe the owner/operator's field crew as they collect ground-water samples.

Name of inspector(s) Dave Stanton / Jimmy Lucille

Date(s) of inspection 9-27-93

1. Review the operating record of the facility. Does the operating record:	Y/N
Include annual reports of ground-water monitoring results including ground-water level data from each well and piezometer in the monitoring system? <i>2 yrs. Rpt. in file folder, under date, each year. Rpt. in another office.</i>	Y
Include an inventory of all sampling devices and purging equipment in use at the facility and information on model number, serial number and manufacturers name? <i>disposable devices used. WUES bring their own sampling equipment</i>	<i>inventory - yes</i> serial #s <i>do.</i> N/A
Include detailed operating, calibration and maintenance procedures for each sampling device? <i>included in SAP</i>	Y
Describe decision criteria to be used to replace or repair sampling equipment and/or monitoring wells? <i>replace wells if damaged (included in SAP)</i>	Y
Include schedules for performing operation and maintenance activities related to the ground-water monitoring system? <i>included in SAP</i>	Y
Include records for ground-water monitoring which provide information on 1) the date, exact place and time of sampling or measurements; 2) the individual(s) who performed the sampling or measurements; 3) the date(s) analyses were performed; 4) the analytical techniques or methods used; and 5) the results of such analyses?	Y
* Include records of all monitoring information including all calibration and maintenance records? <i>Co. said WUES keeps field log - WUES said they give them to Co.</i>	N
Include records of monitoring information including determination of ground-water surface elevations?	Y
Include a determination of ground-water flow rate and direction(s) in the uppermost aquifer on an annual basis (e.g., prepare a potentiometric map annually using data collected during the year)?	Y
Provide for more frequent and intensive inspection of wells constructed of non-inert casing such as PVC? (Refer to Appendix A for permit example.)	N


3. Obtain data on depth to standing water and depth to the bottom of each monitoring well and piezometer in the owner/operator's monitoring system. Record depth measurements to the nearest 0.01 feet. Record the measurements

Date	Well/ Piezometer I.D. No.	Depth to Water (0.01')		Depth of Well/ Piezometer (0.01')
		JURNEY	DNR	
9-27-93	MW-1A	12.61	12.66	
	MW-1C	14.19	14.19	
	MW-11A	15.45	15.40	
	MW-13A	11.20	11.19	
	MW-17A	12.66 <del>11.25</del>	12.64 <del>11.19</del>	23.2 ft.
	MW-17B	15.25	15.22	74 1/2 ft.
	MW-18	14.25	14.23	
	MW-13B		14.68	
	MW-13C		13.23	

**Key:**

- A - survey elevation mark
- B - protective outer casing
- C - gas vent
- D - concrete apron
- E - fitted lock
- F - primary casing material
- G - cap for primary casing
- H - bore hole seal
- I - annular space seal
- J - well screen
- K - filter pack
- L - height of riser
- M - elevation difference
- N - diameter of outer casing
- O - diameter of primary casing
- P - radius of apron
- Q - water level below surface

1. The field inspector has several options in collecting ground water elevation data. The inspector may:
  - a. obtain past data from the operating record; and/or
  - b. take his/her own depth measurements; and/or
  - c. obtain data from the owner/operator's sampling crew.



(Continued)

Well Identification Number _____	Y/N	Photograph Taken Y/N
If the sampling crew used dedicated samplers, did they disassemble and thoroughly clean the devices between samples? <i>used disposable bailers - no need to clean devices between samples</i>	NA	
If samples are collected for organic analyses, did the cleaning procedure include the following steps: 1. non phosphate detergent wash 2. tap water rinse 3. distilled/deionized water rinse 4. acetone rinse 5. pesticide-grade hexane rinse? <i>disposable bailers lab prepared bottles</i>	NA	
If samples are collected for inorganic analyses, does the cleaning procedure include the following steps: 1. dilute acid rinse (HNO <sub>3</sub> or HCL) 2. distilled/de-ionized water rinse? <i>disposable bailers lab prepared bottles</i>	NA	
Did the sampling crew take trip blanks, field blanks and equipment blanks?	Y	
If the sampling crew used bailers, were they bottom valve bailers?	N	
If the sampling crew used bailers, was "teflon" coated wire, single strand stainless steel wire or monofilament used to raise and lower the bailer? <i>polyethylene line</i>	N	
If the sampling crew used bailers, did they lower the bailer slowly to the well?	Y	
If the sampling crew used bailers, were the bailer contents transferred to the sample container to minimize agitation and aeration?	Y	
Did the sampling crew take care to avoid placing clean sampling equipment, hoses, and lines on the ground or other contaminated surfaces prior to insertion in the well?	Y	
If the sampling crew used dedicated bladder pumps: Was the compressed gas from an oilless compressor certified quality commercial compressed gas cylinder? If not, was a suitable oil removal purification system installed and maintained? <i>used bailers</i>	NA	
Was the bladder pump controller capable of throttling the bladder pump discharge flow to 100 ml/min or less for continuous periods of at least 20-30 seconds without restricting liquid discharge?	NA	

(Continued)

Well Identification Number _____	Y/N	Photograph Taken Y/N
Were samples taken from the bladder pump discharge tube, and not from any purge device discharge tube? <i>samples collected w/ boiler</i>	NA	
Was the bladder pump discharge flow checked for the presence of gas bubbles before each sample collection, as a test for bladder integrity?	NA	
Was bladder pump flow performance monitored regularly for dropoff in flow rate and discharge volume per cycle?	NA	
Was the bladder pump incorporated in a combination sample-purge pump design which can expose the bladder pump interior and discharge tubing to the pump drive gas? If so, were operating procedures established and followed to prevent at all times the entry of drive gas into the sample flow or into the bladder pump interior?	NA	
Did the sampling crew collect and containerize samples in the order of the volatilization sensitivity of the parameters?	Y	
Did the sampling crew measure the following parameters in the field: pH, temperature, specific conductance?	Y	
Did the sampling crew sample background wells before sampling downgradient wells? <i>not necessary -&gt; dedicated equipment</i>		
Did the sampling crew use fluorocarbon resin or <u>polyethylene</u> containers with polypropylene caps for samples requiring metals analysis?	Y	
Did the sampling crew use glass bottles with fluorocarbon resin-lined caps for samples requiring metals analysis?	N	
If metals were the analytes of concern, did the sampling crew use containers cleaned with nonphosphate detergent and water, and rinsed with nitric acid, tap water, hydrochloric acid, tap water and finally Type II water? <i>lab prepared containers</i>	NA	
If organics were the analytes of concern, did the sampling crew use containers cleaned with nonphosphate detergent, rinsed with tap water, distilled water, acetone, and finally pesticide quality hexane? <i>lab prepared containers</i>	NA	
Did the sampling crew filter samples requiring analysis for organics? <i>organics should not be filtered</i>	NA	

**After working through Part Two, the field inspector will have:**

- **assessed whether the owner/operator's sampling crew departed from written sampling and analysis procedures as contained in the owner/operator's sampling and analysis plan (interim status) or in the owner/operator's RCRA permit (permit status);**
- **identified deficiencies in the way the owner/operator's sampling crew collected ground-water samples;**
- **identified deficiencies in the owner/operator's program to ensure on-going maintenance of sampling devices and monitoring wells/piezometers;**
- **identified deficiencies in the owner/operator's operating record (Does the operating record have all the information in it that is required?); and**
- **collected field data that will allow the enforcement official to construct potentiometric maps and assess the viability of individual wells.**



*Sampling and Analysis*  
*Inspection*

SAMPLING AND ANALYSIS INSPECTION  
QUANEX CORPORATION  
MID 082 767 591

On September 27th, 1993, a sampling inspection was conducted at the Quanex Corporation as part of an Operation and Maintenance Inspection (O&M). The latest Sampling and Analysis Plan (SAP), is dated April, 1986 with revisions added from deficiencies found in the 1990 O&M inspection.

Consultant Jim Wooster from WW Engineering and Science (WWES) of Livonia was involved in the split sampling. Static water level measurements were conducted using an electric meter by both the MDNR and WWES. All measurements were taken to the nearest .01th of a foot to be used in the making of groundwater contour maps. The largest difference in readings between the wells was .05 feet. For decontamination purposes, WWES rinsed the electric meter with an ample amount of deionized water between the wells. Static water level measurements, purging and sampling was all conducted on September 27, 1993.

A polyethylene disposable bailer was utilized to purge the wells. Purge volumes on the 27th were based on three times the casing water volume, or until the well ran dry. At many of the wells a sounding or depth measurement was not taken. It is important to take the depth measurement at each sampling event due to the settling of sediment that may occur at the bottom of each well. The evacuated water was discharged to a bucket and dumped away from the well. WWES followed good safety protocol by wearing gloves while collecting samples from the wells.

The disposable bailer was also used to collect the water samples that day. No decontamination of the bailers was needed since they were disposable. New polyethylene line was tied to each bailer before sampling. Those samples collected for volatiles were poured slowly from the bailer to reduce aeration of the sample. Samples were stored in appropriate bottles for analysis. The samples were immediately transferred to coolers filled with ice.

Both field parameters of pH and specific conductivity were taken by WWES and the MDNR. Both Meters were calibrated before use, also the pH meter was checked before each well with a buffer. An equipment blank, trip blank and duplicate samples were all taken as part of field QA\QC protocol.

The Sampling and Analysis Plan (SAP), was last revised after the O&M conducted in December of 1990. After review of the plan and sampling procedures, the plan is considered complete.

MICHIGAN DEPARTMENT OF NATURAL RESOURCES  
WASTE MANAGEMENT DIVISION  
Water Sampling Data Sheet

FACILITY: 20ANEX LOCATION: South Lyon  
CONTACT: Donald Comfort PHONE: ( )

Sample #		MW-1A	MW-10	MW-11A	MW-13A	MW-17A	MW-17B
Date		9-27-93					
Time		9:33	10:25	12:20	8:42	11:10	11:35
pH (field)		6.74	6.88	6.84	6.35	6.86	6.90
Conductivity (field)		1150	1080	2140	1650	1330	790
Temperature (°C) (field)		-	-	-	-	-	-
TDS (field)		-	-	-	-	-	-
PO	1	✓	✓	✓	✓	✓	✓
PO	2	✓	✓	✓	✓	✓	✓
ON	3						
OB	GC/MS B/N						
OA	8						
OG	oil & grease						
MA/D	Basic 6/Fe/Mn	✓	✓	✓	✓	✓	✓
	Ca/Mg/Na/K	✓	✓	✓	✓	✓	✓
	Hg/As/Se/Sb/RA	✓	✓	✓	✓	✓	✓
MN	Cl/SO <sub>4</sub> /Alk						
	HCO <sub>3</sub> /CO <sub>3</sub>						
	Fluoride/Cr <sup>6</sup>						
GA	COD/TOC						
	NO <sub>3</sub> /NO <sub>2</sub> /NH <sub>3</sub>						
	Kjel N/TotP						
GG	Phenols						
GB	Total/Free Cn						
Sample Appearance		clear	clear	clear	clear	clear	clear

Additional Notes: \_\_\_\_\_

Basic 6 = Cd, Cr, Cu, Ni, Pb, Zn

MICHIGAN DEPARTMENT OF NATURAL RESOURCES  
WASTE MANAGEMENT DIVISION  
Water Sampling Data Sheet

FACILITY: QUANEX LOCATION: South Lyon  
CONTACT: DONALD Comfort PHONE: ( )

Sample #	FB				
Date	9-27-93				
Time	11:30				
pH (field)	-				
Conductivity (field)	-				
Temperature (°C) (field)	-				
TDS (field)	-				
PO	1	✓			
PO	2	✓			
ON	3				
OB	GC/MS B/N				
OA	8				
OG	oil & grease				
MA/D	Basic 6/Fe/Mn	✓			
	Ca/Mg/Na/K	✓			
	Hg/As/Se/Sb/Pb	✓			
MN	Cl/SO <sub>4</sub> /Atk				
	HCO <sub>3</sub> /CO <sub>3</sub>				
	Fluoride/Cr <sup>+6</sup>				
GA	COD/TOC				
	NO <sub>3</sub> /NO <sub>2</sub> /NH <sub>3</sub>				
	Kjel N/TotP				
GG	Phenols				
GB	Total/Free Cn				
Sample Appearance	clear				

Additional Notes: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Basic 6 = Cd, Cr, Cu, Ni, Pb, Zn

DNR sampling staff: \_\_\_\_\_

Facility sampling staff: \_\_\_\_\_

\* If purging and/or sampling methods differ, report DNR method/facility method

Monitor Well #					
Static Water Level					
Static Method					
Sounding					
Volume Purged					
Purging Method					
Sampling Method					
Lysimeter #					
Volume Purged					
Sampling Method					
Surface Water #					
Description					
Sampling Method					
Detection System #					
Sampling Method					
Private Well #					
Location Sampled.					
Length of Time Purged					

Facility Sampling Notes:

Potential External Sources of Contamination: \_\_\_\_\_

Precautions Taken: \_\_\_\_\_

Field Measurements Taken: \_\_\_\_\_

Handling/Preservation: \_\_\_\_\_

Sampling Bottles Used: \_\_\_\_\_

Replicates and/or Blanks Taken: \_\_\_\_\_

Decontamination Procedures: \_\_\_\_\_

Additional Notes: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

DNR sampling staff: Ginny Loselle & Dave Slayton

Facility sampling staff: \_\_\_\_\_

\* If purging and/or sampling methods differ, report DNR method/facility method

Monitor Well #	MW-1A	MW-2C	MW-11A	MW-13A	MW-17A	MW-17B
Static Water Level	12.66'	14.19'	15.40'	11.19'	12.64'	15.22'
Static Method	Electric Meter			Electric Meter		
Sounding				21.5'	23.2'	74 1/2'
Volume Purged	3 3/4 gal.	31 1/4 gal.	5.75 gal.	5 gal.	5 1/2 gal.	30 1/2 gal.
Purging Method	Polyethylene Bag	Polyethylene Bag	Polyethylene Bag	Polyethylene Bag	Polyethylene Bag	Polyethylene Bag
Sampling Method	" "	" "	" "	" "	" "	" "
Lysimeter #						
Volume Purged						
Sampling Method						
Surface Water #						
Description						
Sampling Method						
Detection System #						
Sampling Method						
Private Well #						
Location Sampled						
Length of Time Purged						

Facility Sampling Notes:

Potential External Sources of Contamination: None Noted

Precautions Taken: Steel Toed boots, Gloves, Safety Glasses

Field Measurements Taken: pH, Conductivity

Handling/Preservation: As Appropriate

Sampling Bottles Used: As Appropriate

Replicates and/or Blanks Taken: Field Blanks

Decontamination Procedures: Deionize Water Rinse

Additional Notes: \_\_\_\_\_

MICHIGAN DEPARTMENT OF NATURAL RESOURCES  
ENVIRONMENTAL LABORATORY

REPORT Waste Management Division  
TO Ottawa Building  
Lansing, MI 48909  
ATTEN JAN SEALOCK

LABORATORY WORK ORDER # 93-09-164  
WORK ID GUANEX  
P.O. # 60026 COST \$ 1745.80  
RECEIVED 09/27/93 CLIENT WM  
REPORTED \_\_\_\_\_ NUMBER OF SAMPLES 7  
LAB CONTACT OR IN MATRIX WATER

TEST	UNITS	MW-1A	MW-1C	MW-11A	MW-13A
Alkalinity of Water		289	339	206	786
mg CaCO3/l					
Carbonate Alkalinity		K 5	K 5	K 5	K 5
mg CaCO3/l					
Bicarbonate Alkalinity		289	339	206	786
mg CaCO3/l					
Chloride in Water		101	107	156	17
mg/l					
Arsenic by Furnace - Diss.		K 1.0	10.3	3.0	3.7
ug/l (Diss)					
Barium - Dissolved		85	80	26	200
ug/l (Diss)					
Calcium - Dissolved		142	122	306	277
mg/l (Diss)					
Cadmium - Dissolved		K 20	K 20	K 20	K 20
ug/l (Diss)					
Chromium - Dissolved		K 25	K 25	K 25	K 25
ug/l (Diss)					
Copper - Dissolved		K 20	K 20	K 20	K 20
ug/l (Diss)					
Iron - Dissolved		5000	2300	1800	9800
ug/l (Diss)					
Potassium - Dissolved		5.02	3.7	22.6	6.1
mg/l (Diss)					
Magnesium - Dissolved		14.4	28.1	43	43
mg/l (Diss)					
Manganese - Dissolved		270	38	470	650
ug/l (Diss)					
Sodium - Dissolved		61.6	55.4	99.4	26.5
mg/l (Diss)					
Nickel - Dissolved		K 50	K 50	K 50	K 50
ug/l (Diss)					
Lead - Dissolved		K 50	K 50	K 50	K 50
ug/l (Diss)					
Zinc - Dissolved		340	K 50	K 50	K 50
ug/l (Diss)					
Sulfate in Water		114	47	676	53
mg/l					

RECEIVED

DEC 09 1993

Waste Management  
Division

Page 2  
Received: 09/27/93

DNR Laboratory  
12/03/93 12:31:00

REPORT

Work Order # 93-09-164

TEST	MW-17A	MW-17B	FB
UNITS			
Alkalinity of Water	275	285	K 20
mg CaCO3/l			
Carbonate Alkalinity	K 5	K 5	K 5
mg CaCO3/l			
Bicarbonate Alkalinity	275	285	K 20
mg CaCO3/l			
Chloride in Water	169	58	K 1
mg/l			
Arsenic by Furnace - Diss.	6.8	14.8	K 1.0
ug/l (Diss)			
Barium - Dissolved	54	146	K 5
ug/l (Diss)			
Calcium - Dissolved	164	90.8	K 1
mg/l (Diss)			
Cadmium - Dissolved	K 20	K 20	K 20
ug/l (Diss)			
Chromium - Dissolved	K 25	K 25	K 25
ug/l (Diss)			
Copper - Dissolved	K 20	K 20	K 20
ug/l (Diss)			
Iron - Dissolved	1900	1700	K 100
ug/l (Diss)			
Potassium - Dissolved	3.21	1.59	K .1
mg/l (Diss)			
Magnesium - Dissolved	16.7	30.3	K 1
mg/l (Diss)			
Manganese - Dissolved	240	28	K 20
ug/l (Diss)			
Sodium - Dissolved	91.4	12.6	K 1
mg/l (Diss)			
Nickel - Dissolved	K 50	K 50	K 50
ug/l (Diss)			
Lead - Dissolved	K 50	K 50	K 50
ug/l (Diss)			
Zinc - Dissolved	K 50	K 50	K 50
ug/l (Diss)			
Sulfate in Water	148	41	K 2
mg/l			

Report prepared By:

*D Hartig* 12-7-93



Page 3  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID MW-1A FRACTION 01C TEST CODE W VOL NAME Volatile 0260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

CAS#	COMPOUND	UNITS <u>ug/L ppb</u>	RESULT	REMARK	REPORTED DETECTION LIMIT
74-87-3	Chloromethane		ND		5.0
75-01-4	Vinyl chloride		ND		5.0
74-83-9	Bromomethane		ND		5.0
75-00-3	Chloroethane		ND		5.0
67-64-1	2-Propanone (Acetone)		ND		5.0
75-35-4	1,1-Dichloroethene		ND		1.0
75-09-2	Methylene chloride		ND		5.0
75-15-0	Carbon Disulfide		ND		5.0
156-60-5	trans-1,2-Dichloroethene		ND		1.0
1634-04-4	Methyl Tert. Butyl Ether		ND		5.0
75-34-3	1,1-Dichloroethane		ND		1.0
78-93-3	2-Butanone (MEK)		ND		5.0
156-59-2	cis-1,2-Dichloroethene		ND		1.0
67-66-3	Chloroform		ND		1.0
71-55-6	1,1,1-Trichloroethane		ND		1.0
107-06-2	1,2-Dichloroethane		ND		1.0
71-43-2	Benzene		ND		1.0
56-23-5	Carbon tetrachloride		ND		1.0
78-87-5	1,2-Dichloropropane		ND		1.0
79-01-6	Trichloroethene		ND		1.0
75-27-4	Bromodichloromethane		ND		1.0
591-78-6	2-Hexanone		ND		5.0
10061-01-5	cis-1,3-Dichloropropene		ND		1.0
10061-02-6	trans-1,3-Dichloropropene		ND		1.0
108-88-3	Toluene		ND		1.0
75-00-5	1,1,2-Trichloroethane		ND		1.0
108-10-1	4-Methyl-2-Propanone (MIBK)		ND		5.0
124-48-1	Dibromochloromethane		ND		1.0
106-93-4	1,2-Dibromoethane		ND		1.0
127-18-4	Tetrachloroethene		ND		1.0
108-90-7	Chlorobenzene		ND		1.0
100-41-4	Ethylbenzene		ND		1.0
108-38-3 & 106-42-3	m & p Xylene		ND		1.0
75-25-2	Bromoform		ND		1.0
100-42-5	Styrene		ND		1.0
95-47-6	o-Xylene		ND		1.0
79-34-5	1,1,2,2-Tetrachloroethane		ND		1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.

Page 4  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID MW-1C FRACTION Q2C TEST CODE W VOL NAME Volatile 8260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

CASH	COMPOUND	UNITS <u>ug/L ppb</u>	RESULT	REMARK	REPORTED DETECTION LIMIT
74-87-3	Chloromethane	ND			5.0
75-01-4	Vinyl chloride	ND			5.0
74-83-9	Bromomethane	ND			5.0
75-00-3	Chloroethane	ND			5.0
67-64-1	2-Propanone (Acetone)	ND			5.0
75-35-4	1,1-Dichloroethene	ND			1.0
75-09-2	Methylene chloride	ND			5.0
75-15-0	Carbon Disulfide	ND			5.0
156-60-5	trans-1,2-Dichloroethene	ND			1.0
1634-04-4	Methyl Tert. Butyl Ether	ND			5.0
75-34-3	1,1-Dichloroethane	ND			1.0
78-93-3	2-Butanone (MEK)	ND			5.0
156-59-2	cis-1,2-Dichloroethene	ND			1.0
67-66-3	Chloroform	ND			1.0
71-55-6	1,1,1-Trichloroethane	ND			1.0
107-06-2	1,2-Dichloroethane	ND			1.0
71-43-2	Benzene	ND			1.0
56-23-5	Carbon tetrachloride	ND			1.0
78-97-5	1,2-Dichloropropane	ND			1.0
79-01-6	Trichloroethene	ND			1.0
75-27-4	Bromodichloromethane	ND			1.0
591-78-6	2-Hexanone	ND			5.0
10061-01-5	cis-1,3-Dichloropropene	ND			1.0
10061-02-6	trans-1,3-Dichloropropene	ND			1.0
108-88-3	Toluene	ND			1.0
77-00-5	1,1,2-Trichloroethane	ND			1.0
108-10-1	4-Methyl-2-Propanone (MIBK)	ND			5.0
124-48-1	Dibromochloromethane	ND			1.0
105-93-4	1,2-Dibromoethane	ND			1.0
127-18-4	Tetrachloroethene	ND			1.0
108-90-7	Chlorobenzene	ND			1.0
100-41-4	Ethylbenzene	ND			1.0
108-38-3 & 106-42-3	m & p Xylene	ND			1.0
75-25-2	Bromoform	ND			1.0
100-42-5	Styrene	ND			1.0
95-47-6	o-Xylene	ND			1.0
77-34-5	1,1,2,2-Tetrachloroethane	ND			1.0

COMMENTS

ND = not detected at the specified detection limit.

Page 5  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID MW-11A FRACTION 03C TEST CODE W VOL NAME Volatile 8260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

CAS#	COMPOUND	UNITS <u>ug/L ppb</u>	RESULT	REMARK	REPORTED DETECTION LIMIT
74-87-3	Chloromethane	ND			5.0
75-01-4	Vinyl chloride	ND			5.0
74-83-9	Bromomethane	ND			5.0
75-00-3	Chloroethane	ND			5.0
67-64-1	2-Propanone (Acetone)	ND			5.0
75-35-4	1,1-Dichloroethene	ND			1.0
75-09-2	Methylene chloride	ND			5.0
75-15-0	Carbon Disulfide	ND			5.0
156-60-5	trans-1,2-Dichloroethene	ND			1.0
1634-04-4	Methyl Tert. Butyl Ether	ND			5.0
75-34-3	1,1-Dichloroethane	17	J		1.0
78-93-3	2-Butanone (MEK)	ND			5.0
156-59-2	cis-1,2-Dichloroethene	ND			1.0
67-66-3	Chloroform	ND			1.0
71-55-6	1,1,1-Trichloroethane	ND			1.0
107-06-2	1,2-Dichloroethane	ND			1.0
71-43-2	Benzene	ND			1.0
56-23-5	Carbon tetrachloride	ND			1.0
78-87-5	1,2-Dichloropropane	ND			1.0
79-01-6	Trichloroethene	ND			1.0
75-27-4	Bromodichloromethane	ND			1.0
591-78-6	2-Hexanone	ND			5.0
10061-01-5	cis-1,3-Dichloropropene	ND			1.0
10061-02-6	trans-1,3-Dichloropropene	ND			1.0
108-88-3	Toluene	ND			1.0
79-00-5	1,1,2-Trichloroethane	ND			1.0
108-10-1	4-Methyl-2-Propanone (MIBK)	ND			5.0
124-48-1	Dibromochloromethane	ND			1.0
106-93-4	1,2-Dibromoethane	ND			1.0
127-18-4	Tetrachloroethene	ND			1.0
108-90-7	Chlorobenzene	ND			1.0
100-41-4	Ethylbenzene	ND			1.0
108-38-3 & 106-42-3	m & p Xylene	ND			1.0
75-25-2	Bromoform	ND			1.0
100-42-5	Styrene	ND			1.0
95-47-6	o-Xylene	ND			1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND			1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.

Page 6  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID MW-13A FRACTION 04C TEST CODE W VOL NAME Volatile 8260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

		UNITS			REPORTED
		ug/L			DETECTION
		ppb			LIMIT
CAS#	COMPOUND	RESULT	REMARK		
74-87-3	Chloromethane	ND			5.0
75-01-4	Vinyl chloride	ND			5.0
74-83-9	Bromomethane	ND			5.0
75-00-3	Chloroethane	ND			5.0
67-64-1	2-Propanone (Acetone)	ND			5.0
75-35-4	1,1-Dichloroethene	ND			1.0
75-09-2	Methylene chloride	ND			5.0
75-15-0	Carbon Disulfide	ND			5.0
156-60-5	trans-1,2-Dichloroethene	ND			1.0
1634-04-4	Methyl Tert. Butyl Ether	ND			5.0
75-34-3	1,1-Dichloroethane	ND			1.0
78-93-3	2-Butanone (MEK)	ND			5.0
156-59-2	cis-1,2-Dichloroethene	ND			1.0
67-66-3	Chloroform	ND			1.0
71-55-6	1,1,1-Trichloroethane	ND			1.0
107-06-2	1,2-Dichloroethane	ND			1.0
71-43-2	Benzene	ND			1.0
56-23-5	Carbon tetrachloride	ND			1.0
78-87-5	1,2-Dichloropropane	ND			1.0
79-01-6	Trichloroethene	ND			1.0
75-27-4	Bromodichloromethane	ND			1.0
591-78-6	2-Hexanone	ND			5.0
10061-01-5	cis-1,3-Dichloropropene	ND			1.0
10061-02-6	trans-1,3-Dichloropropene	ND			1.0
106-88-3	Toluene	ND			1.0
79-00-5	1,1,2-Trichloroethane	ND			1.0
108-10-1	4-Methyl-2-Propanone (MIBK)	ND			5.0
124-48-1	Dibromochloromethane	ND			1.0
106-93-4	1,2-Dibromoethane	ND			1.0
127-18-4	Tetrachloroethene	ND			1.0
106-90-7	Chlorobenzene	ND			1.0
100-41-4	Ethylbenzene	ND			1.0
106-38-3 & 106-42-3	m & p Xylene	ND			1.0
75-25-2	Bromoform	ND			1.0
100-42-5	Styrene	ND			1.0
95-47-6	o-Xylene	ND			1.0
78-34-5	1,1,2,2-Tetrachloroethane	ND			1.0

COMMENTS

ND = not detected at the specified detection limit.

Page 7  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID MW-17A FRACTION 05C TEST CODE W VOL NAME Volatile 8260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

		UNITS <u>ug/L ppb</u>	REPORTED
			DETECTION
CAS#	COMPOUND	RESULT	LIMIT
74-87-3	Chloromethane	ND	5.0
75-01-4	Vinyl chloride	ND	5.0
74-83-9	Bromomethane	ND	5.0
75-00-3	Chloroethane	ND	5.0
67-64-1	2-Propanone (Acetone)	ND	5.0
75-35-4	1,1-Dichloroethene	ND	1.0
75-09-2	Methylene chloride	ND	5.0
75-15-0	Carbon Disulfide	ND	5.0
156-60-5	trans-1,2-Dichloroethene	ND	1.0
1634-04-4	Methyl Tert. Butyl Ether	ND	5.0
75-34-3	1,1-Dichloroethane	1.4 J	1.0
78-93-3	2-Butanone (MEK)	ND	5.0
156-59-2	cis-1,2-Dichloroethene	ND	1.0
67-66-3	Chloroform	ND	1.0
71-55-6	1,1,1-Trichloroethane	3.9	1.0
107-06-2	1,2-Dichloroethane	ND	1.0
71-43-2	Benzene	ND	1.0
56-23-5	Carbon tetrachloride	ND	1.0
78-67-5	1,2-Dichloropropane	ND	1.0
79-01-6	Trichloroethene	ND	1.0
75-27-4	Bromodichloromethane	ND	1.0
591-78-6	2-Hexanone	ND	5.0
10061-01-5	cis-1,3-Dichloropropene	ND	1.0
10061-02-6	trans-1,3-Dichloropropene	ND	1.0
108-88-3	Toluene	ND	1.0
79-00-5	1,1,2-Trichloroethane	ND	1.0
108-10-1	4-Methyl-2-Propanone (MIBK)	ND	5.0
124-48-1	Dibromochloromethane	ND	1.0
106-93-4	1,2-Dibromoethane	ND	1.0
127-18-4	Tetrachloroethene	ND	1.0
106-90-7	Chlorobenzene	ND	1.0
100-41-4	Ethylbenzene	ND	1.0
108-38-3 & 106-42-3	m & p Xylene	ND	1.0
75-25-2	Bromoform	ND	1.0
100-42-5	Styrene	ND	1.0
95-47-8	o-Xylene	ND	1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND	1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.

Page 8  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID MW-17B FRACTION 06C TEST CODE W VOL NAME Volatile 8260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

CAS#	COMPOUND	UNITS <u>ug/L ppb</u>	RESULT	REMARK	REPORTED DETECTION LIMIT
74-87-3	Chloromethane	ND			5.0
75-01-4	Vinyl chloride	ND			5.0
74-83-9	Bromomethane	ND			5.0
75-00-3	Chloroethane	ND			5.0
67-64-1	2-Propanone (Acetone)	ND			5.0
75-35-4	1,1-Dichloroethene	ND			1.0
75-09-2	Methylene chloride	ND			5.0
75-15-0	Carbon Disulfide	ND			5.0
156-60-5	trans-1,2-Dichloroethene	ND			1.0
1634-04-4	Methyl Tert. Butyl Ether	ND			5.0
75-34-3	1,1-Dichloroethane	ND			1.0
78-93-3	2-Butanone (MEK)	ND			5.0
156-59-2	cis-1,2-Dichloroethene	ND			1.0
67-66-3	Chloroform	ND			1.0
71-55-6	1,1,1-Trichloroethane	ND			1.0
107-06-2	1,2-Dichloroethane	ND			1.0
71-43-2	Benzene	ND			1.0
56-23-5	Carbon tetrachloride	ND			1.0
78-97-8	1,2-Dichloropropane	ND			1.0
75-01-6	Trichloroethene	ND			1.0
75-27-4	Bromodichloromethane	ND			1.0
591-78-6	2-Hexanone	ND			5.0
10061-01-5	cis-1,3-Dichloropropene	ND			1.0
10061-02-6	trans-1,3-Dichloropropene	ND			1.0
108-88-3	Toluene	ND			1.0
74-00-5	1,1,2-Trichloroethane	ND			1.0
108-10-1	4-Methyl-2-Propanone (MIBK)	ND			5.0
124-48-1	Dibromochloromethane	ND			1.0
106-93-4	1,2-Dibromoethane	ND			1.0
127-18-4	Tetrachloroethene	ND			1.0
108-90-7	Chlorobenzene	ND			1.0
100-41-4	Ethylbenzene	ND			1.0
108-38-3 & 106-42-3	m & p Xylene	ND			1.0
75-25-2	Bromoform	ND			1.0
100-42-5	Styrene	ND			1.0
95-47-6	o-Xylene	ND			1.0
77-34-5	1,1,2,2-Tetrachloroethane	ND			1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.

Page 9  
Received: 09/27/93

DNR Laboratory REPORT  
Results by Sample

Work Order # 93-09-164

SAMPLE ID FB FRACTION 07C TEST CODE W VOL NAME Volatile 8260 WATER  
Date & Time Collected 09/27/93 Category \_\_\_\_\_

ANALYST GRINWIS  
ANALYZED 09/28/93  
DILUTION 1

CAS#	COMPOUND	UNITS <u>ug/L ppb</u>	RESULT	REMARK	REPORTED DETECTION LIMIT
74-87-3	Chloromethane	ND			5.0
75-01-4	Vinyl chloride	ND			5.0
74-83-9	Bromomethane	ND			5.0
75-00-3	Chloroethane	ND			5.0
67-64-1	2-Propanone (Acetone)	ND			5.0
75-35-4	1,1-Dichloroethene	ND			1.0
75-09-2	Methylene chloride	ND			5.0
75-15-0	Carbon Disulfide	ND			5.0
156-60-5	trans-1,2-Dichloroethene	ND			1.0
1634-04-4	Methyl Tert. Butyl Ether	ND			5.0
75-34-3	1,1-Dichloroethane	ND			1.0
78-93-3	2-Butanone (MEK)	ND			5.0
156-59-2	cis-1,2-Dichloroethene	ND			1.0
67-66-3	Chloroform	ND			1.0
71-55-6	1,1,1-Trichloroethane	ND			1.0
107-06-2	1,2-Dichloroethane	ND			1.0
71-43-2	Benzene	ND			1.0
56-23-5	Carbon tetrachloride	ND			1.0
78-87-5	1,2-Dichloropropane	ND			1.0
79-01-6	Trichloroethene	ND			1.0
75-27-4	Bromodichloromethane	ND			1.0
591-78-6	2-Hexanone	ND			5.0
10061-01-5	cis-1,3-Dichloropropene	ND			1.0
10061-02-6	trans-1,3-Dichloropropene	ND			1.0
108-88-3	Toluene	ND			1.0
79-00-5	1,1,2-Trichloroethane	ND			1.0
108-10-1	4-Methyl-2-Propanone (MIBK)	ND			5.0
124-48-1	Dibromochloromethane	ND			1.0
106-93-4	1,2-Dibromoethane	ND			1.0
127-18-4	Tetrachloroethene	ND			1.0
108-90-7	Chlorobenzene	ND			1.0
100-41-4	Ethylbenzene	ND			1.0
108-39-3 & 106-42-3	m & p Xylene	ND			1.0
75-25-2	Bromoform	ND			1.0
100-42-5	Styrene	ND			1.0
95-47-6	o-Xylene	ND			1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND			1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.

Duanex Corporation - Sampled September 27<sup>th</sup>, 1993

			MID	082	767	591			
Inorganics (PPM)	MW-1A	MW-1C	MW-1A	MW-13A	MW-17A	MW-17B	FB		
Alkalinity	289	339	206	786	275	285	<20		
Carbonate	<5	<5	<5	<5	<5	<5	<5		
Bicarbonate	289	339	206	786	275	285	<20		
Chloride	101	107	156	17	169	58	<1		
Diss. Arsenic	<.001	.0103	.003	.0037	.0068	.0148	<.001		
Diss. Barium									
Diss. Calcium	142	122	306	277	164	90.8	<1		
Diss. Cadmium	<.020	<.020	<.020	<.020	<.020	<.020	<.020		
Diss. Chromium	<.025	<.025	<.025	<.025	<.025	<.025	<.025		
Diss. Copper	<.020	<.020	<.020	<.020	<.020	<.020	<.020		
Diss. Iron	5	2.3	1.8	9.8	1.9	1.7	<.100		
Diss. Potassium	5.02	3.7	22.6	6.1	3.21	159	<.100		
Diss. Magnesium	14.4	28.1	43	43	16.7	30.3	<1		
Diss. Manganese	.270	.038	.470	.650	.240	.028	<.020		
Diss. Sodium	61.6	55.4	99.4	26.5	9.4	12.6	<1		
Diss. Nickel	<.050	<.050	<.050	<.050	<.050	<.050	<.050		
Diss. Lead	<.050	<.050	<.050	<.050	<.050	<.050	<.050		
Diss. Zinc	1340	<.050	<.050	<.050	<.050	<.050	<.050		
Sulfate	114	47	1676	53	148	41	<2		

Organics (PPB)

Seal 8260

1,1-Dichloroethane	ND	ND	17-J	ND	1.4 J	ND	ND
1,1,1-Trichloroethane	ND	ND	ND	ND	3.9	ND	ND

J = Estimated value; value may not be accurate



EL 070

7/9/91

MATRIX = WATER

## MICHIGAN DEPT OF NATURAL RESOURCES

ENVIRONMENTAL LABORATORY

ANALYSIS REQUEST SHEET

#### SAFETY WARNING ####

YES ☒ NO - INFO ON BACK

LAB ORDER# 9309164 PROJ CODE II RECEIVED AT LAB BY ML DATE 9/27/93 TIME 4:40 ☒ AM ☒ PM

SUBMITTER WMD DISTRICT Lansing CONTACT PERSON Dave Slagter PHONE (517) - 373-8012

DIVISION WMD OR OFFICE H.W. Permits FOR QUESTIONS Dave Slagter

LOCATION Quarner COLLECTED BY Lo Selk/Slagter TRANS TO

COST CENTER 60026 SEND RESULTS TO ATTENTION OF Jan Seelock AT ADDRESS H.W. Permits  
(if different than above office) WMD  
Hannab Bldg, Lansing

SAMPLE REMARKS Groundwater

SAMPLE NUMBER	FIELD ID OR DESCRIPTION (25 Characters)	SAMPLE COLLECTED YY/MM/DD	HH:MM	SAMPLE INFORMATION
01	MW-21A	930927	9:33	upgrad shallow
02	MW-1C	930927	10:25	upgrad. deep
03	MW-11A	930927	12:20	dngrd shallow
04	MW-13A	930927	8:42	dngrd shallow
05	MW-17A	930927	11:10	upgrad. shallow

## GENERAL CHEMISTRY

## ORGANICS

## INORGANIC

DO Diss Oxygen ... 1 2 3 4 5	PO1 #1 Halocarbons 1 2 3 4 5	MA Total Metals ... 1 2 3 4 5
CN NO2, o-Phos ... 1 2 3 4 5	PO2 #2 Aromatic HC 1 2 3 4 5	MAD Diss-Field Filtered ... 1 2 3 4 5
Residue SS ... 1 2 3 4 5	ON #3 Chloro HC + Pest & PCB 1 2 3 4 5	MD Diss-Lab Filtered ... 1 2 3 4 5
Residue TDS ... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Ca Mg Na K ... 1 2 3 4 5
BOD Tot 5 day 1 2 3 4 5	OA #8 Phenols ... 1 2 3 4 5	Cd Cr Cu Ni Pb Zn ... 1 2 3 4 5
BOD Carb 5 day 1 2 3 4 5		Fe Co Li Mn ... 1 2 3 4 5
CA Chlorophyll ... 1 2 3 4 5		Al Ba Be Mo Ti V ... 1 2 3 4 5
GA COD ... 1 2 3 4 5		Hg - Mercury ... 1 2 3 4 5
TOC ... 1 2 3 4 5		Se - Selenium ... 1 2 3 4 5
NO3+NO2, NH3 .. 1 2 3 4 5		Sb - Antimony ... 1 2 3 4 5
KJEL N, Tot P . 1 2 3 4 5		LOW LEVEL Ag ... 1 2 3 4 5
66 Phenolics ... 1 2 3 4 5		As ... 1 2 3 4 5
68 Total CN ... 1 2 3 4 5		Cd Cr Cu Ni Pb 1 2 3 4 5
Free CN ... 1 2 3 4 5		Zn Fe ... 1 2 3 4 5
		MN pH, Conductance ... 1 2 3 4 5
		Cl, SO4, Total Alk ... 1 2 3 4 5
		HCO3- CO3= ... 1 2 3 4 5
		CR+6 ... 1 2 3 4 5
		OG Oil and Grease ... 1 2 3 4 5

Initial to indicate that you will accept "HT" coded results for late arriving samples.

EL 070  
7/91  
MATRIX = WATER

MICHIGAN DEPT OF NATURAL RESOURCES  
ENVIRONMENTAL LABORATORY  
ANALYSIS REQUEST SHEET

#### SAFETY WARNING ####  
YES / ☒ NO INFO ON BACK

LAB ORDER# 9309164 PROJ CODE        PRIORITY II RECEIVED DATE 9/27/93 TIME 14:40 AM  
SUBMITTER WMD DISTRICT Lansing CONTACT PERSON Dave Skypen PHONE (517) 373-8010  
DIVISION WMD OR OFFICE H.W. Permits FOR QUESTIONS Dave Skypen

LOCATION Quarry COLLECTED BY LoSelle/Skypen TRANS TO       

COST CENTER 60026 SEND RESULTS TO ATTENTION OF Jan Seaback AT ADDRESS H.W. Permits  
(if different than above office) WMD  
REMARKS Groundwater Hannab Bldg, Lansing

ISAMPLE NUMBER	FIELD ID OR DESCRIPTION (25 Characters)	SAMPLE COLLECTED YY/MM/DD	HH:MM	SAMPLE INFORMATION
06	4w-17B	930927	11:35	up/mod. log
07	FB	930927	11:30	Field Blank
03				
04				
05				

GENERAL CHEMISTRY		ORGANICS		INORGANIC	
DO	Diss Oxygen ... 1 2 3 4 5	P01	#1 Halocarbons 1 2 3 4 5	MA	Total Metals ..... 1 2 3 4 5
GN	NO2, o-Phos ... 1 2 3 4 5	P02	#2 Aromatic HC 1 2 3 4 5	MAD	Diss-Field Filtered ... 1 2 3 4 5
	Residue SS .... 1 2 3 4 5		..... 1 2 3 4 5	MD	Diss-Lab Filtered ..... 1 2 3 4 5
	Residue TDS ... 1 2 3 4 5	ON	#3 Chloro HC + Pest & PCB 1 2 3 4 5		Ca Mg Na K ..... 1 2 3 4 5
	..... 1 2 3 4 5		..... 1 2 3 4 5		Cd Cr Cu Ni Pb Zn ... 1 2 3 4 5
	BOD Tot 5 day 1 2 3 4 5		..... 1 2 3 4 5		Fe Co Li Mn ..... 1 2 3 4 5
	BOD Carb 5 day 1 2 3 4 5		..... 1 2 3 4 5		Al Ba Be Mo Ti V ..... 1 2 3 4 5
	..... 1 2 3 4 5	OB	GC/MS Base Neut 1 2 3 4 5		..... 1 2 3 4 5
CA	Chlorophyll ... 1 2 3 4 5		..... 1 2 3 4 5		Hg - Mercury ..... 1 2 3 4 5
	..... 1 2 3 4 5	OA	#8 Phenols .... 1 2 3 4 5		Se - Selenium ..... 1 2 3 4 5
GA	COD ..... 1 2 3 4 5		..... 1 2 3 4 5		Sb - Antimony ..... 1 2 3 4 5
	TOC ..... 1 2 3 4 5		..... 1 2 3 4 5		..... 1 2 3 4 5
	NO3+NO2, NH3 .. 1 2 3 4 5		..... 1 2 3 4 5		LOW LEVEL Ag ..... 1 2 3 4 5
	KJEL N, Tot P. 1 2 3 4 5		..... 1 2 3 4 5		" As ..... 1 2 3 4 5
	..... 1 2 3 4 5		..... 1 2 3 4 5		" Cd Cr Cu Ni Pb 1 2 3 4 5
	..... 1 2 3 4 5		..... 1 2 3 4 5		" Zn Fe ..... 1 2 3 4 5
GG	Phenolics ..... 1 2 3 4 5		..... 1 2 3 4 5		
	..... 1 2 3 4 5		..... 1 2 3 4 5	MN	pH, Conductance ..... 1 2 3 4 5
GB	Total CN ..... 1 2 3 4 5		..... 1 2 3 4 5		Cl, SO4, Total Alk ... 1 2 3 4 5
	Free CN ..... 1 2 3 4 5		..... 1 2 3 4 5		HCO3- CO3= ..... 1 2 3 4 5
	..... 1 2 3 4 5		..... 1 2 3 4 5		CR+6 ..... 1 2 3 4 5
	..... 1 2 3 4 5		..... 1 2 3 4 5		..... 1 2 3 4 5
	..... 1 2 3 4 5		..... 1 2 3 4 5	OG	Oil and Grease ..... 1 2 3 4 5

Initial to indicate that you will accept "HT" coded results for late arriving samples.

*Monitor Well Data Sheets*

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: JOANEX Location: South Lyon  
 Type of Facility: seamless tube manufacture  
 Contact: Donald Comfort Phone: ( )

WELL INFORMATION

Name/Number: MW-1A Cap Locked: Yes ☒ No ☐  
 Depth:                      Casing Material: galv.  
 Diameter: 2" Screen Slot Size:                       
 Casing Ht. Above Ground: 23' Screen Length:                       
 Top of Casing Elev.:                      Screen Material:                       
 Protective Barrier: NO Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition: good  
 Elevation of Screened Interval:                      to                       
 Location of TOC Survey Mark: none

Measured from latch on  
 permanent metal collar  
 casing (as reference)

SAMPLING INFORMATION Sampled: 9:33

WWES: J. Wooten

Initial Static Water Level:  
 Method:  
 Measured By:  
 Stabilized pH:  
 Stabilized Conductance:  
 Temperature:

DNR	FACILITY
<u>12.66</u>	<u>12.61</u>
<u>Elev. top</u>	<u>Elev. Top</u>
<u>Sample</u>	<u>9m</u>
<u>6.74</u>	<u>6.93</u>
<u>1150</u>	<u>938</u>
	<u>13.60</u>

Purge Method: polythene tubes Vol. Purged: 3<sup>3</sup> gallons  
 Fate of Purge Water: bucket (good water) dumped on road  
 Recovery Rate: good Appearance: clear (no rust, salt, brown)  
 Sampling Method: poly tubes Appearance: clear  
 Staff Present: D. L. Loeble, S. L. Loeble Date: 9-27-83

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes: MW-1B = 14.33' static (14.35 WWES)

no soundings taken

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: QUANEX Location: South Lyon  
 Type of Facility: seamless tube manufacturing  
 Contact: Donald Compost Phone: ( )

WELL INFORMATION

Name/Number: MW-1C (Deep) Cap Locked: Yes ☒ No ☐  
 Depth:                      Casing Material: PVC  
 Diameter: 2" Screen Slot Size:                       
 Casing Ht. Above Ground: 23' Screen Length:                       
 Top of Casing Elev.:                      Screen Material:                       
 Protective Barrier: YES Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition: good  
 Elevation of Screened Interval:                      to                       
 Location of TOC Survey Mark: none

SAMPLING INFORMATION sampled 10:25

	DNR	FACILITY
Initial Static Water Level:	<u>14.19</u>	<u>14.19</u>
Method:	<u>Static</u>	<u>Static</u>
Measured By:	<u>Hayter</u>	<u>Jim</u>
Stabilized pH:	<u>6.88</u>	<u>6.92</u>
Stabilized Conductance:	<u>1080</u>	<u>950</u>
Temperature:		<u>12.5°</u>

Purge Method: polyethylene hose Vol. Purged: 317 gallons  
 Fate of Purge Water:                       
 Recovery Rate: good Appearance: clear  
 Sampling Method: polyethylene Appearance: clear  
 Staff Present: Donald Compost / Clayton / Woodley Date: 9/17/93

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degradation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes: no soundings taken  
no soundings taken

## WASTE MANAGEMENT DIVISION

Facility: Juarez Location: South Lyon  
Type of Facility: seamless tube manufacture  
Contact: Donald Combs Phone: ( )

Name/Number: MW-11A Cap. Locked: Yes ☒ No ☐  
Depth: \_\_\_\_\_ Casing Material: PVC  
Diameter: 2" Screen Slot Size: \_\_\_\_\_  
Casing Ht. Above Ground: 22 1/2 ft Screen Length: \_\_\_\_\_  
Top of Casing Elev.: \_\_\_\_\_ Screen Material: \_\_\_\_\_  
Protective Barrier: N Screen Packed: Yes ☐ No ☐  
Concrete Pad: Yes ☐ No ☒ Well Condition: Good  
Elevation of Screened Interval: \_\_\_\_\_ to \_\_\_\_\_  
Location of TOC Survey Mark: None

Samples: 12120

	<u>DNR</u>	<u>FACILITY</u>
Initial Static Water Level:	15.402k	15.489ft.
Method:	electric tape	→
Measured By:	Sharon	Wardner
Stabilized pH:	6.84	7.22
Stabilized Conductance:	2140	1704
Temperature:		12.40

Purge Method: polythene bag Vol. Purged: 5.75 gallons  
 Fate of Purge Water: graduated bucket dumped on ground  
 Recovery Rate: 90% Appearance: slightly set  
 Sampling Method: poly bag Appearance: clear  
 Staff Present: Boyle, Slater, Wooster Date: 9-27-93

Standing Water: Y ~~(N)~~ Frost Heaving: Y ~~(N)~~  
Collision Damage: Y ~~(N)~~ Well Subsidence: Y ~~(N)~~  
Casing Degredation: Y ~~(N)~~ Photograph Taken: Y ~~(N)~~

Additional Notes: \_\_\_\_\_

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Quarney Location: South Lyon  
 Type of Facility: SEAMLESS TUBE MANUFACTURE  
 Contact: DONALD COMFORT Phone: ( )

WELL INFORMATION

Name/Number: MW-13A Cap Locked: Yes ☒ No ☐  
 Depth: 21.5 Casing Material: PVC  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground: 23' Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier:  Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☐ No ☐ Well Condition:   
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark: no reference mark on rim

WWES measure at  
 base on outer casing

SAMPLING INFORMATION

Sample taken 8:42

WWES staff  
 Jim Wooster

DNR

FACILITY

Initial Static Water Level:  
 Method:  
 Measured By:  
 Stabilized pH:  
 Stabilized Conductance:  
 Temperature:

11.19	11.20
electric meter	electric meter
Stacy	Jim W
6.35	11.50 6.84
1650	13.12
	11.40

Purge Method: polythene bailer Vol. Purged: 5 gal.  
 Fate of Purge Water: bucket dumped on ground  
 Recovery Rate: good Appearance: cloudy grayish  
 Sampling Method: polythene bailer Appearance: clear  
 Staff Present: STAYTON LOSELLE Date: 9-27-93

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes: MW-13B 14.68' static

MW-13C 13.23' static

no bounding of well taken

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

Q & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Funex Location: South Lyon  
 Type of Facility: Seamless tube manufacturer  
 Contact: Donald Comfort Phone: ( )

WELL INFORMATION

Name/Number: MW-17A Cap Locked: Yes ☒ No ☐  
 Depth: 23.2 Casing Material: PVC  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground: 38 Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier: Yes Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition:   
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark: None

SAMPLING INFORMATION Sampled: 11:10

	DNR	FACILITY
Initial Static Water Level:	<u>12.64 ft</u>	<u>12.66 ft</u>
Method:	<u>electric meter</u>	<u>electric meter</u>
Measured By:	<u>Slattery</u>	<u>J. Wooten</u>
Stabilized pH:	<u>6.86</u>	<u>6.94</u>
Stabilized Conductance:	<u>133C</u>	<u>1156</u>
Temperature:	<u></u>	<u>12.40</u>

Purge Method: Polyethylene Vol. Purged: 5 1/2 gallons  
 Fate of Purge Water: graduated bucket dumped on ground  
 Recovery Rate:  Appearance: light  
 Sampling Method: Poly bottle Appearance: clear  
 Staff Present: Slattery/Wooten Date: 9-27-93

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes: Depth 23.2 ft



MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Quonex Location: South Lyon  
 Type of Facility: seamless tube manufacture  
 Contact: Donald Compton Phone: ( )

WELL INFORMATION

Name/Number: MW-17B Cap. Locked: Yes ☒ No ☐  
 Depth: 74 1/2' Casing Material: PVC  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground: 23ft Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier: yes Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☐ No ☒ Well Condition:   
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark: none

SAMPLING INFORMATION Sampled: 11:50

	DNR	FACILITY
Initial Static Water Level:	<u>15.22ft</u>	<u>15.23ft</u>
Method:	<u>electric tape</u>	<u>electric tape</u>
Measured By:	<u>Slayton</u>	<u>Wooten</u>
Stabilized pH:	<u>6.90</u>	<u>7.11</u>
Stabilized Conductance:	<u>790</u>	<u>727</u>
Temperature:	<u></u>	<u>11.80</u>

Purge Method: polyethylene tubing Vol. Purged: 30 1/2 gallons  
 Fate of Purge Water: graduated bucket dumped on ground  
 Recovery Rate:  Appearance: clear  
 Sampling Method: poly bucket Appearance: clear  
 Staff Present: 1 Slayton / Wooten Date: 9-27-93

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes: 74 1/2 ft depth

*Groundwater Contour Map*

O&M INSPECTION  
QUANEX CORPORATION  
MID 082 767 591

---

GROUNDWATER CONTOUR MAP

---

Groundwater elevations were measured by both the consultant (WWES) and the MDNR. The static water levels measured were in good agreement, and are listed below.


STATIC WATER LEVELS MEASURED 9/27/93 (feet)

Well ID.	Top of Casing	Michigan DNR	WWES	Michigan DNR GW Elevation
MW-1A	921.54	12.66	12.61	908.88
MW-1C	921.58	14.19	14.19	907.39
MW-11A	921.00	15.40	15.45	905.60
MW-13A	920.52	11.19	11.20	909.33
MW-17A	921.80	12.64	12.66	909.16
MW-17B	922.32	15.22	15.25	907.10

These groundwater elevations are similar to those measured on December 10, 1993, by WW Engineering & Science (WWES). Since the static water level measurements by the consultant are acceptable, groundwater contour maps presented in the Annual Groundwater Report for 1993 are included to show the site groundwater flow direction.

The upper and lower portion of the glacial drift aquifer have different groundwater flow directions. The upper part of this unconfined aquifer flows south/southwest, while the lower portion flows westerly. Both directions are consistent with historic data.





Annual 1993 Monitoring Summary Report  
Feb. 28, 1994

WW Engineering & Science

FIGURE 1  
SHALLOW WELLS  
GROUND WATER CONTOUR MAP  
(MEASUREMENTS MADE 12-10-93)  
QUANEX CORPORATION  
MICHIGAN SEAMLESS TUBE DIVISION  
SOUTH LYON, MICHIGAN  
FEBRUARY, 1994

SOW-DEE  
LVP02.034

20515.01

## *Additional Reviews*

O&M INSPECTION  
QUANEX CORPORATION  
MID 082 767 591

---

GROUNDWATER QUALITY - STIFF/PIPER DIAGRAMS

---

GROUNDWATER QUALITY

The primary focus of the split sampling was upgradient wells. The intent was to sample some of these newer wells and to confirm arsenic concentrations in the upgradient aquifer. Monitor wells MW-1A (shallow), MW-1C (deep), MW-17A (shallow), and MW-17B (deep) are upgradient. Wells MW-11A and MW-13A are adjacent to the surface impoundments.

Arsenic concentrations in the upgradient wells range from <0.001 to 0.0148 mg/l. Arsenic in the two downgradient wells that the MDNR split sampled were 0.003 and 0.0037 mg/l. Zinc was detected in upgradient well MW-1A at 0.340 mg/l while all others were less than 0.05 mg/l.


The arsenic concentrations in the four upgradient wells sampled were found to be consistent with the data set used for establishing background between August 1991 and June 1992. In 1993, only well MW-6A was found to have statistically significant concentrations of arsenic higher than the background. This well is not adjacent to the surface impoundment, and the arsenic is attributed to other sources since wells next to the impoundments do not show significant levels of arsenic.

STIFF/PIPER DIAGRAMS

Analysis of the major ions was done using Stiff and Piper diagrams, along with Pie charts and bar graphs. These analyses show that the four upgradient wells sampled are similar in general chemistry. The two downgradient wells that are adjacent to the surface impoundments do show an impact. Well MW-11A has a relatively higher concentration of sulfate in the MDNR sample, while MW-13A has a higher concentration of bicarbonate. This can be seen for example on Figure 2, the Piper diagram where wells labeled "2" (MW-11A) and "3" (MW-13A) plot in areas away from the other wells.

# Piper Diagram

#	Date YYMMDD	Zone	Well I.D.
1	930827	1, 3, 5	MW1C
2	930827	1, 3, 5	MW17B




1993 Quenex OSH



# Piper Diagram

#	Date YYMMDD	Zone	Well I.D.
1	930827	1, 4, 9	MW1A
2	930827	1, 4, 6	MW11A
3	930827	1, 3, 5	MW13A
4	930827	1, 4, 9	MW17A




1993 Quanex O&H

# Stiff Diagram

Cations

meq

Anions



930827 MW1C

930827 MW17B

1993 Quenex OSM

MDNR - WASTE MANAGEMENT DIVISION


Figure : 3

Cations

meq

# Stiff Diagram


Anions




1993 Quenex O&M

0 100 500  
 Scale of Radii  
 Area of  
 circle  
 indicates  
 concentration  
 in mg/l

Pie Diagram




930827 MW1C




930827 MW17B

# Pie Diagram


0 100 500 1000  
 Scale of Radii  
 Area of  
 circle  
 indicates  
 concentration  
 in mg/l




930827 MW1A



930827 MW11A



930827 MW13A



930827 MW17A

Cations

Bar Diagram

Anions

Na+K

Ca

Mg

Cl

SO<sub>4</sub>

CO<sub>3</sub>+HCO<sub>3</sub>




FIG. 7

Cations

Bar Diagram

Anions



Na+K



Ca



Mg




Cl



SO4



CO3+HCO3



1993 Guenex O&M

MDNR - WASTE MANAGEMENT DIVISION

Figure : 8

# DATA COMPARISON: QUANEX VS MDNR

Inorganics (ppm)	MW-1A		MW-1C		MW-11A		MW-13A		MW-17A		MW-17B	
	Quanex	MDNR	Quanex	MDNR	Quanex	MDNR	Quanex	MDNR	Quanex	MDNR	Quanex	MDNR
Chloride	106	101	116	107	172	156	20	17	187	275	59	58
Diss. Arsenic	0.0012	<.001	<.001	0.0103	0.0025	0.003	0.0045	0.0037	0.0062	0.0068	0.016	0.0148
Diss. Cadmium	<.010	<.020	<.010	<.020	<.010	<.020	<.010	<.020	<.010	<.020	<.010	<.020
Diss. Chromium	<.050	<.025	<.050	<.025	<.050	<.025	<.050	<.025	<.050	<.025	<.050	<.025
Diss. Copper	<.010	<.020	<.010	<.020	<.010	<.020	<.010	<.020	<.010	<.020	<.010	<.020
Diss. Iron	5	5	2.43	2.3	2.03	1.8	10	9.8	1.9	1.9	2.07	1.7
Diss. Manganese	0.31	0.27	0.047	0.038	0.49	0.47	0.72	0.65	0.28	0.24	0.027	0.028
Diss. Lead	<.050	<.050	<.050	<.050	<.050	<.050	<.050	<.050	<.050	<.050	<.050	<.050
Sulfate	124	114	57	47	755	676	30	53	150	148	47	41
Organics (ppb)												
Dichloroethane(1,1)	<1	<1	<1	<1	5.4	17	<1	<1	<1	1.4	<1	<1

The MDNR data for 1,1-Dichloroethane in MW-11A and MW-17A are estimated values; the value may not be accurate

The data comparison shows very good correlation between the two laboratories for all wells and all parameters. Two of the parameters chloride and sulfate remain above recently calculated Type B standards. The following wells exceed the Type B criteria:

Parameter	Well	Concentration(ppm)	Type B Level(ppm)
Chloride	17A	275 (MDNR)	250 aesthetic value
Sulfate	11A	755 (QUANEX)	250 aesthetic value
	11A	676 (MDNR)	250 aesthetic value



# *Summary Letter*

STATE OF MICHIGAN



NATURAL RESOURCES  
COMMISSION

JERRY C. BARTNIK  
LARRY DEVUYST  
PAUL EISELE  
JAMES HILL  
DAVID HOLLI  
JOEY M. SPANO  
JORDAN B. TATTER

JOHN ENGLER, Governor

DEPARTMENT OF NATURAL RESOURCES

John Hannah Building, P.O. Box 30241, Lansing, MI 48909

ROLAND HARMES, Director

March 23, 1994

Mr. Donald Comfort  
Engineering Manager  
Quanex Corporation  
400 McMunn  
South Lyon, Michigan 48178

Dear Mr. Comfort:

Subject: Quanex 1993 O&M Report  
MID 082 767 591

An O&M inspection has been conducted at the Quanex Corporation, of South Lyon. The inspection included a field audit and split sampling of groundwater (September 27, 1993), O&M checklist, sampling and analysis inspection, monitor well data sheets, groundwater contour map, stiff\piper\pie diagram, and data comparison.

The latest sampling and analysis plan for groundwater monitoring is located within the Groundwater Quality Assessment Program dated April of 1986. This was then approved with revisions on May 20, 1992 by the Michigan Department of Natural Resources.

The attachment to this memo lists one area of concern identified during the field inspection on September 27, 1993. The concern was that depth or sounding measurements were not taken for some of the wells. It is common for sediments to accumulate at the bottom of the well thus changing the depths of the well and the amount of water evacuated for purging. It is therefore, good practice to take depth measurements at each sampling event.

If there are any questions, please contact the number listed below or Mr. David Slayton at 517-373-8012.

Sincerely,

*JAN SEALOCK*

Jan Sealock  
Environmental Quality Analyst  
Waste Management Division  
517-373-4740

cc/enc: Ms. De Montgomery/U.S. EPA Reporting  
Mr. Ben Okwumabua, DNR-Livonia  
Mr. Dave Slayton, DNR  
HWP/C&E File



**ATTACHMENT**

Quanex Corporation  
MID 082 767 591  
O&M Inspection-1993

- 1). Depth or sounding measurements were not taken at some of the wells. This measurement should be taken at each sampling event. [Area of Concern].

NATURAL RESOURCES  
COMMISSION

JERRY C. BARTNIK  
LARRY DEVUYST  
PAUL EISELE  
JAMES HILL  
DAVID HOLLI  
JOEY M. SPANO  
JORDAN B. TATTER

STATE OF MICHIGAN



JOHN ENGLER, Governor

DEPARTMENT OF NATURAL RESOURCES

John Hannah Building, P.O. Box 30241, Lansing, MI 48909

ROLAND HARMES, Director

RECEIVED

SEP 8 1993

OFFICE OF RCRA  
WASTE MANAGEMENT DIV  
EPA, REGION 1

September 2, 1993

RECEIVED  
WMD RCRA  
RECORD CENTER  
SEP 14 1993  
*Compliance*

Mr. Donald Comfort  
Engineering Manager  
Quanex Corporation  
400 McMunn  
South Lyon, Michigan 48178

Dear Mr. Comfort:

SUBJECT: O&M Inspection  
Quanex Corporation  
MID 082 767 591

The Michigan Department of Natural Resources (Department) will be visiting Quanex Corporation on September 27, 1993 to conduct an Operation and Maintenance Inspection (O&M) of your groundwater monitoring system(s).

The O&M is an inspection which the Department conducts to follow up on the Comprehensive Monitoring Evaluation (CME) previously performed at your facility. Whereas the CME inspection was performed to evaluate the technical adequacy of your groundwater monitoring system(s), the O&M inspection is designed to evaluate the performance, operation, and maintenance of this system(s). The basis for the Department's review can be found in 1979 P.A. 64, as amended (Act 64), Part 10, Rule 299.11003(n), which references Part 265 Subpart F of the Resource Conservation and Recovery Act (RCRA), or the environmental monitoring requirements contained in your current Act 64 operating license.

Prior to visiting the site, staff will be reviewing your Sampling and Analysis Plan (SAP) so that they can determine in the field whether your on-site sampling methods comply with the groundwater sampling and handling procedures specified in your SAP and/or permit. In order for our office to accurately perform this pre-inspection review, Waste Management Division (WMD) staff will contact you by telephone to verify whether we have a current copy of your SAP. If we find during that conversation that the WMD does not have one, you will need to submit a copy of your current SAP by September 22, 1993 to:

Jan Sealock  
Michigan Department of Natural Resources  
Waste Management Division



Corporation  
Seamless Tube Division  
Livonia, Michigan 48173



Michigan Seamless  
Tube Division

RECEIVED

April 12, 1991

APR 15 1991

Waste Management  
Division

Mr. Christopher L. Silva  
Michigan Department of Natural Resources  
S.E. Michigan District Headquarters  
Waste Management Division  
38980 Seven Mile Road  
Livonia, MI 48152

CERTIFIED MAIL - P 066 446-676

RE: QUANEX CORPORATION - MID 082 767 591  
RESPONSE TO O&M INSPECTION LETTER

RECEIVED  
JUL 14 1991  
OFFICE OF RCRA  
Waste Management Division  
U.S. EPA, REGION V

Dear Mr. Silva:

The purpose of this letter is to address the issues raised by the MDNR's O&M Inspection at our plant on December 20, 1990. Your letter to me of March 12, 1991, which discusses the results of that inspection, divides the MDNR's concerns into three categories; this response addresses each category in turn.

First, your letter requested five specific changes to the sampling and analysis plan. In cooperation with the MDNR, Quanex is providing revised pages for insertion into the plan which, as requested, thoroughly document the current monitoring procedures. One copy of the revised pages are included in Attachment 1. These pages address all of the issues raised by the MDNR and should replace the current pages as described on the yellow cover sheet.

Nonetheless, Quanex does not believe that the absence of this additional information represents any violation of 40 CFR 265.92(a) or any portions of Michigan Act 64. The monitoring plan was approved by the Environmental Protection Agency in a letter from Mr. William Munro to me dated September 4, 1986. We note that the cited sections of 40 CFR 265.92(a) do not specify that the requested information be included. In accordance with the applicable regulations, the existing plan "included procedures and techniques for (1) sample collection; (2) sample preservation and shipment; (3) analytical procedures; and (4) chain-of-custody control." [40 CFR 265.92(a)]. Moreover, contrary to the O&M inspection report, the MDNR did not send us a post-inspection report notifying us of these "deficiencies" in connection with the 1988 CME. Thus, we object to the MDNR's characterization of the existing plan provisions as being in "violation" of the relevant regulations.

Second, your March 12 letter requested a proposal for additional information to support the claim that the low concentrations of arsenic observed

Outline used to check Sampling &  
Analysis Plan

### SAMPLING AND ANALYSIS PLAN OUTLINE

- Locations sampled (include on a site map)
- Sampling frequency/schedule
- Parameters to be analyzed (based on an evaluation of the materials handled, and considering breakdown products)
- Sampling equipment
  - Method of operation
  - Compatibility with parameters to be analyzed
- Field measured parameters
  - Method(s) used
  - Calibration method and schedule
- Decontamination procedures
- Sample Handling
  - Containers used
  - Special precautions (volatiles, bactis, etc.)
  - Preservation techniques
  - Filtering procedures (where applicable)
- Sample Analysis
  - Identify laboratory(s) used
  - Analytical methods
    - Method reference
    - Holding time
    - Detection limit
- Quality Assurance/Quality Control Programs (QA/QC)
  - Field
    - Duplicate samples
    - Blanks - Trip
      - Air
      - Equipment
  - Laboratory
    - Spikes
    - Standards
    - Duplicates
- Chain of custody procedures
  - Sample labels
  - Field log
  - Sample shipment
  - Chain of custody form
- Static water levels
  - Measurement point
  - Measurement method
  - Level of accuracy
- Well purging
  - Purge volume determination calculations
  - Purge volume measurement
  - Fate of purge water
  - Purge method
- Sampling
  - Time elapsed after purging
  - Sampling method (suitability with parameters to be analyzed)
- Statistical evaluation

STATE OF MICHIGAN

ERA

NATURAL RESOURCES COMMISSION

THOMAS J. ANDERSON  
MARLENE J. FLUHARTY  
KERRY KAMMER  
O. STEWART MYERS  
DAVID D. OLSON  
RAYMOND POUPORE



JOHN ENGLER, ~~XXXXXXXXXXXX~~, Governor

DEPARTMENT OF NATURAL RESOURCES

DAVID F. HALES, Director

S.E. MICHIGAN DISTRICT HEADQUARTERS  
Waste Management Division  
38980 Seven Mile Road  
Livonia, MI 48152

March 12, 1991

Mr. Donald Comfort  
Quanex Corporation  
400 McMunn  
South Lyon, MI 48178

Dear Mr. Comfort:

RE: Quanex Corporation, MID 082 767 591, O&M Inspection

On December 20, 1990, an O&M Inspection was completed by Dave Slayton and Jan Sealock, Geotechnical Support Unit, Waste Management Division. The report is enclosed with this letter. A summary memo in the report, dated February 27, 1991 details the attached listing of conclusions and violations.

Violations of the groundwater monitoring program have been found with the operation and reporting of this monitoring system pursuant to Act 64 P.A. 1979, as amended, Part 10, Rule 299.11003 referencing Part 265 Subpart F of RCRA. The groundwater monitoring program at Quanex Corporation should continue on a quarterly basis.


Additional information is contained within the enclosed O&M Report. You are requested to respond by thirty (30) days from the date of this memo.

Page 2 of 2, 03/12/91  
D. Comfort, MID 082 767 591

A copy of your response is also to be sent to Jan Sealock, Waste Management Division, Department of Natural Resources, P.O. Box 30241, Lansing, MI 48909.

If you have any questions, please contact me at (313)-953-0241, (313)-953-1457, or Jan Sealock at (517)-373- 4630.

Sincerely,

A handwritten signature in cursive script that reads "Christopher L. Silva".

Christopher L. Silva  
Environmental Quality Analyst

CS/cs  
Enclosure: O&M Report  
Attachment  
cc: B. Okwumabua  
Jan Sealock  
C&E File  
U.S. EPA, Region V



ATTACHMENT

Quanex Corporation  
MID 082 767 591  
O&M Inspection for 12/20/90


1. The sampling and analysis plan (April 1986, Groundwater Quality Assessment Program) must be updated to include the following items:
  - a) Detection limits for all required parameters. [Violation - 40 CFR 265.92(a)(3)]
  - b) Laboratory QA/QC procedures (spikes, duplicates, standards). [Violation - 265.92(a)(3)]
  - c) Specify purge method, fate of purged water, how purge volume is calculated. [Violation - 265.92(a)(1)]
  - d) Specify correct analytical methods for dissolved oxygen, nitrate-nitrite, and organic carbon.
  - e) Inspection of well casing, protective casing, surface pad, and lock during routine sampling events. Provisions to repair any damage must be included. [Area of concern]
2. The company must supply additional data supporting its claim that the arsenic detected in some wells is naturally occurring. The company must submit a proposal within ninety (90) days for additional well(s) and sampling. The proposal in the 1990 Annual Groundwater report is not adequate (see discussion in text of O&M writeup). The proposal must address the following: [Area of concern - 265.93(d)(4)(i)]
  - a) Installation of a new deep well at MW-1.
  - b) Sampling of deep wells 12C and 13C.
  - c) Explanation of different top of casing elevations.
  - d) Analysis of vertical gradients to geochemistry.
3. The 1,1 dichloroethane contamination must be addressed. The most obvious vehicle is to address this contaminant through the HSWA process. EPA has already started the RFA. The 1,1 dichloroethane found in low levels in wells 11A and 11B may be related to a SWMU found directly under the southern part of the RCRA impoundments. Another source may also be present at the site because well 6A has shown consistently higher levels, and this well is located farther away from the impoundments. The RFI to be eventually conducted under HSWA must include addressing the 1,1 dichloroethane. [Area of concern]

# *Operation and Maintenance Inspection*

---

*Conducted By  
Waste Management Division  
Michigan Department of Natural Resources*

## BASE MAP OF QUANEX MONITOR WELLS



STATE OF MICHIGAN

NATURAL RESOURCES COMMISSION

THOMAS J. ANDERSON  
MARLENE J. FLUHARTY  
GORDON E. GUYER  
KERRY KAMMER  
ELLWOOD A. MATTSO  
O. STEWART MYERS  
RAYMOND POUPORE



JAMES J. BLANCHARD, Governor

DEPARTMENT OF NATURAL RESOURCES

STEVENS T. MASON BUILDING  
P.O. BOX 30028  
LANSING, MI 48909

DAVID F. HALES, Director

November 30, 1990

Mr. Donald Comfort  
Quanex Corporation  
400 McMunn  
South Lyons, Michigan 48178

Dear Mr. Comfort:

SUBJECT: Quanex Corporation, MID 082 767 591

The Michigan Department of Natural Resources will be visiting Quanex Corporation on December 20, 1990, to conduct an Operation and Maintenance Inspection of your groundwater monitoring system(s).

In follow-up to the Comprehensive Monitoring Evaluation (CME) previously conducted at your facility, which evaluated site hydrogeology and the design adequacy of your groundwater monitoring system, the Operating and Maintenance Inspection or OMI will focus on the performance, operation and maintenance of this system pursuant to act 64 P.A. 1979, as amended, Part 10, Rule 299.11003(n) referencing Part 265, Subpart F of the Resource Conservation and Recovery Act (RCRA) or part of your current Act 64 operating license. The OMI will include the following compliance determinations:

1. A Sampling Inspection and Sampling and Analysis Plan review to verify physical integrity of individual wells and sampling equipment, proper collection of groundwater samples to ensure that sampling and handling procedures as outlined in the S/A plan and/or permit conditions are being followed. The sampling inspection shall include a split sampling of selected wells and collection of groundwater elevation data for establishing groundwater flow directions. This is planned for 12/20/90.
2. A review and evaluation of all data records including recent and previous hydrogeologic information for determination of the continued viability of your facility's groundwater monitoring system.

**QUANEX CORPORATION**

SOUTH LYONS, MICHIGAN

MID 082 767 591

**OPERATION AND MAINTENANCE INSPECTION**

Field Inspection Guide

Sampling and Analysis Inspection

Monitor Well Data Sheets

Groundwater Contour Map

Additional Reviews

1. Total versus Dissolved Metals  
Data Comparison
2. Stiff\Piper\Pie Diagrams
3. 1990 Annual Groundwater Report  
Review

Summary Letter and EPA Reporting Forms

**Evaluated By:**

Dave Slayton  
Jan Sealock

February 27, 1991

*Field Inspection Guide*  
*Checklist*

# **APPENDIX B**

## **Part Two**

### **Field Inspection Guide**

## PART TWO

The field inspector will complete four tasks during the field inspection. They are:

1) review the operating record to identify evidence of deficiencies in the owner/operator's sampling and/or operation and maintenance programs; 2) visually inspect each well and piezometer for evidence of damage or deterioration; 3) obtain measurements from the operations record of depths of water levels and well depths for each well and piezometer; and 4) visually observe the owner/operator's field crew as they collect ground-water samples.

Name of inspector(s) Jane Sealock

Date(s) of inspection 12/20/90

1. Review the operating record of the facility. Does the operating record:	Y/N
Include annual reports of ground-water monitoring results including ground-water level data from each well and piezometer in the monitoring system?	Y
Include an inventory of all sampling devices and purging equipment in use at the facility and information on model number, serial number and manufacturers name?	Y - Not in Plan with EPC 2 Record
Include detailed operating, calibration and maintenance procedures for each sampling device?	Y
Describe decision criteria to be used to replace or repair sampling equipment and/or monitoring wells?	Y
Include schedules for performing operation and maintenance activities related to the ground-water monitoring system?	Y Quarterly Tubers Sampling Well
Include records for ground-water monitoring which provide information on 1) the date, exact place and time of sampling or measurements; 2) the individual(s) who performed the sampling or measurements; 3) the date(s) analyses were performed; 4) the analytical techniques or methods used; and 5) the results of such analyses?	Y
Include records of all monitoring information including all calibration and maintenance records?	Y
Include records of monitoring information including determination of ground-water surface elevations?	Y
Include a determination of ground-water flow rate and direction(s) in the uppermost aquifer on an annual basis (e.g., prepare a potentiometric map annually using data collected during the year)?	Y
Provide for more frequent and intensive inspection of wells constructed of non-inert casing such as PVC? (Refer to Appendix A for permit example.)	N - Quarterly when Sampling Wells



2. Visually inspect each well and piezometer and complete the table below (one line entry for each well or piezometer):

Well/ Piezometer	Survey Mark Present?	Standing or Ponded Water?	Evidence of Collision Damage?	Evidence of Frost Heaving?	Evidence of Casing De- gradation?	Lock in Place?	Evidence of Well Sub- sidence?	Photograph Taken?
MW 11A	N	N	N	N	N	Y	N	N
MW 11B	N	N	N	N	N	Y	N	N
MW 11D	N	N	N	N	N	Y	N	N
MW 13A	N	N	N	N	N	Y	N	N
MW 13B	N	N	N	N	Y	Y	N	N
MW 1	N	N	N	N	N	Y	N	N

4. Observe the owner/operator's staff as they collect ground-water samples at several wells. Complete the following table for each well (Note: revise or add to the table if permit conditions dictate a different requirement the owner/operator must follow):

Position/Title	Name	Sampling Experience (years and type)
Field Services Supervisor	Bob Thomas	4 yrs. exp. - Soil, Water, Wastewater Exp.
Field Services Technician	Jim Wooster	2 yrs. exp. - Soil, Water, Wastewater Exp.

Well Identification Number <u>MW's 11A, 11B, 11D, 13A, 13B, MW 1</u>	Y/N	Photograph Taken Y/N
Did the sampling crew measure static water levels in the well and well depths prior to the sampling event?	Yes	No
Did the sampling crew use a steel tape or electronic device to take depth measurements?	Yes	No
Did the sampling crew record depths to +/- 0.01 feet?	Yes	No
Did the sampling crew follow these procedures: 1. remove locking and protective cap; 2. sample the air in the well head for organic vapors; -NO 3. determine the static water level; and 4. lower an interface probe into the well to detect immiscible layers. -NO	Yes	No
If immiscible samples were collected, were they collected prior to well purging?	NA	No
Did the sampling crew evacuate low yielding wells to dryness prior to sampling?	Yes	No
Did sampling crew evacuate high yielding wells so that at least three casing volumes were removed?	Yes	No
Did the sampling crew collect the purge water for storage and analysis or for shipment off-site to a RCRA treatment facility?	No	No
Were sampling devices constructed of fluorocarbon resins or stainless steel? Teflon Baller	Yes	No

(Continued)

Well Identification Number <u>MW3 - 11A, 11B, 11D, 13A,</u> <u>13B, MW1</u>	Y/N	Photograph Taken Y/N
Were samples taken from the bladder pump discharge tube, and not from any purge device discharge tube?	NA	N
Was the bladder pump discharge flow checked for the presence of gas bubbles before each sample collection, as a test for bladder integrity?	NA	N
Was bladder pump flow performance monitored regularly for dropoff in flow rate and discharge volume per cycle?	NA	N
Was the bladder pump incorporated in a combination sample-purge pump design which can expose the bladder pump interior and discharge tubing to the pump drive gas? If so, were operating procedures established and followed to prevent at all times the entry of drive gas into the sample flow or into the bladder pump interior?	NA	N
Did the sampling crew collect and containerize samples in the order of the volatilization sensitivity of the parameters?	Yes	N
Did the sampling crew measure the following parameters in the field: pH, temperature, specific conductance?	Yes	N
Did the sampling crew sample background wells before sampling downgradient wells?	No	N
Did the sampling crew use fluorocarbon resin or polyethylene containers with polypropylene caps for samples requiring metals analysis?	Yes	N
Did the sampling crew use glass bottles with fluorocarbon resin-lined caps for samples requiring metals analysis?	No	N
If metals were the analytes of concern, did the sampling crew use containers cleaned with nonphosphate detergent and water, and rinsed with nitric acid, tap water, hydrochloric acid, tap water and finally Type II water?	NA	N
If organics were the analytes of concern, did the sampling crew use containers cleaned with nonphosphate detergent, rinsed with tap water, distilled water, acetone, and finally pesticide quality hexane?	No	N
Did the sampling crew filter samples requiring analysis for organics?	No	N

After working through Part Two, the field inspector will have:

- assessed whether the owner/operator's sampling crew departed from written sampling and analysis procedures as contained in the owner/operator's sampling and analysis plan (interim status) or in the owner/operator's RCRA permit (permit status);
- identified deficiencies in the way the owner/operator's sampling crew collected ground-water samples;
- identified deficiencies in the owner/operator's program to ensure on-going maintenance of sampling devices and monitoring wells/piezometers;
- identified deficiencies in the owner/operator's operating record (Does the operating record have all the information in it that is required?); and
- collected field data that will allow the enforcement official to construct potentiometric maps and assess the viability of individual wells.

*Sampling and Analysis*  
*Inspection*

**Sampling and Analysis Inspection**  
**Quanex Corporation**  
**MID 082 767 591**

On December 20th, 1990, a sampling inspection was conducted at the Quanex Corporation as part of an Operational and Maintenance Inspection (O&M). The latest Sampling and Analysis Plan (SAP), is dated April, 1986. This plan is kept on-site. It has been determined that this plan must be updated with the deficiencies outlined in this report.

Consultants Jim Wooster and Bob Thomas from WW Engineering and Science (WWES) of Livonia were involved in the split sampling. Static water level measurements were conducted using an electric meter by both the MDNR and WWES. All measurements were taken to the nearest .01th of a foot to be used in the making of groundwater contour maps. Static water level measurements and purging were conducted on December 20th by WWES, the samples were collected directly after purging. For decontamination purposes, WWES rinsed the electric meter with an ample amount of deionized water between wells. All wells were in good condition. There was, however, some casing degradation found at well 13B. This should be inspected periodically for further deterioration. The revised SAP should incorporate the inspection of the monitoring system during each sampling event so that problems can be identified and rectified.

A teflon bailer was utilized to purge the wells. Purge volumes on the 20th were based on three times the casing water volume, or until the well ran dry. The evacuated water was discharged to a graduated 5 gallon bucket for accurate volume determination. This volume was disposed away from the well, preventing infiltration into the casing and the immediate groundwater sampling point. WWES followed good safety protocol by wearing gloves while collecting samples from the wells.

The teflon bailer was also used to collect the water samples that day. All bailers were cleaned and decontaminated before sampling began. There was one bailer for each well so no decontamination was done at the site. New nylon rope was tied to each bailer before sampling. Those samples collected for volatiles were poured slowly from the bailer to reduce aeration of the sample. Samples were stored in appropriate bottles for analysis. The samples were immediately transferred to coolers filled with ice.

Both field parameters of pH and specific conductivity were

taken by WWES and the MDNR. Both meters were calibrated before use, also the pH meter was checked before each well with a buffer. An equipment blank and a field blank were both taken as part of field QA\QC protocol.

The most recent Sampling and Analysis Plan (SAP) is a Groundwater Quality Assessment Program received by the MDNR was an April, 1986 document submitted by EDI Engineering and Science. A number of areas are incorporated in the plan, however, some areas were deficient. All deficiencies listed below were deficiencies listed in the Comprehensive Monitoring Evaluation (CME) done in 1988. These deficiencies will be listed as violations. No information was provided in the plan on detection limits, laboratory QA\QC such as spikes, standards, or duplicates. No information was provided on the purge method utilized, fate of purge water and purge water volume determination calculations. The method references for some parameters appear to be in error. The Standard Methods reference should be 421, not 412 for dissolved oxygen. Nitrate-nitrite should be method 353 for reference 3, not 201. Reference 3 method 415 should be cited for organic carbon, not 236. These changes must be added to the Groundwater Quality Assessment Program. This concludes the sampling and analysis portion of the O&M inspection.

MICHIGAN DEPARTMENT OF NATURAL RESOURCES  
WASTE MANAGEMENT DIVISION  
Water Sampling Data Sheet

FACILITY: Quarver LOCATION: South Lyons  
CONTACT: Bob Comfort PHONE: (313) 486-0100

Sample #	11A	11B	11D	13A	13G	Max 1	FB
Date	12/20/90	12/20/90	12/20/90	12/20/90	12/20/90	12/20/90	12/20/90
Time	10:30	11:00	11:35	12:05	12:20	12:45	1:17
pH (field)							
Conductivity (field)	1600	1710	1010	1715	1560	1310	
Temperature (°C) (field)							
TDS (field)							
PO 1	✓	✓	✓	✓	✓	✓	✓
PO 2	✓	✓	✓	✓	✓	✓	✓
ON 3							
OB GC/MS B/N							
OA 8							
OG oil & grease	<del>N/A</del>	<del>N/A</del>	<del>N/A</del>			<del>N/A</del>	<del>N/A</del>
MA/D Basic 6/Fe	✓	✓	✓	✓	✓	✓	✓
Ca/Mg/Na/K							
Hg/As/Se/Sb							
MN Cl/SO <sub>4</sub> /Alk	✓	✓	✓	✓	✓	✓	✓
HCO <sub>3</sub> /CO <sub>3</sub>							
Fluoride/Cr <sup>6</sup>							
GA COD/TOC							
NO <sub>3</sub> /NO <sub>2</sub> /NH <sub>3</sub>							
Kjel N/TotP							
GG Phenols							
GB Total/Free Cn							
Sample Appearance	Light Brown Silty Brown	Clear	Silty Brown	Clear	Clear	Clear	Clear

Additional Notes:

\* All samples Filtered at least twice.



MICHIGAN DEPARTMENT OF NATURAL RESOURCES  
ENVIRONMENTAL LABORATORY

REPORT Waste Management Division  
TO Ottawa Building  
Lansing, MI 48909

ATTEN JAN SEALOCK

LABORATORY WORK ORDER # 90-12-073

WORK ID QUANEX - SOUTH LYON

P.O. # 60026

COST \$ 1523.50

RECEIVED 12/20/90

CLIENT WM

REPORTED

NUMBER OF SAMPLES 7

LAB CONTACT OR IN

MATRIX WATER

TEST	MW-11A	MW-11B	MW-11D	MW-13A
UNITS				
Alkalinity of Water	156	170	284	517
mg CaCO3/l				
Carbonate Alkalinity	K 5	K 5	K 5	K 5
mg CaCO3/l				
Bicarbonate Alkalinity	156	170	284	517
mg CaCO3/l				
Arsenic by Furnace	20	7.8		
ug/l				
Barium in Water	86	52		
ug/l				
Calcium in Water	325	373		
mg/l				
Cadmium in Water	K 20	K 20		
ug/l				
Chloride in Water	99	121	64	51
mg/l				
Chromium in Water	K 50	K 50		
ug/l				
Copper in Water	K 20	K 20		
ug/l				
Arsenic by Furnace - Diss.	5.2	3.9	5.5	3.0
ug/l (Diss)				
Barium - Dissolved	59	20	126	306
ug/l (Diss)				
Calcium - Dissolved	313	339	142	342
mg/l (Diss)				
Cadmium - Dissolved	K 20	K 20	K 20	K 20
ug/l (Diss)				
Chromium - Dissolved	K 50	K 50	K 50	K 50
ug/l (Diss)				
Copper - Dissolved	K 20	K 20	K 20	K 20
ug/l (Diss)				
Iron - Dissolved	5300	4600	3000	10000
ug/l (Diss)				
Potassium - Dissolved	11	6.7	2.45	6.1
mg/l (Diss)				
Magnesium - Dissolved	32.9	40.2	36	52
mg/l (Diss)				

RECEIVED

JAN 31 1991

Waste Management  
Division

Page 3  
Received: 12/20/90

DNR Laboratory  
01/29/91 10:51:51

REPORT

Work Order # 90-12-073  
Continued From Above

TEST	UNITS	MW-13B	MW-1	FIELD BLANK
Cadmium in Water	ug/l		K 20	
Chloride in Water	mg/l	142	81	K 1
Chromium in Water	ug/l		K 50	
Copper in Water	ug/l		K 20	
Arsenic by Furnace - Diss.	ug/l (Diss)	4.8	K 1.0	K 1.0
Barium - Dissolved	ug/l (Diss)	27	27	K 10
Calcium - Dissolved	mg/l (Diss)	312	272	K 1
Cadmium - Dissolved	ug/l (Diss)	K 20	K 20	K 20
Chromium - Dissolved	ug/l (Diss)	K 50	K 50	K 50
Copper - Dissolved	ug/l (Diss)	K 20	K 20	K 20
Iron - Dissolved	ug/l (Diss)	6850	4800	K 100
Potassium - Dissolved	mg/l (Diss)	4.8	5.6	K .1
Magnesium - Dissolved	mg/l (Diss)	45	19	K 1
Manganese - Dissolved	ug/l (Diss)	250	535	K 20
Sodium - Dissolved	mg/l (Diss)	92.7	57.5	K 1
Nickel - Dissolved	ug/l (Diss)	K 50	K 50	K 50
Lead - Dissolved	ug/l (Diss)	K 50	K 50	K 50
Zinc - Dissolved	ug/l (Diss)	K 50	1100	K 50
Iron in Water	ug/l		11700	
Potassium in Water	mg/l		5.9	
Magnesium in Water	mg/l		20.8	
Manganese in Water	ug/l		595	
Sodium in Water	mg/l		59.8	

Page 5  
Received: 12/20/90

DNR Laboratory REPORT  
Results by Sample

Work Order # 90-12-073

SAMPLE ID MW-11A FRACTION 01A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 12/20/90 Category \_\_\_\_\_

ANALYST WILFORD  
ANALYZED 12/27/90  
DILUTION 1

UNITS ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION
				LIMIT
75-01-4	Vinyl chloride	ND		5.0
74-83-9	*Bromomethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-69-4	*Trichlorofluoromethane	ND		5.0
75-35-4	1,1-Dichloroethene	ND		1.0
75-09-2	Methylene chloride	ND		5.0
156-60-5	trans-1,2-Dichloroethene	ND		1.0
75-34-3	1,1-Dichloroethane	3.2	UC	1.0
156-59-2	cis-1,2-Dichloroethene	ND		1.0
67-66-3	Chloroform	ND		1.0
71-55-6	1,1,1-Trichloroethane	ND		1.0
56-23-5	Carbon tetrachloride	ND		1.0
107-06-2	1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethene	ND		1.0
78-87-5	1,2-Dichloropropane	ND		1.0
75-27-4	Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	1,1,2-Trichloroethane	ND		1.0
127-18-4	Tetrachloroethene	ND		1.0
124-48-1	Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		1.0
75-25-2	Bromoform	ND		1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 7  
Received: 12/20/90

DNR Laboratory REPORT  
Results by Sample

Work Order # 90-12-073

SAMPLE ID MW-11B FRACTION 02A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 12/20/90 Category \_\_\_\_\_

ANALYST WILFORD  
ANALYZED 12/27/90  
DILUTION 1

		UNITS <u>ug/L ppb</u>			DETECTION
<u>CAS#</u>	<u>COMPOUND</u>	<u>RESULT</u>	<u>REMARK</u>	<u>LIMIT</u>	
75-01-4	Vinyl chloride	ND		5.0	
74-83-9	*Bromomethane	ND		5.0	
75-00-3	*Chloroethane	ND		5.0	
75-69-4	*Trichlorofluoromethane	ND		5.0	
75-35-4	1,1-Dichloroethene	ND		1.0	
75-09-2	Methylene chloride	ND		5.0	
156-60-5	trans-1,2-Dichloroethene	ND		1.0	
75-34-3	1,1-Dichloroethane	3.2	UC	1.0	
156-59-2	cis-1,2-Dichloroethene	ND		1.0	
67-66-3	Chloroform	ND		1.0	
71-55-6	1,1,1-Trichloroethane	ND		1.0	
56-23-5	Carbon tetrachloride	ND		1.0	
107-06-2	1,2-Dichloroethane	ND		1.0	
79-01-6	Trichloroethene	ND		1.0	
78-87-5	1,2-Dichloropropane	ND		1.0	
75-27-4	Bromodichloromethane	ND		1.0	
10061-01-5	cis-1,3-Dichloropropene	ND		1.0	
10061-02-6	trans-1,3-Dichloropropene	ND		1.0	
79-00-5	1,1,2-Trichloroethane	ND		1.0	
127-18-4	Tetrachloroethene	ND		1.0	
124-48-1	Dibromochloromethane	ND		1.0	
108-90-7	Chlorobenzene	ND		1.0	
75-25-2	Bromoform	ND		1.0	
79-34-5	1,1,2,2-Tetrachloroethane	ND		1.0	

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Received: 12/20/90

Results by Sample

SAMPLE ID MW-110 FRACTION Q3A TEST CODE SC 1 NAME Scan 1 Water  
 Date & Time Collected 12/20/90 Category \_\_\_\_\_

ANALYST WILFORDANALYZED 12/27/90DILUTION 1UNITS ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION
				LIMIT
75-01-4	Vinyl chloride	ND		5.0
74-83-9	*Bromomethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-69-4	*Trichlorofluoroethane	ND		5.0
75-35-4	1,1-Dichloroethene	ND		1.0
75-09-2	Methylene chloride	ND		5.0
156-60-5	trans-1,2-Dichloroethene	ND		1.0
75-34-3	1,1-Dichloroethane	ND		1.0
156-59-2	cis-1,2-Dichloroethene	ND		1.0
67-66-3	Chloroform	ND		1.0
71-55-6	1,1,1-Trichloroethane	ND		1.0
56-23-5	Carbon tetrachloride	ND		1.0
107-06-2	1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethene	ND		1.0
78-87-5	1,2-Dichloropropane	ND		1.0
75-27-4	Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	1,1,2-Trichloroethane	ND		1.0
127-18-4	Tetrachloroethene	ND		1.0
124-48-1	Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		1.0
75-25-2	Bromoform	ND		1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.

\* Compound identity not confirmed by second independent technique.

Page 11  
Received: 12/20/90

DNR Laboratory  
Results by Sample

REPORT

Work Order # 90-12-073

SAMPLE ID MW-13A FRACTION 04A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 12/20/90 Category

ANALYST WILFORD  
ANALYZED 12/27/90  
DILUTION 1

UNITS ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION LIMIT
75-01-4	Vinyl chloride	ND		5.0
74-83-9	*Bromomethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-69-4	*Trichlorofluoromethane	ND		5.0
75-35-4	1,1-Dichloroethene	ND		1.0
75-09-2	Methylene chloride	ND		5.0
156-60-5	trans-1,2-Dichloroethene	ND		1.0
75-34-3	1,1-Dichloroethane	ND		1.0
156-59-2	cis-1,2-Dichloroethene	ND		1.0
67-66-3	Chloroform	ND		1.0
71-55-6	1,1,1-Trichloroethane	ND		1.0
56-23-5	Carbon tetrachloride	ND		1.0
107-06-2	1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethene	ND		1.0
78-87-5	1,2-Dichloropropane	ND		1.0
75-27-4	Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	1,1,2-Trichloroethane	ND		1.0
127-18-4	Tetrachloroethene	ND		1.0
124-48-1	Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		1.0
75-25-2	Bromoform	ND		1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 13  
Received: 12/20/90

DNR Laboratory REPORT  
Results by Sample

Work Order # 90-12-073

SAMPLE ID MW-13B FRACTION 05A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 12/20/90 Category

ANALYST WILFORD  
ANALYZED 12/28/90  
DILUTION 1

		UNITS <u>ug/L ppb</u>			DETECTION
CASE#	COMPOUND	RESULT	REMARK		LIMIT
75-01-4	Vinyl chloride	ND			5.0
74-83-9	*Bromomethane	ND			5.0
75-00-3	*Chloroethane	ND			5.0
75-69-4	*Trichlorofluoromethane	ND			5.0
75-35-4	1,1-Dichloroethene	ND			1.0
75-09-2	Methylene chloride	ND			5.0
156-60-5	trans-1,2-Dichloroethene	ND			1.0
75-34-3	1,1-Dichloroethane	ND			1.0
156-59-2	cis-1,2-Dichloroethene	ND			1.0
67-66-3	Chloroform	ND			1.0
71-55-6	1,1,1-Trichloroethane	ND			1.0
56-23-5	Carbon tetrachloride	ND			1.0
107-06-2	1,2-Dichloroethane	ND			1.0
79-01-6	Trichloroethene	ND			1.0
78-87-5	1,2-Dichloropropane	ND			1.0
75-27-4	Bromodichloromethane	ND			1.0
10061-01-5	cis-1,3-Dichloropropene	ND			1.0
10061-02-6	trans-1,3-Dichloropropene	ND			1.0
79-00-5	1,1,2-Trichloroethane	ND			1.0
127-18-4	Tetrachloroethene	ND			1.0
124-48-1	Dibromochloromethane	ND			1.0
108-90-7	Chlorobenzene	ND			1.0
75-25-2	Bromoform	ND			1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND			1.0

COMMENTS

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 15  
Received: 12/20/90

DNR Laboratory  
Results by Sample

REPORT

Work Order # 90-12-073

SAMPLE ID MW-1 FRACTION 06A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 12/20/90 Category

ANALYST WILFORD  
ANALYZED 12/28/90  
DILUTION 1

		UNITS <u>ug/L ppb</u>			DETECTION
<u>CAS#</u>	<u>COMPOUND</u>	<u>RESULT</u>	<u>REMARK</u>	<u>LIMIT</u>	
75-01-4	Vinyl chloride	ND		5.0	
74-83-9	*Bromomethane	ND		5.0	
75-00-3	*Chloroethane	ND		5.0	
75-69-4	*Trichlorofluoromethane	ND		5.0	
75-35-4	1,1-Dichloroethene	ND		1.0	
75-09-2	Methylene chloride	ND		5.0	
156-60-5	trans-1,2-Dichloroethene	ND		1.0	
75-34-3	1,1-Dichloroethane	ND		1.0	
156-59-2	cis-1,2-Dichloroethene	ND		1.0	
67-66-3	Chloroform	ND		1.0	
71-55-6	1,1,1-Trichloroethane	ND		1.0	
56-23-5	Carbon tetrachloride	ND		1.0	
107-06-2	1,2-Dichloroethane	ND		1.0	
79-01-6	Trichloroethene	ND		1.0	
78-87-5	1,2-Dichloropropane	ND		1.0	
75-27-4	Bromodichloromethane	ND		1.0	
10061-01-5	cis-1,3-Dichloropropene	ND		1.0	
10061-02-6	trans-1,3-Dichloropropene	ND		1.0	
79-00-5	1,1,2-Trichloroethane	ND		1.0	
127-18-4	Tetrachloroethene	ND		1.0	
124-48-1	Dibromochloromethane	ND		1.0	
108-90-7	Chlorobenzene	ND		1.0	
75-25-2	Bromoform	ND		1.0	
79-34-5	1,1,2,2-Tetrachloroethane	ND		1.0	

COMMENTS

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.



Page 17  
Received: 12/20/90

DNR Laboratory REPORT  
Results by Sample

Work Order # 90-12-073

SAMPLE ID FIELD BLANK FRACTION 07A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 12/20/90 Category \_\_\_\_\_

ANALYST WILFORD  
ANALYZED 12/28/90  
DILUTION 1

		UNITS <u>ug/L ppb</u>		DETECTION
<u>CAS#</u>	<u>COMPOUND</u>	<u>RESULT</u>	<u>REMARK</u>	<u>LIMIT</u>
75-01-4	Vinyl chloride	ND		5.0
74-83-9	*Bromomethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-69-4	*Trichlorofluoromethane	ND		5.0
75-35-4	1,1-Dichloroethene	ND		1.0
75-09-2	Methylene chloride	ND		5.0
156-60-5	trans-1,2-Dichloroethene	ND		1.0
75-34-3	1,1-Dichloroethane	ND		1.0
156-59-2	cis-1,2-Dichloroethene	ND		1.0
67-66-3	Chloroform	ND		1.0
71-55-6	1,1,1-Trichloroethane	ND		1.0
56-23-5	Carbon tetrachloride	ND		1.0
107-06-2	1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethene	ND		1.0
78-87-5	1,2-Dichloropropane	ND		1.0
75-27-4	Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	1,1,2-Trichloroethane	ND		1.0
127-18-4	Tetrachloroethene	ND		1.0
124-48-1	Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		1.0
75-25-2	Bromoform	ND		1.0
79-34-5	1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS \_\_\_\_\_

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Quawser Corp. South Lyon, MI MID 082:767 591

Parameter	Sampled 12/20/90							Field Blank
in ppm / mg/L	MW-11A	MW-11B	MW-11D	MW-13A	MW-13B	MW-1		
Inorganics								
Alkalinity	156	170	284	517	216	169	<10	
Carbonate	<5	<5	<5	<5	<5	<5	<5	
Bicarbonate	156	170	284	517	216	169	<10	
Arsenic	.020	.0078				.0056		
Diss Arsenic	.0052	.0039	.0055	.0030	.0048	<.0010	<.0010	
Barium	.086	.052				.052		
Calcium	325	373				277		
Diss Calcium	313	339	142	342	312	272	<1.0	
Cadmium	<.020	<.020				<.020		
Diss Cadmium	<.020	<.020	<.020	<.020	<.020	<.020	<.020	
Chloride	99	121	64	51	142	81	<1.0	
Chromium	<.050	<.050				<.050		
Diss Chromium	<.050	<.050	<.050	<.050	<.050	<.050	<.050	
Copper	<.020	<.020				<.020		
Diss Copper	<.020	<.020	<.020	<.020	<.020	<.020	<.020	
Diss Barium	.059	.020	.126	.306	.027	.027	<.010	
Iron	12.9	12.3				11.7		
Diss Iron	5.3	4.6	3.0	10.0	6.85	4.8	<.100	
Potassium	11.2	7.2				5.9		
Diss Potassium	11.0	6.7	2.45	6.1	4.8	5.6	<.10	
Lithium	35	48				20.8		
Diss Magnesium	32.9	40.2	36	52	45	19	<1.0	
Manganese	.680	.545				.595		
Diss Manganese	.680	.390	.050	.765	.250	.535	<.020	
Sodium	77	70.6				59.8		
Diss Sodium	75.4	69.2	18	49.6	92.7	57.5	<1.0	
Nickel	<.050	<.050				<.050		
Diss Nickel	<.050	<.050	<.050	<.050	<.050	<.050	<.050	
Lead	<.050	<.050				<.050		
Diss Lead	<.050	<.050	<.050	<.050	<.050	<.050	<.050	
Sulfate	832	873	177	624	759	629	<2	
Zinc	<.050	<.050				23.0		
Diss Zinc	.078	.061	<.050	1.50	<.050	1.1	<.050	
ORGANICS								
ug/L PPB								

1,1-Dichloroethane	3.2 UC*	3.2 UC*	<1.0	<1.0	<1.0	<1.0	<1.0
the Scan 1 & 2 Parameters*	<Detection	<Detection	<Detection	<Detection	<Detection	<Detection	<Detection

\* UC=No attempt has been made to confirm the identity of the reported compound by a second independent technique due to equipment or sample problems.

\* A list of Scan 1 & Scan 2 detection limits is provided with this report.

# SCAN 1 - PURGEABLE HALOCARBONS

<u>COMPOUND</u>	<u>DETECTION LIMIT (ug/l)</u>
Vinyl chloride	5.0
Bromomethane*	5.0
Chloroethane*	5.0
Trichlorofluoromethane*	5.0
1,1-Dichloroethene	1.0
Methylene chloride*	5.0
trans-1,2-Dichloroethene	1.0
1,1-Dichloroethane	1.0
cis-1,2-Dichloroethene	1.0
Chloroform*	1.0
1,1,1-Trichloroethane*	1.0
Carbon tetrachloride*	1.0
1,2-Dichloroethane*	1.0
Trichloroethene	1.0
1,2-Dichloropropane*	1.0
Bromodichloromethane*	1.0
cis-1,3-Dichloropropene	1.0
trans-1,3-Dichloropropene	1.0
1,1,2-Trichloroethane*	1.0
Tetrachloroethene	1.0
Dibromochloromethane*	1.0
Chlorobenzene	5.0
Bromoform*	1.0
1,1,2,2-Tetrachloroethane*	1.0

\* Compound not confirmed by second independent technique.

# SCAN 2 - PURGEABLE AROMATIC HYDROCARBONS

<u>COMPOUND</u>	<u>DETECTION LIMIT (ug/l)</u>
Benzene	1.0
Toluene	1.0
Ethylbenzene	1.0
Xylene isomers	1.0

EL 070

5/90

MATRIX = WATER

## MICHIGAN DEPT OF NATURAL RESOURCES

ENVIRONMENTAL LABORATORY

ANALYSIS REQUEST SHEET

\*\*\*\* SAFETY WARNING \*\*\*\*

YES / (NO) - INFO ON BACK

LAB ORDER# 9012073 PROJ CODE \_\_\_\_\_ PRIORITY II RECEIVED AT LAB BY M DATE TIME 12/20/90 1530 AM PM  
 SUBMITTER DISTRICT Central CONTACT PERSON PHONE  
 DIVISION WMD OR OFFICE Lansing FOR QUESTIONS Jan Seabock (517) - 373-4740

LOCATION COLLECTED BY Seabock/Skayton TRANS TO \_\_\_\_\_  
 SAMPLED Quanex, South Lyon

COST SEND RESULTS TO ATTENTION OF Jan Seabock AT ADDRESS S. Ottawa Bldg  
 CENTER 60026 (if different than above office) WMD/ONR

SAMPLE REMARKS groundwater Lansing

SAMPLE NUMBER	FIELD ID OR DESCRIPTION (25 Characters)	SAMPLE COLLECTED		SAMPLE INFORMATION
		YY/MM/DD	HH:MM	

01	MW-11A	901220	10:30	gw - monitor well
02	MW-11B	901220	11:00	"
03	MW-11D	901220	11:35	"
04	MW-13A	901220	12:05	"
05	MW-13B	901220	12:20	"

## GENERAL CHEMISTRY

## ORGANICS

## INORGANIC

DO Diss Oxygen ... 1 2 3 4 5	PO1 #1 Halocarbons 1 2 3 4 5	MA Total Metals ... 1 2 3 4 5
GN NO2, o-Phos ... 1 2 3 4 5	PO2 #2 Aromatic HC 1 2 3 4 5	MAD Diss-Field Filtered .. 1 2 3 4 5
Residue SS .... 1 2 3 4 5	DN #3 Chloro HC + Pest & PCB . 1 2 3 4 5	MD Diss-Lab Filtered .... 1 2 3 4 5
Residue TDS ... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Ca Mg Na K ... 1 2 3 4 5
BOD Tot 5 day 1 2 3 4 5	OA #8 Phenols .... 1 2 3 4 5	Cd Cr Cu Ni Pb Zn ... 1 2 3 4 5
BOD Carb 5 day 1 2 3 4 5	OB Oil & Grease .. 1 2 3 4 5	Fe Co Li Mn ... 1 2 3 4 5
CA Chlorophyll ... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Al Ba Be Mo Ti V ... 1 2 3 4 5
GA COD ... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Hg - Mercury ... 1 2 3 4 5
TOC ... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Se - Selenium ... 1 2 3 4 5
NO3+NO2, NH3 .. 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Sb - Antimony ... 1 2 3 4 5
KJEL N, Tot P . 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	LOW LEVEL Ag ... 1 2 3 4 5
GG Phenolics .... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	As ... 1 2 3 4 5
GB Total CN ..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Cd ... 1 2 3 4 5
Free CN ..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Cr Cu Ni Pb .. 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Zn Fe ..... 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	MN pH, Conductance ..... 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Cl, SO4, Total Alk ... 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	HCO3- CO3= ... 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	CR+6 ..... 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Fluoride ..... 1 2 3 4 5
..... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	..... 1 2 3 4 5

\* If samples are already past holding time or close to holding time when submitted, than initial to indicate that you will accept "ht" coded results.

EL 070

5/90

MATRIX = WATER

## MICHIGAN DEPT OF NATURAL RESOURCES

## ENVIRONMENTAL LABORATORY

## ANALYSIS REQUEST SHEET

#### SAFETY WARNING ####

YES ☒ NO ☐ INFO ON BACK

LAB ORDER# 9012073 PROJ CODE \_\_\_\_\_ PRIORITY II RECEIVED AT LAB BY ML DATE TIME 12/20/90 1530 AM PM

SUBMITTER DISTRICT Central CONTACT PERSON PHONE (517) 373-4740  
DIVISION WMD OR OFFICE Lansing FOR QUESTIONS Jan Seabolt

LOCATION Quarar, South Lyon COLLECTED BY Seabolt/Skyton TRANS TO \_\_\_\_\_

COST 60026 SEND RESULTS TO ATTENTION OF Jan Seabolt AT ADDRESS S. Ottawa Bldg  
(if different than above office) WMD / ONR

SAMPLE REMARKS groundwater

ISAMPLE NUMBER	FIELD ID OR DESCRIPTION (25 Characters)	SAMPLE COLLECTED YY/MM/DD HH:MM	SAMPLE INFORMATION
----------------	---	---------------------------------	--------------------

06	MW-1	901220 12:48	gww - monitor well
----	------	--------------	--------------------

07	FB	901220 1:17	Field blank
----	----	-------------	-------------

03			
----	--	--	--

04			
----	--	--	--

05			
----	--	--	--

## GENERAL CHEMISTRY

## ORGANICS

## INORGANIC

DO Diss Oxygen ... 1 2 3 4 5	PO1 #1 Halocarbons 1 2 3 4 5	MA Total Metals ... 1 2 3 4 5
GN NO2, o-Phos ... 1 2 3 4 5	PO2 #2 Aromatic HC 1 2 3 4 5	MAD Diss-Field Filtered ... 1 2 3 4 5
Residue SS ... 1 2 3 4 5	ON #3 Chloro HC + Pest & PCB 1 2 3 4 5	MD Diss-Lab Filtered ... 1 2 3 4 5
Residue TDS ... 1 2 3 4 5	OB GC/MS Base Neut 1 2 3 4 5	Ca Mg Na K ... 1 2 3 4 5
BOD Tot 5 day 1 2 3 4 5	OA #8 Phenols ... 1 2 3 4 5	Cd Cr Cu Ni Pb Zn ... 1 2 3 4 5
BOD Carb 5 day 1 2 3 4 5	OG Oil & Grease .. 1 2 3 4 5	Fe Co Li Mn ... 1 2 3 4 5
CA Chlorophyll ... 1 2 3 4 5		Al Ba Be Mo Ti V ... 1 2 3 4 5
GA COD ... 1 2 3 4 5		Hg - Mercury ... 1 2 3 4 5
TOC ... 1 2 3 4 5		Se - Selenium ... 1 2 3 4 5
NO3+NO2, NH3 .. 1 2 3 4 5		Sb - Antimony ... 1 2 3 4 5
KJEL N, Tot P . 1 2 3 4 5		LOW LEVEL Ag ... 1 2 3 4 5
66 Phenolics .... 1 2 3 4 5		* AS ... 1 2 3 4 5
68 Total CN ..... 1 2 3 4 5		* Cd ... 1 2 3 4 5
Free CN ..... 1 2 3 4 5		* Cr Cu Ni Pb .. 1 2 3 4 5
		* Zn Fe ..... 1 2 3 4 5
		MN pH, Conductance ..... 1 2 3 4 5
		Cl, SO4, Total Alk .... 1 2 3 4 5
		HCO3- CO3= ..... 1 2 3 4 5
		CR+6 ..... 1 2 3 4 5
		Fluoride ..... 1 2 3 4 5

\* If samples are already past holding time or close to holding time when submitted, than initial to indicate that you will accept "ht" coded results.

# *Monitor Well Data Sheets*

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Quanex Location: South Lyons  
 Type of Facility: Land Disposal  
 Contact: Dan Comfoot Phone: (313) 486-0100

WELL INFORMATION

Name/Number: MW 11A Cap Locked: Yes ☒ No ☐  
 Depth: 27.25' Casing Material: PVC  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground:  Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier:  Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition: Good  
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark:

SAMPLING INFORMATION

	DNR	FACILITY
Initial Static Water Level:	<u>14.58'</u>	<u>14.56'</u>
Method:	<u>Electric Meter</u>	<u>Electric Meter</u>
Measured By:	<u>Dan S</u>	<u>Bob Thomas</u>
Stabilized pH:	<u></u>	<u>6.87</u>
Stabilized Conductance:	<u>11600</u>	<u>1884</u>
Temperature:	<u></u>	<u>9.34</u>

Purge Method: Teflon Bailor Vol. Purged: 6.25 gallons to purge  
 Fate of Purge Water: Scaven Bucket Away from well  
 Recovery Rate: Good Appearance: Light Brown Color  
 Sampling Method: Teflon Bailor Appearance: Light Brown  
 Staff Present: Jim Sealock, Dave Snyder Date: 12/20/90

Standing Water: Y/N Frost Heaving: Y/N  
 Collision Damage: Y/N Well Subsidence: Y/N  
 Casing Degredation: Y/N Photograph Taken: Y/N

Additional Notes: Jim Wooster Bob Thomas Nylon Rope  
Teflon Bailor used to sample wells. pH & Conductivity taken,  
Calibrations done before sampling. Also bailer reading before  
well. Equipment blank and field blank taken.  
Bailers are precleaned before sampling and rinsed before use.

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Quaker Location: South Lyons MI  
 Type of Facility: Land Disposal  
 Contact: Don Comfort Phone: (313) 486-0100

WELL INFORMATION

Name/Number: 11B Cap Locked: Yes ☒ No ☐  
 Depth: 36.5 Casing Material: o/c  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground: 25' Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier:  Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition: good  
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark:

SAMPLING INFORMATION

	DNR	FACILITY
Initial Static Water Level:	<u>15.01'</u>	<u>15.00'</u>
Method:	<u>barometer</u>	<u>Electronic</u>
Measured By:	<u>John R.</u>	<u>Bob Thomas</u>
Stabilized pH:	<u></u>	<u>6.97</u>
Stabilized Conductance:	<u>1710</u>	<u>1987</u>
Temperature:	<u></u>	<u>10.9°C</u>

Purge Method: air bailer Vol. Purged: 10.5  
 Fate of Purge Water: disposal  
 Recovery Rate: good Appearance: Silty Brown  
 Sampling Method: bottom bailer Appearance: Silty Brown  
 Staff Present: John Seibert Date: 12/20/90

Standing Water: Y/N Frost Heaving: Y/N  
 Collision Damage: Y/N Well Subsidence: Y/N  
 Casing Degredation: Y/N Photograph Taken: Y/N

Additional Notes: Bob - 4 hrs Exp - Field Services Supervisor  
Jim - 2 1/2 hrs Exp - Field Services Tech  
Filter was in the field. Different Nylon Rope used on the wells

277711 CW 11/12 16/12 (8")



MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Crooner Location: South Lucas MI  
 Type of Facility: Landfill  
 Contact: Don Comfort Phone: (313) 486-0100

WELL INFORMATION

Name/Number: MW 11D Cap Locked: Yes ☒ No ☐  
 Depth: 72.8 Casing Material: PVC  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground:  Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier:  Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition: Good  
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark:

SAMPLING INFORMATION

	DNR	FACILITY
Initial Static Water Level:	<u>14.87'</u>	<u>14.88'</u>
Method:	<u>Electric Meter</u>	<u>Electric Meter</u>
Measured By:	<u>Don Slayton</u>	<u>Bob Thomas</u>
Stabilized pH:	<u></u>	<u>6.73</u>
Stabilized Conductance:	<u>400</u>	<u>1030</u>
Temperature:	<u></u>	<u>11.6</u>

Purge Method: Teflon Bailor Vol. Purged: 28.5 gal  
 Fate of Purge Water: 5 gallon Bucket away from well  
 Recovery Rate: Good Appearance: Silty somewhat clear  
 Sampling Method: Teflon Bailor Appearance: Clear  
 Staff Present: Don Slayton, Don Simpson Date: 12/20/90

Standing Water: Y/N Frost Heaving: Y/N  
 Collision Damage: Y/N Well Subsidence: Y/N  
 Casing Degredation: Y/N Photograph Taken: Y/N

Additional Notes: Sampling for Metals, Organics & General  
Chemistry Parameters

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

Q & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Quarries Location: South Haven, MI  
 Type of Facility: Land Disposal  
 Contact: Don Comfort Phone: (313) 486-0100

WELL INFORMATION

Name/Number: 13 A Cap Locked: Yes ☒ No ☐  
 Depth: 21.7' Casing Material: PVC  
 Diameter: 2" Screen Slot Size:           
 Casing Ht. Above Ground:          Screen Length:           
 Top of Casing Elev.:          Screen Material:           
 Protective Barrier:          Screen Packed: Yes ☐ No ☒  
 Concrete Pad: Yes ☐ No ☒ Well Condition: Good  
 Elevation of Screened Interval:          to           
 Location of TOC Survey Mark:         

SAMPLING INFORMATION

	DNR	FACILITY
Initial Static Water Level:	10.30'	10.34'
Method:	Electric Meter	Electric Meter
Measured By:	Jan Seidel	Bob Thomas
Stabilized pH:	6.65	6.65
Stabilized Conductance:	175 $\mu$ S/cm	196 $\mu$ S/cm
Temperature:	16.4°C	16.4

Purge Method: Teflon Bailor Vol. Purged: 55 G.L.  
 Fate of Purge Water: 5 gallon bucket away from well  
 Recovery Rate: Good Appearance: Silty Brown  
 Sampling Method: Teflon Bailor Appearance: Silty Brown  
 Staff Present: Jan Seidel, Dave Gaylor Date: 12/20/90

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes:

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

O & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Granex Location: South Lyon, MI  
 Type of Facility: Land Disposal  
 Contact: Don Comfort Phone: (313) 486-0100

WELL INFORMATION

Name/Number: 13 B Cap Locked: Yes ☒ No ☐  
 Depth: 52' Casing Material: PVC  
 Diameter: 2" Screen Slot Size: \_\_\_\_\_  
 Casing Ht. Above Ground: \_\_\_\_\_ Screen Length: \_\_\_\_\_  
 Top of Casing Elev.: \_\_\_\_\_ Screen Material: \_\_\_\_\_  
 Protective Barrier: \_\_\_\_\_ Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☒ Well Condition: Good  
 Elevation of Screened Interval: \_\_\_\_\_ to \_\_\_\_\_  
 Location of TOC Survey Mark: \_\_\_\_\_

SAMPLING INFORMATION

13C  
12.65'

	DNR	FACILITY
Initial Static Water Level:	13.84'	13.34'
Method:	Electric Meter	Electric Meter
Measured By:	Tom Sealock	Bob Thomas
Stabilized pH:	7.88	
Stabilized Conductance:	1999	
Temperature:	10.9°C	

Purge Method: Teflon Bailer Vol. Purged: 17.25  
 Fate of Purge Water: Discharged to sewer away from well  
 Recovery Rate: Good Appearance: Clear  
 Sampling Method: Teflon Bailer Appearance: Clear  
 Staff Present: Tom Sealock, Jane Singleton Date: 12/20/90

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐  
Sealock and Tom

Additional Notes: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

WASTE MANAGEMENT DIVISION

Q & M MONITOR WELL & GROUND WATER DATA SHEET

Facility: Quamex Location: South Lyons, MI  
 Type of Facility: LAND DISPOSAL  
 Contact: Don Comfort Phone: (313) 486-0100

Bob Thomas  
 Jim Wooster

WELL INFORMATION

Name/Number: MW 1 Cap Locked: Yes ☒ No ☐  
 Depth: 19.40' Casing Material: Galvanized Steel  
 Diameter: 2" Screen Slot Size:   
 Casing Ht. Above Ground:  Screen Length:   
 Top of Casing Elev.:  Screen Material:   
 Protective Barrier:  Screen Packed: Yes ☐ No ☐  
 Concrete Pad: Yes ☒ No ☐ Well Condition: Good - New casing put in  
 Elevation of Screened Interval:  to   
 Location of TOC Survey Mark:

SAMPLING INFORMATION

	DNR	FACILITY
Initial Static Water Level:	<u>12.04'</u>	<u>11.98'</u>
Method:	<u>Electric Meter</u>	<u>Electric Meter</u>
Measured By:	<u>Don Slayton</u>	<u>Bob Thomas</u>
Stabilized pH:	<u></u>	<u>6.98</u>
Stabilized Conductance:	<u>1310</u>	<u>1575</u>
Temperature:	<u></u>	<u>10.1</u>

Purge Method: Teflon Bailor Vol. Purged: 4 gallons  
 Fate of Purge Water: 5 gal. Put away from well  
 Recovery Rate: Good Appearance: Silty Brown  
 Sampling Method: Teflon Bailor Appearance: clear  
 Staff Present: Tom Sealeck, Don Slayton Date: 12/20/90

Standing Water: Y ☒ N ☐ Frost Heaving: Y ☒ N ☐  
 Collision Damage: Y ☒ N ☐ Well Subsidence: Y ☒ N ☐  
 Casing Degredation: Y ☒ N ☐ Photograph Taken: Y ☒ N ☐

Additional Notes:

# *Groundwater Contour Map*

# QUANEX O&M INSPECTION

2/27/91

## GROUNDWATER FLOW

---

Groundwater flow direction has remained virtually unchanged at this site since records have been kept (about 1984). The attached groundwater contour map is based on data from shallow monitoring wells. The data was obtained by the consultant for Quanex on 12/20/90. Shallow groundwater flow in the vicinity of the RCRA impoundments is toward the southwest, with a turn toward the west in the vicinity of wells MW-15 and MW-16. The map was done with a contouring program on a personal computer. The contour map was compared with a hand drawn map to confirm.

In addition, there are multiple well clusters available at this site. Groundwater flow in the mid-level monitoring wells (11B, 12B, 13B, 15B, 16B) based on a hand contour map was also found to be toward the west-southwest. For the deepest wells (12C, 13C, 11D), the groundwater flow direction is nearly due west for the December 1990 Quanex data. Attached is a groundwater contour map for the mid-level wells (B wells) from the 1990 Annual Groundwater Report (WWES).

The relative groundwater elevations found in all the wells during the December 1990 sampling are very similar to historic measurements. In fact, groundwater contour maps contained in the Groundwater Quality Assessment Program done by EDI Engineering & Science in April 1986 in figures 16, 17, and 18 are almost identical to the groundwater flow found in recent samplings. The exception is that there is less mounding now around the impoundments because they are no longer in use.

The Assessment Program report referenced in the preceding paragraph also contains an excellent discussion of site geology. The higher groundwater levels in the north and northeast part of the site seem to be controlled by an underlying silt/clay/sand unit. This lower permeability unit is found only in the northeast part of the site under a 20-25 foot thick sand and gravel unit. Groundwater over this unit has a higher elevation than areas to the south and southwest where there is a much thicker sequence of sand and gravel. See figures 7 through 14, and figure 16 for cross-sections and maps related to geology and groundwater flow.

Vertical gradients are well documented at this site because of the excellent system of well clusters found here. Vertical gradients are important in relation to the question of whether the low levels of arsenic detected in some wells comes from the impoundments or is naturally occurring deeper in the aquifer. Although there are variations, most wells clusters show a downward gradient from the shallowest well ("A") to the next deeper one ("B") for wells 11, 12, 13, 15, 16. For well clusters with a deep well ("C"), there is an


upward gradient from the deepest (C) to the mid-level (B) well (MW 12, 13). For well cluster 11, there are four wells at various depths. There is a downward gradient from shallow (A) to mid (B and C), and usually an upward gradient from the deepest (D) to the "C" well. There is a question however regarding the top of casing elevation. For example, for well 11D, the Groundwater Assessment Report (4/86) listed the TOC elevation as 921.07, the 1988 Annual GW report has 920.77, and the 1990 Annual GW report lists 921.77. The overall difference of 1.0 feet can make a large difference in the interpretation of vertical gradients.

The vertical gradient question is important regarding the source of the arsenic and 1,1 dichloroethane found in wells 11A and 11B, and the arsenic found occasionally in wells 11D, 12B, 13A, 13B, and 14A. It is possible that the arsenic may have come from the impoundments because arsenic is detected in well 11A on some occasions, and in 11B consistently. There is a consistent downward gradient from 11A to 11B. Arsenic was also detected consistently in well 14A until its removal. Wells 11A, 13A, and 14A are shallow.

Other evidence however points to the arsenic possibly being naturally occurring deeper in the aquifer, perhaps related to the silt/clay/sand unit. For example, arsenic has not been detected in well 12A, but is consistently found in well 12B. There is a downward gradient from 12A to 12B, but no arsenic in 12A. There is an upward gradient from 12C to 12B. Well 11D also consistently has detectable arsenic, and there is an upward gradient. For a summary refer to the 1990 Annual Groundwater Report (dated 2/21/91) done by WW Engineering & Science which contains a historic summary of water level data and analytical results. Copies of the arsenic and 1,1 dichloroethane data are included in this section of the O&M report.


There is also another possible source for the 1,1 dichloroethane found in wells 11A and 11B. Soil boring logs and excavation related to closure of the impoundments revealed the existence of a former landfill. The impoundments southern portions are constructed over the landfill, which contains organics as revealed by testing of the landfill waste. Only wells 11A and 11B detect the 1,1 DCEa, while other wells around the impoundments do not. Other wells also detect the 1,1 DCEa, but they are farther from the landfill and impoundments. Well 6A has shown higher levels in the past compared to 11A and 11B. This may be due to an as yet unknown source.

# GROUNDWATER CONTOUR MAP OF SHALLOW WELLS AT QUANEX



STATICS TAKEN ON 12/20/90 BY QUANEX  
CONTOUR INTERVAL: 1 FOOT

SCALE 1 inch = 250 Feet






# 1990 Annual G.W. Report

## Figure 1 Contour of the Intermediate Depth Piezometric Surface (B Wells)

Quanex  
Michigan Seamless Tube Division  
November, 1990 20515.01

### LEGEND


906.08 Elevations from Wells Screened  
between 865' to 890'

 Horizontal Component  
of Groundwater Flow

Based on Water Levels  
Measured on 9/24/90



0 50 100 200  
Horizontal Scale in Feet



## GROUND WATER MONITORING DATA

Ground Water Quality Assessment Plan Monitoring

1990 ANNUAL REPORT (dated 2/21/91)  
 WW Engineering + Science

Arsenic, dissolved (ug/l)

SAMPLED															FIELD		TRIP
FROM -	TO	1	6-A	9	11-A	11-B	11-D	12-A	12-B	13-A	13-B	14-A	15-A	16-A	BLANK	BLANK	
10/17/86		< 2.0			< 2.0	4.2	5.6	< 2.0	5.3	< 2.0	5.2	6.4		< 2.0	< 2.0	< 2.0	
12/22/86						6.3	6.9		16		11	11					
12/22/86						7.8	6.0		15		13	13					
12/22/86						17	5.9		20		16	18					
03/11/87	03/12/87	< 2.0		< 2.0	< 2.0	3.3	4.6	< 2.0	9.5	< 2.0	5.0	9.3		< 2.0	< 2.0	< 2.0	
05/18/87	05/19/87	< 2.0			< 2.0	2.4	5.3	< 2.0	9.3	< 2.0	7.6	8.7		< 2.0	< 2.0		
05/18/87	05/19/87					3.5	5.6		11		6.3	4.8					
05/18/87	05/19/87					4.0	5.4		11		6.6	4.8					
08/18/87	08/19/87	< 2.0			< 2.0	4.9	5.9	< 2.0	9.4	< 2.0	5.9	8.6		< 2.0	< 2.0		
11/12/87		< 2.0			< 2.0	3.7	4.6	< 2.0	9.2	< 2.0	5.6	8.4		< 2.0		< 2.0	
11/12/87						3.5	5.5		9.1		5.4	9.8					
11/12/87						4.2	4.8		8.9		5.2	8.7					
02/10/88		< 2.0			2.1	4.0	6.0	< 2.0	8.0	< 2.0	5.5	6.6		< 2.0	< 2.0	< 2.0	
05/10/88		< 2.0	4.1		5.4	3.9	6.7	< 2.0	6.4	< 2.0	8.5	plugged	< 2.0	< 2.0	< 2.0		
05/10/88					6.4	4.2	8.1		8.0		9.1						
05/10/88					7.7	4.1	10		7.6		9.5						
08/10/88		< 2.0	7.9		< 2.0	4.0	6.7	< 2.0	7.1	< 2.0	5.4		< 2.0	< 2.0	< 2.0		
08/10/88			9.1														
08/10/88			9.2														
11/03/88		< 2.0	13		2.2	2.3	7.5	< 2.0	10	< 2.0	8.5		< 2.0	< 2.0			
11/03/88						< 2.0	5.5		8.6		9.5						
11/03/88						< 2.0	7.3		8.1		8.6						
03/26/90	03/27/90	< 2.0		< 2.0	2.9	5.1	< 2.0	6.7	2.1	4.6			< 2.0	< 2.0	< 2.0	< 2.0	
06/18/90		< 2.0			2.4	4.1	5.4	< 2.0	7.6	< 2.0	4.9		< 2.0	< 2.0	< 2.0	< 2.0	
06/18/90	dup					2.7	5.6		9.0	3.0	4.7						
06/18/90	trip					3.2	6.1		9.8	2.6	5.2						
06/18/90	quad					3.3	5.7		6.8	3.0	4.6						
09/24/90		< 2.0			3.1	3.0	4.1	< 2.0	5.4	3.0	4.6		< 2.0	< 2.0	< 2.0	< 2.0	
09/24/90	dup				3.5												
09/24/90	trip				3.7												
12/20/90		< 2.0			5.3	4.6	6.5	< 2.0	7.7	2.7	5.7		< 2.0	< 2.0	< 2.0	< 2.0	
12/20/90	dup				4.5	4.1	6.4		6.1	4.3	5.6						
12/20/90	trip				3.9	3.5	5.4		6.8	6.2	5.5						

## GROUND WATER MONITORING DATA

1990 ANNUAL REPORT (dated 2/21/91)  
 WW Engineering + Science

## Ground Water Quality Assessment Plan Monitoring

1,1-Dichloroethane (ug/l)

## SAMPLED

FROM - TO	1	6-A	9	11-A	11-B	11-D	12-A	12-B	13-A	13-B	14-A	15-A	16-	FIELD BLANK	TRIP BLANK
10/17/86 (note 1)	< 2			6	6	< 2	< 2								< 2
12/22/86	< 1			3.0	5.1										
12/22/86	< 1			3.4	4.9										
12/22/86				3.6	4.7										
03/11/87 03/12/87	< 1		< 1	< 1	4	< 1	< 1	< 1	< 1	< 1	< 1	< 1	< 1	< 1	< 1
05/18/87 05/19/87	< 1			3.0	2.1	< 1	< 1	< 1	< 1	< 1	< 1	< 1	< 1	< 1	
05/18/87 05/19/87					2.2										
05/18/87 05/19/87					2.3										
08/18/87 08/19/87	< 1			9.9	6.1	< 1	< 1	< 1	< 1	< 1	1.1	< 1	< 1	< 1	
08/18/87 08/19/87				5.2											
08/18/87 08/19/87				4.7											
11/12/87	< 1			4.1	5.3	< 1	< 1	< 1	< 1	< 1	1.2	< 1	< 1	< 1	< 1
11/12/87					5.5						1.4				
11/12/87					5.2						1.1				
02/10/88	< 1		BROKE BTL	3.5	< 1	< 1	< 1	< 1	< 1	< 1	1.2	< 1	< 1	< 1	< 1
02/10/88				1.8											
02/10/88			< 1												
05/10/88	< 1	42		1.0	3.4	< 1	< 1	< 1	< 1	< 1	plugged	< 1	< 1	< 1	
05/10/88					3.5										
05/10/88					3.8										
08/10/88	< 1	42		3.7	3.0	< 1	< 1	< 1	< 1	< 1		< 1	< 1		
08/10/88		58		3.6											
08/10/88		53		3.7											
11/03/88	< 1	70	< 1	4.5	< 1	< 1	< 1	< 1	< 1	< 1		< 1	< 1		
11/03/88				4.5											
11/03/88				4.4											
03/26/90 03/27/90	< 1			2	< 1	< 1	< 1	< 1	< 1	< 1		< 1	< 1	< 1	< 1
06/18/90	< 1			3	3	< 1	< 1	< 1	< 1	< 1		< 1	< 1	< 1	< 1
06/18/90 dup				3											
06/18/90 trip				3											
06/18/90 quad				3											
09/24/90	< 1			2	3	< 1	< 1	< 1	< 1	< 1		< 1	< 1	< 1	< 1
09/24/90 dup					2										
09/24/90 trip					2										
12/20/90	< 1			2	3	< 1	< 1	< 1	< 1	< 1		< 2	< 2	< 2	< 2
12/20/90 dup				3	3										
12/20/90 trip				3	4										

## *Additional Reviews*

QUANEX O&M INSPECTION  
2/27/91  
TOTAL vs DISSOLVED METALS

---

Since there is an ongoing debate as to whether groundwater samples should be filtered or not, samples were taken at three wells for both total metals (not filtered, preserved in the field with acid) and for dissolved metals (field filtered and then preserved). This is also a relevant question since the recent EPA proposal is to deny the delisting petition submitted by Quanex for the liquid portion of its waste. Previously, the sludge from lime stabilization of pickle liquor sludge was delisted. EPA based part of the proposed denial on samples EPA took on 8-26-87 that apparently were not filtered which detected chromium and lead. Historical data from Quanex and from two MDNR samplings have not shown any statistically significant problem that I am aware of with chromium or lead as referenced in the EPA proposed denial (Federal Register, Vol. 55, No 224, Tuesday November 20, 1990). For a recent groundwater data summary, refer to the 1990 Annual Groundwater Report by WW Engineering & Science. Copies of the chromium and lead data are included here.

The three wells where total and dissolved metals Michigan DNR samples were taken are 11A, 11B, and 1 (the upgradient well). For the following metals, all total and dissolved results were non-detect at the detection level in mg/l noted in parenthesis: Cadmium (0.02), Chromium (0.05), Copper (0.02), Nickel (0.05), Lead (0.05).

The data for zinc shows inconsistent results. Two of the three wells had non-detect zinc in the total analysis while having detectable levels in the dissolved (MW-11A, 11B). For well MW-1, the upgradient well, there was zinc detected in the dissolved phase, and very high zinc in the total analysis. It must be noted that the other wells are PVC, while MW-1 has galvanized casing. The elevated zinc in MW-1 is likely related to the casing.

For iron, the data shows that the total analysis had at least twice the amount as the dissolved analysis. This is not surprising since iron is a common metal associated with clay and silt particles. It may be important at this site because arsenic, which is detected in some wells, can be controlled by adsorption on hydrous iron oxide (USGS Water-Supply Paper 2254, Study and Interpretation of the Chemical Characteristics of Natural Water, Third Edition, by Hem). The arsenic may be associated with the high iron content of the groundwater (see attached data on iron).

For arsenic, the total level is higher than the dissolved level in all three wells. In the upgradient well, the dissolved arsenic was non-detect (at 0.001 mg/l). Overall, the data for arsenic, iron, and zinc show that there can be a substantial difference in metals levels depending on how the sample is taken. How much sediment is in the groundwater sample will affect total versus dissolved analysis.

1990 ANNUAL REPORT (dated 2/21/91)  
 WW Engineering + Science

GROUND WATER MONITORING DATA

Ground Water Quality Assessment Plan Monitoring

Chromium, dissolved (mg/l)

SAMPLED															FIELD	TRIP
FROM -	TO	1	6-A	9	11-A	11-B	11-D	12-A	12-B	13-A	13-B	14-A	15-A	16-A	BLANK	BLANK
10/17/86		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05
03/11/87	03/12/87	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05
05/18/87	05/19/87	< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	
08/18/87	08/19/87	< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	
11/12/87		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05		< 0.05
02/10/88		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05
05/10/88		< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	plugged	< 0.05	< 0.05	< 0.05	
08/10/88		< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	
11/03/88		< 0.08	< 0.08		< 0.08	< 0.08	< 0.08	< 0.08	< 0.08	< 0.08	< 0.08		< 0.08	< 0.08		
03/26/90	03/27/90	0.06			< 0.05	< 0.05	0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05
06/18/90		0.06			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	0.08		< 0.05	< 0.05	0.08	< 0.05
06/18/90	dup	0.06					0.06									
06/18/90	trip	0.06					0.06									
06/18/90	quad	0.08					0.08									
09/24/90		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05
09/24/90	dup										< 0.05					
09/24/90	trip										< 0.05					
12/20/90		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05

↑  
 upgradient  
 well

## GROUND WATER MONITORING DATA

Ground Water Quality Assessment Plan Monitoring

1990 ANNUAL REPORT (dated 2/21/91)

WW Engineering + Science

Lead, dissolved (mg/l)

SAMPLED		1	6-A	9	11-A	11-B	11-D	12-A	12-B	13-A	13-B	14-A	15-A	16-A	FIELD BLANK	TRIP BLANK
FROM -	TO															
10/17/86		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05
03/11/87	03/12/87	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05
05/18/87	05/19/87	< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	
08/18/87	08/19/87	< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	
11/12/87		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05		< 0.05
02/10/88		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05
05/10/88		< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	plugged	< 0.05	< 0.05	< 0.05	
08/10/88		< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	
11/03/88		< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05		
03/26/90	03/27/90	< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05
06/18/90		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05
09/24/90		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05
12/20/90		< 0.05			< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05		< 0.05	< 0.05	< 0.05	< 0.05

**GROUND WATER MONITORING DATA**  
**Ground Water Quality Assessment Plan Monitoring**  
**Annual Parameters (mg/l)**

Well	Date	Chloride	Sulfate	Manganese	Iron
1	10/17/86	130	2400	1.1	3.5
1	11/12/87	65	900	0.84	4.8
1	11/03/88	150	674	0.59	6.5
1	06/18/90	76	744	0.61	4.2
6-A	11/03/88	85	1380	0.11	22
11-A	10/17/86	36	880	0.27	0.1
11-A	11/12/87	57	690	0.62	2.6
11-A	11/03/88	60	823	0.46	0.84
11-A	06/18/90	97	886	0.52	2.3
11-B	10/17/86	37	920	0.31	1.5
11-B	11/12/87	99	800	0.42	2.6
11-B	11/03/88	61	837	0.35	0.57
11-B	06/18/90	134	900	0.49	5
11-D	10/17/86	48	150	0.05	1.7
11-D	11/12/87	55	120	0.04	1.9
11-D	11/03/88	65	134	0.04	2.6
11-D	06/18/90	66	176	0.06	2.8
12-A	10/17/86	35	540	0.03	< 0.01
12-A	11/12/87	62	370	0.03	0.04
12-A	11/03/88	59	637	< 0.01	< 0.01
12-A	06/18/90	74	824	0.06	< 0.01
12-B	10/17/86	69	540	0.10	3.4
12-B	11/12/87	66	540	0.13	4.4
12-B	11/03/88	63	547	0.11	3.6
12-B	06/18/90	65	606	0.16	4.5
13-A	10/17/86	45	2900	0.96	6.1
13-A	11/12/87	42	1330	0.87	6.3
13-A	11/03/88	67	1290	0.81	6.1
13-A	06/18/90	56	698	0.92	9
13-B	10/17/86	39	860	0.22	4.3
13-B	11/12/87	62	890	0.31	7.7
13-B	11/03/88	58	992	0.25	8.5
13-B	06/18/90	151	870	0.31	7
14-A	10/17/86	140	610	0.12	11
14-A	11/12/87	130	390	0.16	21



**GROUND WATER MONITORING DATA**  
**Ground Water Quality Assessment Plan Monitoring**  
**Annual Parameters (mg/l)**

Well	Date	Chloride	Sulfate	Manganese	Iron
15-A	11/03/88	38	460	< 0.01	< 0.01
15-A	06/18/90	11	74	< 0.01	< 0.01
16-A	10/17/86	37	500	0.18	0.05
16-A	11/12/87	73	610	0.08	0.07
16-A	06/18/90	70	759	0.08	< 0.01
EQP BLK	10/17/86	6.2	< 5	< 0.01	< 0.01
EQP BLK	11/12/87	< 1	< 5		< 0.01
EQP BLK	06/18/90	< 2	< 5	< 0.01	< 0.01
TRP BLK	10/17/86	3.8	< 5	< 0.01	< 0.01
TRP BLK	11/12/87	1.9	< 5	< 0.01	< 0.01
TRP BLK	06/18/90	< 2	< 5	< 0.01	< 0.01
EPA STD		250	250	0.05	0.3

QUANEX O&M INSPECTION  
2/27/91  
STIFF and PIPER DIAGRAMS

-----

Stiff and Piper Diagrams were constructed for the six wells that MDNR split sampled. Four of the six wells, MW 1, 11A, 11B, and 13B, have very similar chemistry. The other two are only slightly different. MW-13A has relatively more bicarbonate ( $\text{HCO}_3$ ) as compared to the first four wells listed. Well 11D, the deepest of the wells represented in MDNR samples has less overall dissolved solids, and has more bicarbonate than sulfate. This difference can be seen graphically in the attached stiff diagrams and Piper Trilinear diagrams.

There is little evidence of impacts on groundwater quality related to the impoundments. One explanation for relatively higher bicarbonate in 13A is discharge from the pond of water with higher  $\text{HCO}_3$  content related to the lime treatment that occurred in the past. In all wells except the deep MW-11D, sulfate is the dominant anion. In fact, the natural shallow groundwater quality in this area appears to be high in sulfate. The higher bicarbonate in well 11D may be the natural state of groundwater deeper in the aquifer. Wells 11A and 11B, which are shallower than 11D do not show higher bicarbonate. The deeper groundwater quality does appear to be different than shallow groundwater chemistry.

# CHEMISTRY ANALYSIS

PROJECT: QUANEX  
LOCATION: SOUTH LYON

FILE: 1

WELL NO.: MW11A

CATIONS	PPM	EPM	% EPM
Ca	325.00	16.22	72.13
Mg	32.90	2.71	12.03
Na+K	86.40	3.56	15.84

ANIONS	PPM	EPM	% EPM
HCO3+CO3	156.00	2.56	11.28
SO4	832.00	17.32	76.41
Cl	99.00	2.79	12.31

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 0.60 %  
SODIUM ABSORPTION RATION (S.A.R.): 1.07

WELL NO.: MW11B

CATIONS	PPM	EPM	% EPM
Ca	339.00	16.92	72.29
Mg	40.20	3.31	14.13
Na+K	75.80	3.18	13.58

ANIONS	PPM	EPM	% EPM
HCO3+CO3	170.00	2.79	11.43
SO4	873.00	18.18	74.57
Cl	121.00	3.41	14.00

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 1.69 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.95

MICHIGAN DEPT. OF NATURAL RESOURCES

# CHEMISTRY ANALYSIS

PROJECT: QUANEX  
LOCATION: SOUTH LYON

FILE: 1

WELL NO.: MW11D

CATIONS	PPM	EPM	% EPM
Ca	142.00	7.09	65.05
Mg	38.00	2.96	27.18
Na+K	20.45	0.85	7.76

ANIONS	PPM	EPM	% EPM
HCO3+CO3	284.00	4.65	45.88
SO4	177.00	3.69	36.33
Cl	64.00	1.80	17.79

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 4.04 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.35

WELL NO.: MW13A


CATIONS	PPM	EPM	% EPM
Ca	342.00	17.07	72.14
Mg	52.00	4.28	18.08
Na+K	55.70	2.31	9.78

ANIONS	PPM	EPM	% EPM
HCO3+CO3	517.00	8.47	37.00
SO4	624.00	12.99	56.72
Cl	51.00	1.44	6.28

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 2.37 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.66

MICHIGAN DEPT. OF NATURAL RESOURCES

# STIFF GRAPH




PROJECT: Quanex  
 FILE: 1  
 LOCATION: South Lyon

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE: 1





PROJECT: Quanex  
FILE: 1  
LOCATION: South Lyon

PIE DIAGRAMS  
SHOWING WATER QUALITY

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE: 3

# CHEMISTRY ANALYSIS

PROJECT: QUANEX  
LOCATION: SOUTH LYON

FILE: 1

WELL NO.: MW13A

CATIONS	PPM	EPM	% EPM
Ca	342.00	17.07	72.14
Mg	52.00	4.28	18.08
Na+K	55.70	2.31	9.78

ANIONS	PPM	EPM	% EPM
HCO3+CO3	517.00	8.47	37.00
SO4	624.00	12.99	56.72
Cl	51.00	1.44	6.28

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 2.37 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.66

WELL NO.: MW13B

CATIONS	PPM	EPM	% EPM
Ca	312.00	15.57	66.46
Mg	45.00	3.70	15.80
Na+K	97.50	4.16	17.74

ANIONS	PPM	EPM	% EPM
HCO3+CO3	216.00	3.54	15.16
SO4	759.00	15.80	67.68
Cl	142.00	4.00	17.15

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 0.69 %  
SODIUM ABSORPTION RATION (S.A.R.): 1.30

MICHIGAN DEPT. OF NATURAL RESOURCES



# CHEMISTRY ANALYSIS

---

PROJECT: QUANEX  
LOCATION: SOUTH LYON

FILE: 1

WELL NO.: MW1


CATIONS	PPM	EPM	% EPM
Ca	272.00	13.57	76.34
Mg	19.00	1.56	8.79
Na+K	63.10	2.64	14.87

ANIONS	PPM	EPM	% EPM
HCO3+CO3	169.00	2.77	15.26
SO4	629.00	13.10	72.15
Cl	81.00	2.28	12.59

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 0.55 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.91

MICHIGAN DEPT. OF NATURAL RESOURCES


# STIFF GRAPH



PROJECT: GUANEX  
 FILE: 2  
 LOCATION: SOUTH LYON

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE: 4




PROJECT: GUANEX  
 FILE: 2  
 LOCATION: SOUTH LYON

PIPER TRILINEAR DIAGRAM

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE: 5



PROJECT: QUANEX  
FILE: 2  
LOCATION: SOUTH LYON

PIE DIAGRAMS  
SHOWING WATER QUALITY

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE: 6

QUANEX O&M INSPECTION  
2/27/91  
REVIEW OF 1990 ANNUAL GROUNDWATER REPORT  
-----

The Waste Management Division of Michigan DNR received the Annual Groundwater Report covering 1990 on 2/21/91. The report has been reviewed as part of this inspection. The report deals with the question of arsenic, the origin of the 1,1 dichloroethane, and groundwater flow evaluation. The report states that a "fundamental change in the monitoring program is necessary". This O&M inspection deals specifically with these issues in the list of items that Quanex must address.

Water Level Evaluation:

Groundwater flow direction, both horizontally and vertically has been well established at this site. There is a good system of vertical well clusters. Groundwater flow has been consistently to the west or southwest. Vertical gradient have been relatively consistent. There is a downward gradient from shallow to mid-level, and an upward gradient from deep wells to the mid-level ones.

However, there is a problem related to the top-of-casing elevations. In reviewing the water level measurement contained in the First Quarter 1990 Report dated 5/7/90, the vertical gradients are not consistent with the conventional wisdom as explained in the preceding paragraph. Checking of other records shows that the top-of-casing elevations for the wells has changed. For example, well 11D elevations:

<u>T.O.C.</u>	<u>date</u>	<u>Report</u>
921.07	4/86	Groundwater Assessment Report
920.77	1/89	1988 Annual Groundwater Report
921.77	2/91	1990 Annual Groundwater Report

Depending on which elevation is current, the vertical gradient could be much different. This will greatly affect the question of arsenic origin. The difference in elevation must be explained.

1,1 Dichloroethane:

I agree that the likely source of the 1,1, dichloroethane is the landfill (SWMU) found directly under the southern portion of the former impoundments. All evidence to date supports that conclusion. There are also other possible sources. For example, well 6A has shown in the past consistently higher levels of 1,1, DCEa. Since this appears to be a more widespread problem, it would be appropriate to address this contaminant under the HSWA program.

### Arsenic:

With regards to arsenic, I agree with the statement that a fundamental change is needed in the monitoring program to answer the question of source. There is evidence of upward gradients at the impoundments, and arsenic is present in mid to deep level wells. However, arsenic is also present in shallow wells 6A, 11A, 13A, and 14A. Arsenic is also present in mid-level wells 11B, 12B, and 13B. For 11B there is a consistent downward gradient from shallow (11A) to 11B, and from 11B to 11C. If the gradient is consistently downward, how did arsenic from 11D get to 11B? For 13B, there is a downward gradient from shallow well 13A, and 13A has shown detectable arsenic.

Part of the data gap is for wells 12C and 13C. Proof of arsenic detected in these deep wells would be invaluable. All of the proof of arsenic is also from wells located next to the impoundments. There is no data from deep in the aquifer away from the impoundments. Upgradient data from the deep aquifer would also be invaluable. Therefore, sampling of well 12C and 13C will be requested, along with installation of an upgradient deep well.

### Proposal to Include Well 11D In Upgradient Data:

I do not agree with combining data from 11D and upgradient well 1. This will not necessarily represent the background concentration of arsenic deep in the aquifer. First, the wells are constructed of different materials. Well 11D is PVC, and well 1 has galvanized casing. Second, the wells are set at different depths. Third, the shallow groundwater chemistry is different than the deeper portion of the aquifer as noted in the 1990 Annual Report on page 3. I believe it is preferable to install a new upgradient well in the deeper part of the aquifer.

In summary, the 1990 Annual Groundwater Report does contain a proposal to address the arsenic question. I agree that a change in monitoring is needed, but not along the lines proposed. The O&M inspection will request that Quanex submit another proposal.

*Summary Letter and  
EPA Reporting Forms*

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

INTEROFFICE COMMUNICATION

February 27, 1991

TO: Ben Okwumabua, Supervisor  
Southeast Michigan District, WMD

FROM: Jan Sealock *JS*  
David Slayton *DS*  
Geotechnical Unit, WMD

SUBJECT: Summary Memo - 1991 O&M Inspection  
Quanex Corporation  
MID 082 767 591

An O&M inspection has been conducted at Quanex Corporation of South Lyons. The inspection includes a field overview of the company's consultant as they sampled, an audited split sampling of groundwater (on 12/20/90), a sampling & analysis plan review, groundwater flow direction review, Stiff/Piper/Pie diagrams, Annual report review, and O&M checklists.

The attachment to this memo lists violations and areas of concern that need to be addressed by Quanex. This list can be attached to the summary letter that the District sends to the company. A draft summary letter from the District to the company is included in the O&M package for your use.

The company must continue the quarterly assessment monitoring until a permit is issued (post-closure/HSWA), or the facility is clean closed as approved by MDNR. In line with the ongoing assessment monitoring, the company must conduct further study in regards to the question of whether or not the low levels of arsenic detected in some wells is naturally occurring or not. The question of the 1,1 dichloroethane detected in some wells should be addressed in the HSWA permit when it is issued. This parameter does not appear to be attributable to the RCRA Units.

The hazardous waste container storage area is closed, and the certification approved by MDNR. The company started closure of the two RCRA impoundments, but work stopped after solidification of sludge while a delisting petition for the treated liquid waste was submitted to EPA. EPA proposes to deny the delisting. EPA also conducted a VSI in the fall of 1990 as part of an RFA. A revised closure plan is to be submitted by Quanex in regards to the impoundments. Then there will probably need to be a post-closure/HSWA permit. If there are any questions, please contact Jan Sealock at (517)373-4740, or David Slayton at (517)373-8012.

cc: De Montgomery  
HWP/C&E file  
Geotech file



ATTACHMENT

Quanex Corporation  
MID 082 767 591  
O&M Inspection - February 27, 1991  
-----

1. The sampling and analysis plan (April 1986, Groundwater Quality Assessment Program) must be updated to include the following items:
  - a) Detection limits for all required parameters.  
[Violation - 40 CFR 265.92(a)(3)]
  - b) Laboratory QA/QC procedures (spikes, duplicates, standards). [Violation - 265.92(a)(3)]
  - c) Specify purge method, fate of purged water, how purge volume is calculated. [Violation - 265.92(a)(1)]
  - d) Specify correct analytical methods for dissolved oxygen, nitrate-nitrite, and organic carbon.  
[Violation - 265.92(a)(3)]
  - e) Inspection of well casing, protective casing, surface pad, and lock during routine sampling events.  
Provisions to repair any damage must be included.  
[Area of concern]
2. The company must supply additional data supporting its claim that the arsenic detected in some wells is naturally occurring. The company must submit a proposal within 90 days for additional well(s) and sampling. The proposal in the 1990 Annual Groundwater report is not adequate (see discussion in text of O&M writeup). The proposal must address the following:  
[Area of Concern -265.93(d)(4)(i)]
  - a) Installation of a new deep well at MW-1.
  - b) Sampling of deep well 12C and 13C.
  - c) Explanation of different top of casing elevations.
  - d) Analysis of vertical gradients to geochemistry.
3. The 1,1 dichloroethane contamination must be addressed. The most obvious vehicle is to address this contaminant is through the HSWA process. EPA has already started the RFA. The 1,1 dichloroethane found in low levels in wells 11A and 11B may be related to a SWMU found directly under the southern part of the RCRA impoundments. Another source may also be present at the site because well 6A has shown consistently higher levels, and this well is located farther away from the impoundments. The RFI to be eventually conducted under HSWA must include addressing the 1,1 dichloroethane. [Area of concern]

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

INTEROFFICE COMMUNICATION

June 30, 1988

TO: Ben Okwumabua, District Supervisor  
Northville Office, WMD

FROM: David Slayton, Geologist *DS*  
Geotechnical Unit, WMD

SUBJECT: Quanex Corporation, South Lyons, MID 082 767 591  
CME Summary

This summary is for the Comprehensive Monitoring Evaluation (CME) conducted at Quanex. Monitor wells were split sampled between DNR and the company in February 1988. Liz Browne sent her review comments to Lynne King in a memo dated 3/17/88. This summary includes the items Liz noted in her review, plus additional ones developed during data review. Liz's memo does have more detail.

1. The sampling and analysis plan contained in the April 1986 Ground-water Assessment plan needs to be updated to reflect actual field procedures used and additional information as detailed below.
  - a. The plan must include details on the method used to determine the purge volume, the method of measuring purged water removed, and disposal of purge water.
  - b. The plan must include information on the EDI laboratory QA/QC program such as use of spikes, duplicates, and standards.
  - c. Table 13 must include detection limits, and the method references must be checked and updated to be consistent with SW-846, Third edition and Standard Methods 16th edition. Methods referenced in error are dissolved oxygen, nitrate-nitrite, and organic carbon, and specific methods are needed for metals.
  - d. The plan must be updated to include details on any field measurements taken, as well as the method and schedule of meter calibration. Information must be included on field filtering methods, and decontamination of this equipment.
  - e. Clarification is needed on the time elapsed between purging and sampling of wells, and the plan should specify precautions taken when sampling for volatile organics to minimize aeration, such as lowering the bailer slowly.
2. Since the consultant, EDI Engineering & Science, concludes that the arsenic levels detected in some wells is naturally occurring, we must now proceed to verify. The company must submit a proposal on

how they intend to show that the arsenic is naturally occurring by October 1, 1988.

3. The company should propose what steps, if any, will be taken to remediate the 1,1-dichloroethane. This should be submitted by October 1, 1988, also. Is the fuel oil recovery still in progress, and if so, would it capture the 1,1-dichloroethane?
4. The company must explain why the First Quarter 1988 Report dated 4/8/88 only had resampling done on 4 parameters (see attachment D of that report). Resampling is to be done if the concentration of a constituent in a well measured during the fourth quarter 1987 was above the mean background concentration and above the detection limit. The annual report dated 1/29/88 lists eleven (11) parameters that were above background in the fourth quarter of 1987. Therefore, all should have been resampled in the first quarter of 1988. The company must explain this perceived discrepancy.
5. When the impoundments are excavated, the area around soil boring SB-22, at the southwest corner of the west impoundment, must be excavated to remove the material noted on the boring log. The log from 9.5-15 feet lists wood, black, oily, tar odor, and pieces of metal. This must be removed at closure.

In summary, no major deficiencies were found. The groundwater monitoring program being conducted is of good quality. The sampling and analysis plan needs to be updated to include some specifics on actual field procedures, and there needs to be a resolution of the arsenic and 1, 1 dichloroethane contamination questions. Please contact me if there are any questions.

cc: Ms. Marilyn Sabadaszka, Region V, U.S. EPA  
Ms. Andrea Schoenrock/C & E File  
Geotech Unit File

# FY 1988 HAZARDOUS WASTE COMPLIANCE MONITORING AND ENFORCEMENT LOG

1. EPA ID: M1 D082767591 4. Data Entry: Rev 14

2. HANDLER NAME: Quaker Corp. Update 1

3. ADDRESS: 400 McMunn, South Lyon, MI

5. DATE OF INITIAL EVALUATION WHICH IS 5a. AGENCY RESPONSIBLE FOR E = EPA O = Other  
 THE BASIS FOR THIS REPORT: 6/30/88 EVALUATION: S S = State B = Contractor/State  
 Put code in box S C = Contractor/EPA X = Oversight

6. TYPE OF EVALUATION COVERED BY THIS REPORT: 4 1 = Compliance Eval. Inspection(CSI) 4 = Comp GYM Eval(CHE)  
 Select Evaluation Type and insert in box: 4 2 = Sampling Inspection 5 = Compliance Sched. Eval  
 3 = Record Review 11 = Case Dev. Inspection  
 12 = O&M Inspection

7. DATE OF EVALUATION COVERED BY THIS REPORT (enter only if different from 5): 1/1

7a. Eval. Comments: No major deficiencies, sampling + analysis plan needs minor revisions to reflect actual field procedures.

8. CLASS and VIOLATIONS		Violations/Releases								
Key	Class of Violation	GYM/RLSE	C/FC	Fin. Res	Pt. B	Cont. Sch	Manifest	Land-Ban	Other	
'X' = Violations, no Specialties										
'B' = Violations & Specialty	I	0								
'S' = Same Viol./Specialty										
'Z' = Pending determination	II	0								
'O' = No Viol or Specialty found										
Acceptable Codes										
		X	X	X	X	X	X	X	X	X
Specialties		S	S	S	S	S	S	S	S	S
		Z	Z	Z	Z	Z	Z	Z	Z	Z
'I' = No-insurance only		O	O	O	O	O	O	O	O	O
'C' = CI Schedule Violation		R		I		C				
'R' = 3008(h)-like release		B		B		B				
'* = Class I only										

8a. Viol. Comment: \_\_\_\_\_

## 9. ENFORCEMENT ACTIONS:

Area of Class	Type (Viol./rel.)	Date Action Taken	Compliance Dates Scheduled	Actual	Penalty Assessed	Collected	Resp. Ag. (use code)

Codes for 03 = Warning Letter 11 = Filed Civil Action 15 = CI Init. Admin. Order Resp. Agency Codes  
 Types of 04 = Admin. Complaint 12 = Filed Criminal Action Order E = EPA  
 Enforcement 05 = Final Admin. Order 13 = Civil Referral to AG/DOJ 16 = CI Final Admin. Order S = State  
 Actions: 10 = Informal 19 = Final Judicial Order Order X = EPA Oversight

10. Enforc. Comment: \_\_\_\_\_

FY 1988 FACILITY STATUS SHEET

1.a. EPA ID: M10082767591

2.a. Date Status Sheet Submitted 6/30/88

b. Facility Name: Dyanex Corp.

b. First Time Report ☒ Update ☐

This form only applies to facilities that have some form of land disposal. Of these facilities, complete this form for only those facilities that are not on a permit track for their land disposal.

3. Facility Ground Water Monitoring Status (Choose one)
- A D = 265 Detection  
A = 265 Assessment  
 W = Waiver (Hydrogeologic)
- N = GWM Not Required  
 X = No wells but should have

4. GWM Activity Reported with this Submission (More than one Activity can be reported on a single Status Sheet)	Respon. Agency	Date	Compliance Status	Date	Compliance Status	Hazardous Waste Constituent
	E-EPA	Status	Y=Compliance	Report	Submitted	Y-HWC in GT
	S-Status	Determined	N=Non-Compl.			W-No HWC in GT
			U=Under Review			
01 Evaluation of Installation of Well System	S	6/30/88	Y			
02 Evaluation of Sampling, Analysis and Evaluation Program	S	6/30/88	Y			
03 Notice of Significant Increase in Concentrations						
04 Groundwater Quality Assessment Report						
05 Waiver Demonstration						
06 GWM Records	S	6/30/88				
07 Evaluation of Hydrogeologic Information	S	6/30/88				

GWM Comment: Good program in place, sampling + analysis adequate, assessment program in progress.

5. Financial Requirements	Respon. Agency	Date	Compliance Status	Compliance Status
		Determined or:	Y= Compliance	
		N = Not Evaluated	N= Non-Compliance	
		X = Not Applicable	B= Bankruptcy	
C = Closure Assurance				
L = Post Closure Assurance				
S = Sudden Liability Instrument				
N = Non-Sudden Liability Instrument				
R = Corrective Action Assurance Instrument				

Financial Comment: \_\_\_\_\_

QUANEX CORPORATION  
MID 082 767 591  
CME FILE

MAY 19, 1988

SUBJECT: Evaluation of Quanex Corporation's statistics for  
annual report 1987 and first quarter report 1988.

When MDNR calculated out the data using a statistical program for T-test on the computer, the same results were encountered that EDI Engineering and Science reported in the 1987 annual report and first quarterly report of 1988.

Within the EDI 1987 annual report (dated 1-29-87) the following monitoring wells showed significant increases in arsenic: 11-B, 11-D, 12-B, 13-B, 14-A. Significant increases in 1,1-DCA were noted in monitoring wells 11-B and 14-A. The T-test computer program used to check company data confirmed EDI calculations for significant increases of arsenic and 1,1-DCA.

In analyzing EDI data from the first quarter 1988 report (dated 4-8-88) and again applying the T-test program, we found the same results which EDI calculated. No significant increases were found in the following monitoring wells and listed parameters which were suspect due to the previous quarter's sampling results:

11-A	1,1-DCA
12-A	Selenium
12-A	Copper
16-A	Copper

In summary, the data presented in the two reports have been found to be accurate. No problems were encountered in the company's calculations of the t-test with continuity correction.

Although the calculations and statistics are correct, there is a problem with procedures under the groundwater assessment monitoring program. The first quarter 1988 report dated 4/8/88 from EDI states that if the concentration of a constituent measured during the fourth quarter 1987 was above the mean background concentration, and above the detection limit, then that well was purged and sampled during the Feb. 1988 sampling. Only four samples were "rechecked". The annual report dated 1/29/88 lists eleven parameters in various wells that measured above the mean background and the detection limit. All eleven of these should have been rechecked in the next quarter (Feb 1988).

# GNIFICANT INCREASE IN ARSENIC

An. Report 1987

CILITY  
ANEX

## BACKGROUND WELL

## SAMPLE PARAMETER ARSENIC

SAMPLE DATA	READING	X	DELTA
1-DEC-83	1	.5	.5
1-MAR-84	10	5	5
1-JUN-84	1	1	.5
1-SEP-84	1	.5	.5
1-SEP-85	1	.5	.5
1-OCT-85	4.4	4.4	.05
1-OCT-86	2	1	1
1-MAR-87	1	.5	.5
1-MAY-87	2	1	1
1-AUG-87	2	1	1
1-NOV-87	2	1	1

## BACKGROUND STATISTICS

	MEAN	VARIANCE	LLVOM
1	1.490909	3.599326	.6875569

## DWNGRADIANT WELL

B

## SAMPLE PARAMETER ARSENIC

SAMPLE DATE	READING	X	DELTA
1-AUG-87	4.9	4.9	.05
1-NOV-87	3.7	3.7	.05
1-NOV-87	3.7	3.7	.05
1-NOV-87	4.2	4.2	.05

## DWNGRADIANT WELL STATISTICS

	MEAN	VARIANCE	LLVOM
	4.125	.3236107	.000625

## IMPARISON STATISTICS

PHA	T*	Tc
01	3.004832	2.951081

An. Report 1987

# SIGNIFICANT INCREASE IN ARSENIC

WELL  
WELL

BACKGROUND WELL

SAMPLE PARAMETER  
ARSENIC

SAMPLE DATA	READING	X	DELTA
3-DEC-83	1	.5	.5
1-MAR-84	10	5	5
3-JUN-84	1	1	.5
7-SEP-84	1	.5	.5
4-SEP-85	1	.5	.5
3-OCT-85	4.4	4.4	.05
7-OCT-86	2	1	1
1-MAR-87	1	.5	.5
3-MAY-87	2	1	1
3-AUG-87	2	1	1
2-NOV-87	2	1	1

## BACKGROUND STATISTICS

MEAN	VARIANCE	LLVOM
11 1.490909	3.599326	.6875569

DWNGRADIENT WELL  
1D

SAMPLE PARAMETER  
ARSENIC

SAMPLE DATE	READING	X	DELTA
7-AUG-87	5.9	5.9	.05
NOV-87	4.6	4.6	.05
2-NOV-87	5.5	5.5	.05
2-NOV-87	4.8	4.8	.05

## DWNGRADIENT WELL STATISTICS

MEAN	VARIANCE	LLVOM
4 5.2	.3677824	.000625

## COMPARISON STATISTICS

_PHA	T*	Tc
.01	4.201059	2.973605



IGNIFICANT INCREASE IN ARSENIC

ACILITY  
JANEX

BACKGROUND WELL

SAMPLE PARAMETER  
ARSENIC

SAMPLE DATA	READING	X	DELTA
3-DEC-83	1	.5	.5
4-MAR-84	10	5	5
5-JUN-84	1	1	.5
7-SEP-84	1	.5	.5
4-SEP-85	1	.5	.5
3-OCT-85	4.4	4.4	.05
7-OCT-86	2	1	1
1-MAR-87	1	.5	.5
3-MAY-87	2	1	1
3-AUG-87	2	1	1
2-NOV-87	2	1	1

BACKGROUND STATISTICS

	MEAN	VARIANCE	LLVDM
11	1.490909	3.599326	.6875569

DWNGRADIENT WELL  
2B

SAMPLE PARAMETER  
ARSENIC

SAMPLE DATE	READING	X	DELTA
7-AUG-87	9.4	9.399999	.05
2-NOV-87	9.2	9.2	.05
2-NOV-87	9.1	9.100001	.05
2-NOV-87	8.9	8.899999	.05

DWNGRADIENT WELL STATISTICS

	MEAN	VARIANCE	LLVDM
4	9.149999	4.445625E-02	.000625

COMPARISON STATISTICS

CPHA	T*	Tc
.01	9.163067	2.792267

An. Report 1987

SIGNIFICANT INCREASE IN ARSENIC

FACILITY  
QUANEX

BACKGROUND WELL  
1

SAMPLE PARAMETER  
ARSENIC

SAMPLE DATA	READING	X	DELTA
23-DEC-83	1	.5	.5
14-MAR-84	10	5	5
20-JUN-84	1	1	.5
27-SEP-84	1	.5	.5
24-SEP-85	1	.5	.5
23-OCT-85	4.4	4.4	.05
17-OCT-86	2	1	1
11-MAR-87	1	.5	.5
18-MAY-87	2	1	1
18-AUG-87	2	1	1
12-NOV-87	2	1	1

BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVOM
11	1.490909	3.599326	.6875569

DOWNGRADIENT WELL  
13B

SAMPLE PARAMETER  
ARSENIC

SAMPLE DATE	READING	X	DELTA
19-AUG-87	5.9	5.9	.05
2-NOV-87	5.6	5.6	.05
12-NOV-87	5.4	5.4	.05
12-NOV-87	5.2	5.2	.05

DOWNGRADIENT WELL STATISTICS

n	MEAN	VARIANCE	LLVOM
4	5.525	9.028094E-02	.000625

COMPARISION STATISTICS

ALPHA	T*	Tc
.01	4.787156	2.820479

An. Report 1987

SIGNIFICANT INCREASE IN arsenic

FACILITY

guanex

BACKGROUND WELL

1

SAMPLE PARAMETER

arsenic

SAMPLE DATA

	READING	X	DELTA
23-dec-83	1	.5	.5
14-mar-84	10	5	5
20-june-84	1	1	.5
27-sept-84	1	.5	.5
24-sept-85	1	.5	.5
23-oct-85	4.4	4.4	.05
17-oct-86	2	1	1
11-mar-87	1	.5	.5
18-may-87	2	1	1
18-aug-87	2	1	1
12-nov-87	2	1	1

BACKGROUND STATISTICS

	MEAN	VARIANCE	LLVDM
11	1.490909	3.599326	.6875569

DOWNGRAIDENT WELL

4A

SAMPLE PARAMETER

arsenic

SAMPLE DATE

	READING	X	DELTA
9-aug-87	8.6	8.600001	.05
2-nov-87	8.4	8.399999	.05
2-nov-87	9.8	9.8	.05
2-nov-87	8.7	8.7	.05

DOWNGRAIDENT WELL STATISTICS

	MEAN	VARIANCE	LLVDM
4	8.875	.3969445	.000625

COMPARISION STATISTICS

ALPHA	T*	Tc
.01	8.324665	2.988128

## SIGNIFICANT INCREASE IN 1,1-DCA

An. Report 1987

FACILITY  
QUANEX

## BACKGROUND WELL

## SAMPLE PARAMETER

1

1,1-DCA

## SAMPLE DATA

## READING

X

## DELTA

24-SEP-85	1	.5	.5
17-OCT-86	2	1	1
22-DEC-86	1	.5	.5
22-DEC-86	1	.5	.5
11-MAR-87	1	.5	.5
18-MAY-87	1	.5	.5
18-AUG-87	1	.5	.5
12-NOV-87	1	.5	.5

## BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVDM
8	.5625	.1622024	.0859375

## DOWNGRAIDENT WELL

## SAMPLE PARAMETER

11B

1,1-DCA

## SAMPLE DATE

## READING

X

## DELTA

19-AUG-87	6.1	6.1	.05
12-NOV-87	5.3	5.3	.05
12-NOV-87	5.5	5.5	.05
12-NOV-87	5.2	5.2	.05

## DOWNGRAIDENT WELL STATISTICS

n	MEAN	VARIANCE	LLVDM
4	5.525	.1636147	.000625

## COMPARISION STATISTICS

ALPHA	T*	Tc
.01	13.93383	3.495586

NO SIGNIFICANT INCREASE IN 1,1-DCA

An. Report 198

FACILITY  
QUANEX

BACKGROUND WELL  
1

SAMPLE PARAMETER  
1,1-DCA

SAMPLE DATA	READING	X	DELTA
24-SEP-85	1	.5	.5
17-OCT-86	2	1	1
22-DEC-86	1	.5	.5
22-DEC-86	1	.5	.5
11-MAR-87	1	.5	.5
18-MAY-87	1	.5	.5
18-AUG-87	1	.5	.5
12-NOV-87	1	.5	.5

BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVOM
8	.5625	.1622024	.0859375

DOWNGRAIDENT WELL  
14A

SAMPLE PARAMETER  
1,1-DCA

SAMPLE DATE	READING	X	DELTA
19-AUG-87	1.1	1.1	.05
12-NOV-87	1.2	1.2	.05
12-NOV-87	1.4	1.4	.05
12-NOV-87	1.1	1.1	.05

DOWNGRAIDENT WELL STATISTICS

n	MEAN	VARIANCE	LLVOM
4	1.2	2.111109E-02	.000625

COMPARISION STATISTICS

ALPHA	T*	Tc
.01	2.110797	3.087279

15/ October 1988

NO SIGNIFICANT INCREASE IN COPPER

FACILITY  
TUANEX

BACKGROUND WELL  
1

SAMPLE PARAMETER  
COPPER

SAMPLE DATA	READING	X	DELTA
23-OCT-85	.01	.005	.005
17-OCT-86	.02	.02	.005
11-MAR-87	.01	.005	.005
18-MAY-87	.01	.005	.005
19-AUG-87	.01	.005	.005
12-NOV-87	.01	.005	.005
10-FEB-88	.01	.005	.005

BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVOM
7	7.142857E-03	4.18651E-05	6.25E-06

DOWNGRAIDENT WELL  
16A

SAMPLE PARAMETER  
COPPER

SAMPLE DATE	READING	X	DELTA
12-NOV-87	.03	.03	.005
10-FEB-88	.01	.005	.005
10-FEB-88	.01	.005	.005
10-FEB-88	.01	.005	.005

DOWNGRAIDENT WELL STATISTICS

n	MEAN	VARIANCE	LLVOM
4	.01125	1.673611E-04	6.25E-06

COMPARISION STATISTICS

ALPHA	T*	Tc
.01	.5922583	4.35931

1st Quarter 1988

NO SIGNIFICANT INCREASE IN COPPER

FACILITY  
QUANEX

BACKGROUND WELL                      SAMPLE PARAMETER  
1                                      COPPER

SAMPLE DATA	READING	X	DELTA
23-OCT-85	.01	.005	.005
17-OCT-86	.02	.02	.005
11-MAR-87	.01	.005	.005
18-MAY-87	.01	.005	.005
19-AUG-87	.01	.005	.005
12-NOV-87	.01	.005	.005
10-FEB-88	.01	.005	.005

BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVDM
7	7.142857E-03	4.18651E-05	6.25E-06

DOWNGRAIDENT WELL                      SAMPLE PARAMETER  
12A                                      COPPER

SAMPLE DATE	READING	X	DELTA
12-NOV-87	.01	.01	.005
10-FEB-88	.01	.005	.005
10-FEB-88	.01	.005	.005
10-FEB-88	.01	.005	.005

DOWNGRAIDENT WELL STATISTICS

n	MEAN	VARIANCE	LLVDM
4	.00625	1.736112E-05	6.25E-06

COMPARISION STATISTICS

ALPHA	T*	Tc
.01	-.252538	3.842

1st Quarter 1986

NO SIGNIFICANT INCREASE IN SELENIUM

FACILITY  
QUANEX

## BACKGROUND WELL

SAMPLE PARAMETER  
SELENIUM

1

## SAMPLE DATA

## READING

X

## DELTA

23-DEC-83	10	5	5
14-MAR-84	1	.5	.5
20-JUN-84	10	5	5
27-SEP-84	10	5	5
24-SEP-85	1	.5	.5
23-OCT-85	2	1	1
17-OCT-86	2	1	1
11-MAR-87	2	1	1
18-MAY-87	2	1	1
18-AUG-87	2	2	.05
12-NOV-87	2	1	1
10-FEB-88	2.4	2.4	.05

## BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVOM
12	2.116667	5.757426	1.677188

## DOWNGRAIDENT WELL

SAMPLE PARAMETER  
SELENIUM

12A

## SAMPLE DATE

## READING

X

## DELTA

2-NOV-87	2.9	2.9	.05
10-FEB-88	10	10	.5
10-FEB-88	11	11	.5
10-FEB-88	11	11	.5

## DOWNGRAIDENT WELL STATISTICS

n	MEAN	VARIANCE	LLVOM
4	8.725001	15.3861	4.703125E-02

## COMPARISION STATISTICS

ALPHA	T*	Tc
.01	2.811748	3.987475



NO SIGNIFICANT INCREASE IN 1-1-DCA

1st Quarter 1988

FACILITY  
QUANEX

BACKGROUND WELL  
1

SAMPLE PARAMETER  
1-1-DCA

SAMPLE DATA	READING	X	DELTA
24-SEP-85	1	.5	.5
17-OCT-86	2	1	1
22-DEC-86	1	.5	.5
22-DEC-86	1	.5	.5
11-MAR-87	1	.5	.5
18-MAY-87	1	.5	.5
18-AUG-87	1	.5	.5
12-NOV-87	1	.5	.5
10-FEB-88	1	.5	.5

BACKGROUND STATISTICS

n	MEAN	VARIANCE	LLVOM
9	.5555556	.1527778	8.333334E-02

DOWNGRADIANT WELL  
11A

SAMPLE PARAMETER  
1-1-DCA

SAMPLE DATE	READING	X	DELTA
12-NOV-87	4.1	4.1	.05
10-FEB-88	1.8	1.8	.05
10-FEB-88	1	.5	.5

DOWNGRADIANT WELL STATISTICS

n	MEAN	VARIANCE	LLVOM
3	2.133333	3.365834	.02125

COMPARISION STATISTICS

ALPHA	T*	Tc
.01	1.43715	6.683668

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

INTEROFFICE COMMUNICATION

March 17, 1988

TO: Lynne King, Northville District Office, WMD  
FROM: Liz Browne, HW Permits, WMD *Liz*  
SUBJECT: Quanex Corp., Michigan Seamless Tube Division  
South Lyons, MID 082 767 591

On February 10, 1988 I conducted a sampling inspection at this facility as part of a Comprehensive Monitoring Evaluation (CME). Although no violations of 40 CFR 265.92 [as referenced in Act 64 R299.11003(m)] were found at this time, concerns were noted and are mentioned within the following inspection summary.

EDI Engineering and Science of Grand Rapids conducts all field and laboratory work for the facility. The Ground Water Quality Assessment Program, dated April, 1986, authored by EDI, contained the Sampling and Analysis Plan (SAP) that was used for this review.

Static water level readings are taken with a steel tape to the nearest 0.01 foot. The readings are taken to the top of the casing, and not to the top of the locking cap. Although this is stated in the plan, it should be emphasized to field staff should personnel change. Measurements compared reasonably well with those obtained with the DNR meter.

Purging is accomplished using either stainless steel or teflon bottom filling bailers and polypropylene rope. A new bailer, steam cleaned prior to the site visit, with new rope attached at the time of purging is used. Three casing volumes are purged prior to sampling. The purge water is directed into a graduated bucket to enable a volume measurement, and to facilitate the disposal of the water away from the well. The methods used to determine purge volume needed, method of measuring purge volume removed, and the disposal of the purge water should all be addressed in the plan.

Samples are obtained using the same equipment as, and immediately after, purging, where recovery allows. The plan states that the wells should be sampled within 24 hours of purging. Sampling immediately after purging is the preferable method. If this is not possible, recovery rates should be determined for each well, and sampling done as soon as sufficient volume exists.

Field measured parameters include pH and specific conductance. The meters are calibrated at the beginning of the day. The plan only mentions pH as a field parameter, and does not address the meter calibration. The plan should be updated to reflect field conditions. Other

field work includes the filtering of the metals sample immediately upon collection, prior to preservation. These are all excellent field methods to attempt to maintain the integrity of unstable parameters.

Field QA/QC procedures include the use of clean bailers and new line as already mentioned. Additionally, trip and equipment blanks and sample replicates are used to evaluate the sampling program. These are all good measures to help to assure that representative samples are taken. One item of concern noted during the sampling was the handling of the bailer during volatile organic sampling. The bailer should be lowered carefully for all sample collection, to reduce aeration, but especially for the volatile organics. A note to emphasize this may be appropriate in the plan. Other items of potential concern were not noted during this inspection. The sampling crew appeared to be familiar with the plan, worked carefully, and kept adequate field notes.

Chain of custody appears to be well documented. Field notes, bottle labels, a chain of custody form and an Analytical Services Project Sheet are used to track all samples. Copies of all forms have been included in the plan. Good control can be maintained since sample requests, bottle orders, sampling and analysis are all handled by EDI.

A list of sample parameters with sample container, preservation, holding time, minimum sample size and method references is included in the plan. A table indicating the detection limit attainable by EDI's laboratory is needed to complete this set of information. Also, the method references for some parameters appear to be in error. The Standard Methods reference should be 421, not 412 for dissolved oxygen. Nitrate-nitrite should be method 353 for reference 3, not 201. Reference 3 method 415 should be cited for organic carbon, not 236. All references should be rechecked. The latest editions of the references (SW-846 3rd edition and Standard Methods 16th edition) should be used. Specific methods should be cited, rather than items 200-289 for metals analysis.

A quality assurance/quality control program for EDI's laboratory is needed. Items such as the use of spikes, duplicate samples and standards should be included. The plan does indicate that lab notebooks are kept, and discusses some of the items to be included. This additional information is needed to assure that the careful practices that were evidenced in the field are maintained through the sample preparation and analysis steps.

In summary, both the written plan and the field work were acceptable in most areas. The plan needs to be updated to include details on purging and lab QA/QC. It should also be changed to better reflect the field measurement information, measuring both pH and specific conductance at the time of sampling, as well as the method and schedule of meter calibration. More information on the methods used to filter the samples, and to decontaminate this equipment should be included. Clarification on the time elapsed between purging and sampling should be made, and a note on the care needed for volatile organic sampling should be added. Finally, Table 13 should include detection limits, and the method references need to be checked and updated to reflect newer editions of the references, where applicable.

This concludes the sampling and analysis portion of the CME inspection. A final summary document (including a hydrogeo evaluation, statistical review, ground water contours, etc.) will be forthcoming.

Please call if you have any questions regarding this review.

cc Mr. D. Slayton  
Mr. J. Bohunsky  
Mr. D. Drake  
C&E File  
CME Reports ✓  
Ms. M. Sabadaszka, U.S. EPA-Region V

1988 CME  
QUANEX Corp.  
David Slayton

Hydrogeology  
Groundwater Monitoring  
Groundwater Quality

Hydrogeology

The facility rests on glacial drift deposits that are typical in Michigan. The Quanex facility in South Lyons is in an interlobate area, northwest of the Erie glacial lobe. The north-northeast part of the facility has 15-30 feet of outwash sand and gravel deposits resting on interbedded silt, sand, and clay. In the southern part of the site, only outwash deposits are encountered, which are at least 70 feet deep. The January 1986 Part B application for Quanex by EDI Engineering & Science has a good discussion of site geology. The attached cross-sections in appendix A come from the Part B application, and are used in this report because they are of excellent quality.

Groundwater elevation measurements have consistently shown mounding of the water table under the two impoundments. There are multiple well clusters on all four sides of the impoundments. The cross-sections in Appendix A include vertical groundwater gradients, showing the obvious mounding and downward head at the impoundments. The mounding dissipates rapidly, particularly at the south end where the thick outwash deposits are. In the northern part of the impoundments, the outwash is thinner on top of the silt/sand/clay unit, and the mounding does not dissipate as fast. Without the influence of the impoundments, the flow direction of shallow groundwater would likely be northeast to southwest. Appendix B is a groundwater contour map from the Quanex 1987 annual report, clearly showing the mounding around the impoundments, and groundwater flow radially outward from the impoundments. Some groundwater will likely discharge to the northwest into the adjacent swamp, while the discharge point for the most of the groundwater under the facility is Yerkes Drain on the south side of the plant.

The groundwater flow velocity as calculated in the 1987 annual report of 0.22 ft/day is a good estimate for areas outside of the groundwater "mound" at the impoundments. Immediately adjacent to the impoundments, the flow will be much faster due to the steep gradient. Using the same permeability ( $9.4 \times 10^{-3}$  cm/sec) and porosity (.35) as the annual report calculations, the groundwater flow velocity next to the lagoons is 4.5 feet/day using a gradient of 0.06.

Groundwater Monitoring History

Quanex started RCRA interim status groundwater monitoring under 40 CFR 265, Subpart F in late 1983. The four quarterly background sampling events were done in 12/83, 3/84, 6/84, and 9/84. Subsequent sampling in 1/85, 4/85 and 7/85 and statistical analyses indicated exceedances. A

groundwater assessment plan by Keck Consulting was implemented that included six steps.

In step 2, wells 1, 2, 3, and 4 were analyzed for volatile organics, water quality parameters, and selected groundwater protection parameters. Step 2 included a resampling of the wells for methylene chloride which was detected in Step 1. In April 1986, Quanex proposed through their consultant, EDI Engineering & Science to modify the assessment plan to include recent information developed for the Part B application. The April 1986 plan was revised in July 1986, and approved in October 1986. Since then, quarterly sampling has occurred, and Quanex has been submitting quarterly and annual reports. The constituents of concern have been identified as arsenic and 1,1-dichloroethane.

Due to expansion of the Quanex wastewater treatment plant, three monitoring wells have been plugged and abandoned (see 3/18/88 letter to D. Slayton from EDI). Monitor wells 3, 14A and 14B will be removed from service. Monitor wells 6A and 15A will be sampled as substitutes for the abandoned wells.

Quanex has an approved closure plan for the two surface impoundments, but has not started closure yet. The impoundments are to be no longer used by November 8, 1988. The wastewater treatment plant is being expanded to replace the impoundments.

During closure, excavation in the southwest corner of the west lagoon should proceed until the fill material is removed. Soil boring SB-22 noted "wood, black, oily, tar odor" from 9.5-15 feet deep. This material must be removed at closure.

#### Groundwater Quality

Comparison of laboratory data between DNR and EDI was done for six samples. Appendix C contains a table of comparison and a copy of the analytical results. For the mutual parameters, there is good correlation except for barium and field pH. For barium, the DNR results are consistently much lower than EDI data. The reason is unknown. For field pH, the DNR data is again consistently lower. The probable reasons is use of different meters and calibration standards. For the two parameters of concern, 1,1-dichloroethane and arsenic, there is very good correlation.

Appendix D contains piper diagrams, stiff diagrams, and pie charts. Two wells show slight impacts based on this data. Well 13A has higher total dissolved solids and bicarbonate ( $\text{HCO}_3$ ) compared to other wells. Well 14A shows the most impact based on the graphs. This well has less sulfate ( $\text{SO}_4$ ) and more chloride (Cl) relative to other wells. Both wells are downgradient of the impoundments, but well 14A could also be affected by the wastewater treatment plant. Well 14A is to be removed for expansion of the WWTP.

1,1-Dichloroethane was detected at wells 11-B (DNR, EDI) and 14A (EDI), at 1.2 to 4.0 ppb. Arsenic was detected at wells 11A, 11B, 13B, and 14A by both DNR and EDI from 2.1 to 6.6 ppb. EDI also detected arsenic at

11-D and 12-B, which DNR did not sample. Sulfate concentrations are high, upgradient and downgradient. Manganese values exceed secondary drinking water standards, and iron values are high. Both parameters are elevated in the upgradient well #1, although DNR results show higher iron in wells 13B and 14A. Historically, 1,1-dichloroethane has been detected in wells 11A, 11B, and 14A, although not always at "statistically significant" levels based on the groundwater assessment plan statistical procedure.


In summary, the impacts on groundwater quality have been minor from the impoundments. The parameters in question are 1,1-dichloroethane (low ppb range) and arsenic (low ppb range). There has been no proposed remediation for either parameter, although the company contends that the arsenic is naturally occurring from deeper in the aquifer.

## APPENDIX A

### CROSS-SECTIONS



Figure E.3  
Traces of the Geologic  
Cross Sections  
Quanex  
Michigan Seamless Tube Division  
January, 1986 20454



	Gravel
	Sand
	Silt
	Clay
	Clay, Sand and Gravel or Rock Fragments
	Clay with Sand
	Clay with Silt
	Silt with Sand and Gravel
	Silt with Sand
	Sand with Gravel
	Peat
	Clay, Silt and Sand
	Silt with Sand and Gravel
	Wood and Metal Fill

	Well Screen and Water
911.6	Level Recorded 10-23-85
	Division Between Outwash and Interbedded Silt, Clay and Sand
	Contour of Piezometric Surface
	Water Table
	Piezometric Contour Interval: 1 foot

Horizontal Scale 1" = 100'  
 Vertical Scale 1" = 25'  
 Vertical Exaggeration 4:1

A

A'




Figure E.5

## Geologic Cross Section A-A'

Quanex  
Michigan Seamless Tube Division  
December, 1985

20454

B

B'




Figure E.6

Geologic Cross Section B-B'

Quanex  
Michigan Seamless Tube Division

December, 1985

20454

C

C'




Figure E.7  
Geologic Cross Section C-C'

Quanex  
Michigan Seamless Tube Division  
December, 1985 20454

D

D'




Figure E.8  
 Geologic Cross Section D-D'  
 Quanex  
 Michigan Seamless Tube Division  
 December, 1985 20454




Figure E.9  
 Geologic Cross Section E-E'  
 Quanex  
 Michigan Seamless Tube Division  
 December, 1985 20454




Figure E.10  
 Geologic Cross Section F-F'  
 Quanex  
 Michigan Seamless Tube Division  
 December, 1985 20454



APPENDIX B

GROUNDWATER CONTOUR MAP

ATTACHMENT A  
 QUANEX CORPORATION, Michigan Seamless Tube Division  
 Updated: 11/12/87


Water level data

WELL	T.O.C.	3/11/87 S.W.L.	5/18/87 S.W.L.	8/18/87 S.W.L.	from 11/12/87 TOC	11/12/87 S.W.L.	elev. ground	elev. screen
1	920.62	908.71	908.77	908.31	12.39	908.23	918.3	901.0
2	921.42	broken	broken	broken	NM		918.4	899.6
3	915.02	906.53	906.46	906.00	8.92	906.10	911.7	898.9
4	907.94	903.81	903.45	902.79	4.47	903.46	904.7	895.2
5	909.25	904.62	904.00	903.44	4.76	904.49	907.2	895.5
6 A	914.03	906.20	905.99	905.75	8.24	905.79	911.7	898.3
6 B	913.46	905.84	905.52	905.25	8.04	905.42	911.8	876.8
7 A	914.94	906.39	906.17	905.85	8.98	905.95	914.3	895.2
7 B	915.63	905.91	905.57	905.28	10.11	905.52	914.3	854.9
8	910.86	NM	NM	NM	NM	NM	900.5	NM
9	921.48	910.55	910.84	910.29	11.34	910.14	920.5	900.5
11 A	921.00	906.58	906.52	906.04	14.86	906.14	918.5	894.2
11 B	921.05	906.08	905.97	905.44	15.41	905.64	918.5	885.0
11 C	921.97	905.77	905.44	905.09	16.69	905.28	918.5	859.3
11 D	920.77	905.76	905.42	905.05	15.5	905.27	918.2	848.3
12 A	918.12	910.92	911.75	910.59	7.59	910.53	916.2	902.3
12 B	918.15	906.59	906.50	906.03	12.02	906.13	916.1	874.7
12 C	918.38	906.64	906.44	905.92	12.16	906.22	915.9	854.5
13 A	920.52	910.88	911.65	910.68	9.96	910.56	917.5	899.0
13 B	920.31	906.60	906.53	906.01	13.61	906.70	917.6	868.3
13 C	920.12	907.13	906.74	906.31	13.45	906.67	917.7	845.9
14 A	914.02	906.44	906.36	905.94	7.84	906.18	911.4	899.3
14 B	914.25	906.33	906.19	905.80	8.34	905.91	911.5	882.4
15 A	913.37	906.25	906.05	905.84	7.45	905.92	910.6	901.6
15 B	913.30	905.96	905.71	905.43	7.7	905.59	910.6	878.8
16 A	915.32	906.54	906.44	906.04	9.22	906.10	912.8	900.9
16 B	915.65	906.14	905.93	905.65	9.86	905.79	913.2	884.0

GROUNDWATER CONTOUR MAP

QUANEX

FROM 1987 Annual Report  
(dated 1-29-88)  
STATS TAKEN 11-12-87  
EDI Engineering + Science



## APPENDIX C

### LAB COMPARISON OF DATA

# ATTACHMENT B

## ANALYTICAL RESULTS FROM FIRST QUARTERLY SAMPLING IN 1988

### QUANEX CORPORATION, MICHIGAN SEAMLESS TUBE DIVISION

SAMPLED ON FEBRUARY 10, 1988

(Metal analyses for monitoring well 14A and 16A sampled on 2/17/88

due to defective filter during initial sampling)

	Units	Detection Limit	Well 1	Well 11-A	Well 11-B	M.W. 11-D	M.W. 12-A	M.W. 12-B
1,1-Dichloroethane	ug/l	1	<1	**	3.5	<1	<1	<1
Arsenic	ug/l	2.0	<2.0	2.1	4.0	6.0	<2.0	8.0
Barium	mg/l	0.1	0.31	0.47	0.32	0.34	0.15	0.27
Cadmium	mg/l	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
Copper	mg/l	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
Chromium	mg/l	0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Lead	mg/l	0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Selenium	ug/l	2.0	2.4	<2.0	<2.0	<2.0	10	<2.0
Silver	mg/l	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
*Conductivity (Field)	umhos/cm	5	1,745	1,758	1,676	859	1,212	1,550
pH (field)	standard	NA	7.32	7.57	7.42	7.43	7.66	7.41
	Units	Detection Limit	M.W. 13-A	M.W. 13-B	M.W. 14-A	M.W. 16-A	Field Blank	Trip Blank
1,1-Dichloroethane	ug/l	1	<1	<1	1.2	<1	<1	<1
Arsenic	ug/l	2.0	<2.0	5.5	6.6	<2.0	<2.0	<2.0
Barium	mg/l	0.1	0.57	0.26	0.26	0.32	<0.10	<0.10
Cadmium	mg/l	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
Copper	mg/l	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
Chromium	mg/l	0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Lead	mg/l	0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Selenium	ug/l	2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Silver	mg/l	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
*Conductivity (Field)	umhos/cm	5	2,161	1,799	1,714	1,638	NA	NA
pH (field)	standard	NA	7.15	7.25	7.28	7.37	NA	NA

< - Not detected at the indicated detection limit.

NA - Not analyzed.

\* - Temperature adjusted.

\*\* - Sample vial broken upon log-in.

FEB. 10, 1988

Quanex Corp., South Lyons

MID 082 767 591

Parameter	mg/l unless noted	MW1	MW11A	MW11B	MW13A	MW13B	MW14A	Field
Alkalinity		103	136	120	308	142	350	<5.0
Carbonate Alk		<5	<5	<5	<5	<5	<5	<5
Bicarbonate Alk		103	136	120	308	142	350	<5
Chloride		47	74	78	44	50	170	<1.0
Arsenic		<0.002	0.0034	0.004	<0.002	0.004	0.0066	<0.002
Barium		0.034	0.072	0.022	0.125	0.026	0.118	<0.01
Calcium		365	374	334	497	391	306	<1
Cadmium		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Chromium		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Copper		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Iron	dissolved	3.3	5.95	3.1	3.5	6.35	12.5	<0.1
Potassium		7.6	10.6	5.14	2.45	5.2	3.4	<0.1
Magnesium		32.2	34.2	37.5	78	53	19.7	<1
Manganese		0.995	0.885	0.45	0.9	0.36	0.17	<0.02
Sodium		84.1	61.3	61.9	61.1	54.6	73	<1
Nickel		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Lead		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Zinc		0.97	<0.05	<0.05	<0.05	<0.05	0.48	<0.05
Conductivity	umhos/cm	1880	1720	1680	2300	1645	1660	—
pH	su	6.5	6.8	6.8	6.6	6.8	6.6	—
Sulfate		1070	910	818	1120	1050	330	<2.0
1,1 Dichloroethane	mg/l	<1.0	<1.0	4.0	<1.0	<1.0	<1.0	<1.0
Others in Scan 1 *		< detection	< detection	< detection	< detection	< detection	< detection	< detection
Toluene		<1.0	<1.0	1.1 UC	<1.0	<1.0	<1.0	<1.0
Others in Scan 2 *		< detection	< detection	< detection	< detection	< detection	< detection	< detection

\* All volatile organic scan data coded HT

HT - The recommended maximum laboratory holding time was exceeded before analysis.

See attached list for organic scan parameters and detection limits.

MDNR Samples from 2/10/88 split sampling  
with Quanex. Samples analyzed at DNR lab.

Comparison of DNR and Company (EDI) Lab Results  
 Quanex Corp - Feb. 10, 1988

		1,1 DCE	As	Ba	Cd	Cu	Cr	Pb	pH	Conduct.
		ug/l	ug/l	mg/l	mg/l	mg/l	mg/l	mg/l	SU	umhos/cm
MW-1	DNR	K1.0	K2.0	0.034	K0.02	K0.02	K0.05	K0.05	6.50	1,880
	EDI	K1.0	K2.0	0.310	K0.01	K0.01	K0.05	K0.05	7.32	1,745
MW-11A	DNR	K1.0	3.4	0.072	K0.02	K0.02	K0.05	K0.05	6.80	1,720
	EDI	*	2.1	0.470	K0.01	K0.01	K0.05	K0.05	7.57	1,758
MW-11B	DNR	4.0	4.0	0.022	K0.02	K0.02	K0.05	K0.05	6.80	1,680
	EDI	3.5	4.0	0.320	K0.01	K0.01	K0.05	K0.05	7.42	1,676
MW-13A	DNR	K1.0	K2.0	0.125	K0.02	K0.02	K0.05	K0.05	6.60	2,200
	EDI	K1.0	K2.0	0.570	K0.01	K0.01	K0.05	K0.05	7.15	2,161
MW-13B	DNR	K1.0	4.0	0.026	K0.02	K0.02	K0.05	K0.05	6.80	1,645
	EDI	K1.0	5.5	0.260	K0.01	K0.01	K0.05	K0.05	7.25	1,799
MW-14A	DNR	K1.0	6.6	0.118	K0.02	K0.02	K0.05	K0.05	6.60	1,660
	EDI	1.2	6.6	0.260	K0.01	K0.01	K0.05	K0.05	7.28	1,714

K - less than

\* - sample vial broken upon log-in


APPENDIX D

GRAPHICAL ANALYSIS  
OF  
GROUNDWATER DATA



# LEGEND

- 1 - MW 1
- 2 - MW 11 A
- 3 - MW 11 B
- 4 - MW 13 A
- 5 - MW 13 B
- 6 - MW 14 A



PROJECT: GUANEX CORP.  
 FILE: MID 082 767 591  
 LOCATION: SOUTH LYONS MI.


PIPER TRILINEAR DIAGRAM

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE:



# STIFF GRAPH




PROJECT: QUANEX CORP  
 FILE: MID 082 767 591  
 LOCATION: SOUTH LYONS

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE:


# STIFF GRAPH




PROJECT: QUANEX CORP  
FILE: MID 082 767 591  
LOCATION: SOUTH LYONS

MICHIGAN DEPT. OF NATURAL RESOURCES


FIGURE:




MW 1



MW 11A



MW 11B




MW 13A

0 35 70

SCALE OF RADII  
(TOTAL OF EQUIVALENTS  
PER MILLION)

NOTE ERROR (IF ANY) IN CATION/ANION  
BALANCE HAS BEEN REMOVED




MW 13B

PROJECT: QUANEX CORP  
FILE: MID 082 767 591  
LOCATION: SOUTH LYONS

PIE DIAGRAMS  
SHOWING WATER QUALITY

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE:



0 20 40

SCALE OF RADII  
(TOTAL OF EQUIVALENTS  
PER MILLION)

NOTE ERROR (IF ANY) IN CATION/ANION  
BALANCE HAS BEEN REMOVED

PROJECT: QUANEX CORP  
FILE: MID 082 767 591  
LOCATION: SOUTH LYONS

PIE DIAGRAMS  
SHOWING WATER QUALITY

MICHIGAN DEPT. OF NATURAL RESOURCES

FIGURE:

# CHEMISTRY ANALYSIS

PROJECT: GUANEX CORP  
LOCATION: SOUTH LYONS

FILE: MID 082 767 591

WELL NO.: MW 1

CATIONS	PPM	EPM	% EPM
Ca	365.00	18.21	73.70
Mg	32.20	2.65	10.71
Na+K	91.70	3.85	15.59

ANIONS	PPM	EPM	% EPM
HCO3+CO3	108.00	1.85	7.29
SO4	1070.00	22.28	87.51
Cl	47.00	1.33	5.21

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 1.24 %  
SODIUM ABSORPTION RATION (S.A.R.): 1.13

WELL NO.: MW 11A

CATIONS	PPM	EPM	% EPM
Ca	374.00	18.66	76.45
Mg	34.20	2.81	11.52
Na+K	71.90	2.94	12.03

ANIONS	PPM	EPM	% EPM
HCO3+CO3	141.00	2.40	10.23
SO4	910.00	18.95	80.87
Cl	74.00	2.09	8.91

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 3.45 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.8

# CHEMISTRY ANALYSIS

PROJECT: QUANEX CORP  
LOCATION: SOUTH LIONS

FILE: MID 082 767 371

WELL NO.: MW 11B

CATIONS	PPM	EPM	% EPM
Ca	334.00	16.67	73.53
Mg	37.50	3.08	13.66
Na+K	67.04	2.82	12.51

ANIONS	PPM	EPM	% EPM
HCO3+CO3	125.00	2.13	9.99
SO4	818.00	17.03	79.72
Cl	78.00	2.20	10.30

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 3.00 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.86

WELL NO.: MW 13A

CATIONS	PPM	EPM	% EPM
Ca	497.00	24.80	73.08
Mg	78.00	6.41	18.90
Na+K	63.55	2.72	8.02

ANIONS	PPM	EPM	% EPM
HCO3+CO3	313.00	5.21	17.51
SO4	1120.00	23.32	78.32
Cl	44.00	1.24	4.17

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 6.72 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.67



# CHEMISTRY ANALYSIS

PROJECT: QUANEX CORP  
LOCATION: SOUTH LYONS

FILE: MID 082 7&7 591

WELL NO.: MW 13E

CATIONS	PPM	EPM	% EPM
Ca	391.00	19.51	73.97
Mg	53.00	4.36	16.32
Na+K	59.80	2.51	9.51

ANIONS	PPM	EPM	% EPM
HCO3+CO3	147.00	2.49	9.68
SO4	1050.00	21.86	84.85
Cl	50.00	1.41	5.47

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 1.60 %  
SODIUM ABSORPTION RATION (S.A.R.): 0.69

MICHIGAN DEPT. OF NATURAL RESOURCES

CHEMISTRY ANALYSIS

---

PROJECT: QUANEX CORP  
LOCATION: SOUTH LYONS

FILE: MID 052 767 591

WELL NO.: MW 14A

CATIONS	PPM	EPM	% EPM
Ca	306.00	15.27	75.77
Mg	19.70	1.62	8.04
Na+K	76.40	3.26	16.19

ANIONS	PPM	EPM	% EPM
HCO <sub>3</sub> +CO <sub>3</sub>	355.00	5.90	33.80
SO <sub>4</sub>	330.00	6.87	39.11
Cl	170.00	4.79	27.29

TOTAL DISSOLVED SOLIDS:  
ERROR IN CATION/ANION BALANCE: 7.94 %  
SODIUM ABSORPTION RATION (S.A.R.): 1.09

MICHIGAN DEPT. OF NATURAL RESOURCES

Quarrier  
MKD 082 969 591

Feb 23, 1988

Dave Slayton

Quarrier, Don Comfort

## RCRA PART 265

### SUBPART F

### ERTEC INSPECTION FORMS

#### Reference Documents

- Feb 1986  
① Groundwater Quality Assent Program April 1986 by ERTI  
② Part B App. Jan 1986

Neutralized pickle liquor sludge generated here has been de-listed effective 12/5/84 (June 5, 1984 Federal Register Vol. 49, No. 109). The water in the lagoons was not, and the company has submitted a delisting petition.

Groundwater monitoring continues quarterly under a groundwater assessment program (h1 Dichloroethane and arsenic).

Company is going to close the two impoundments, and go to treatment in tanks.

APPENDIX - A

COMPLIANCE CHECKLIST FORMS

APPENDIX A-1

FACILITY INSPECTION FORM FOR COMPLIANCE WITH INTERIM  
STATUS STANDARDS COVERING GROUND-WATER MONITORING

Company Name: Quamex ; EPA I.D. Number: MI0 082 767 591

Company Address: 400 McMunn ; Inspector's Name: Don Clayton  
South Lyon, MI  
48178

Company Contact/Official: Don Comfort ; Branch/Organization: \_\_\_\_\_

Title: Engineering Manager ; Date of Inspection: 2-23-88

Type of facility: (check appropriately)	<u>Yes</u>	<u>No</u>	<u>Unknown</u>	<u>Waived</u>
a) surface impoundment	<u>✓</u>	<u>      </u>		
b) landfill	<u>      </u>	<u>✓</u>		
c) land treatment facility	<u>      </u>	<u>✓</u>		
d) disposal waste pile*	<u>      </u>	<u>✓</u>		

(2 S.I.)  
- sludge dewatered  
- water still has  
but a petition  
is in to delist

Ground-Water Monitoring Program

1. Was the ground-water monitoring program reviewed prior to site visit?  
If "No",

a) Was the ground-water program reviewed at the facility prior to site inspection?

2. Has a ground-water monitoring program (capable of determining the facility's impact on the quality of groundwater in the uppermost aquifer underlying the facility) been implemented? 265.90(a)

<u>✓</u>	<u>      </u>		
<u>✓</u>	<u>      </u>		
<u>✓</u>	<u>      </u>	<u>      </u>	<u>      </u>

\*Listed separate from landfill for convenience of identification.

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
d) The potential for hazardous waste or hazardous waste constituents which may enter the uppermost aquifer to migrate to a water supply well or surface water, by evaluation of: 265.90(c)(2)			
1) Saturated zone characteristics, including:			
(a) Geologic materials?	_____	_____	
(b) Physical properties?	_____	_____	
(c) Rate of ground-water flow?	_____	_____	
2) Proximity of the facility to water supply wells or surface water?	_____	_____	

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>	<u>Waived</u>
3. Has at least one monitoring well been installed in the uppermost aquifer hydraulically upgradient from the limit of the waste management area? 265.91(a)(1)	<u>✓</u>	<u>(mw1)</u>		
a) Are ground-water samples from the uppermost aquifer, representative of background ground-water quality and not affected by the facility (as ensured by proper well number, locations and depths?)	<u>✓</u>			
4. Have at least three monitoring wells been installed hydraulically downgradient at the limit of the waste handling or management area? 265.91(a)(2)	<u>✓</u>			
a) Do well number, locations and depths ensure prompt detection of any statistically significant amounts of HW or HW constituents that migrate from the waste management area to the uppermost aquifer?	<u>✓</u>			
5. Have the locations of the waste management areas been verified to conform with information in the ground-water program?	<u>✓</u>			
a) If the facility contains multiple waste management components, is each component adequately monitored?	<u>N.A.</u>	<u>impounds are next together</u>		
6. Do the numbers, locations, and depths of the ground-water monitoring wells agree with the data in the ground-water monitoring system program? If "No", explain discrepancies.	<u>✓</u>			
7. Well completion details. 265.91(c)				
a) Are wells properly cased?	<u>✓</u>			
b) Are wells screened (perforated) and packed where necessary to enable sampling at appropriate depths?	<u>✓</u>			
c) Are annular spaces properly sealed to prevent contamination of ground-water?	<u>✓</u>			

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
8. Has a ground-water sampling and analysis plan been developed? 265.92(a)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
a) Has it been followed?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
b) Is the plan kept at the facility?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
c) Does the plan include procedures and techniques for:			
1) Sample collection?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2) Sample preservation?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3) Sample shipment?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4) Analytical procedures?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5) Chain of custody control?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9. Are the required parameters in ground-water samples being tested quarterly for the first year? 265.92(b) and 265.92 (c)(1)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
a) Are the ground-water samples analyzed for the following: <i>started 12/83</i>			
1) Parameters characterizing the suitability of the ground-water as a drinking water supply? 265.92(b)(1)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2) Parameters establishing ground-water quality? 265.92(b)(2)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
3) Parameters used as indicators of ground-water contamination? 265.92(b)(3)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(i) For each indicator parameter are at least four replicate measurements obtained at each upgradient well for each sample obtained during the first year of monitoring? 265.92(c)(2)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
(ii) Are provisions made to calculate the initial background arithmetic mean and variance of the respective parameter concentrations or values obtained from the upgradient well(s) during the first year? 265.92(c)(2)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
b) For facilities which have completed first year ground-water sampling and analysis requirements:			
1) Have samples been obtained and analyzed for the ground-water quality parameters at least annually? 265.92(d)(1)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2) Have samples been obtained and analyzed for the indicators of ground-water contamination at least semi-annually? 265.92(d)(2)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

*New Browne Lib*

*April 1986  
Asent Plan  
contains  
the STA plan*



	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
c) Were ground-water surface elevations determined at each monitoring well each time a sample was taken? 265.92(e)	<u>✓</u>	_____	
d) Were the ground-water surface elevations evaluated annually to determine whether the monitoring wells are properly placed? 265.93(f)	<u>✓</u>	_____	
e) If it was determined that modification of the number, location or depth of monitoring wells was necessary, was the system brought into compliance with 265.91(a)? 265.93(f)	<u>N.A.</u>	_____	
10. Has an outline of a ground-water quality assessment program been prepared? 265.93(a)*	<u>✓</u>	_____	
a) Does it describe a program capable of determining:			
1) Whether hazardous waste or hazardous waste constituents have entered the ground water?	<u>✓</u>	_____	
2) The rate and extent of migration of hazardous waste or hazardous waste constituents in ground water?	<u>✓</u>	_____	
3) Concentrations of hazardous waste or hazardous waste constituents in ground water?	<u>✓</u>	_____	
b) After the first year of monitoring, have at least four replicate measurements of each indicator parameter been obtained for samples taken for each well? 265.93(b)	<u>✓</u>	_____	
1) Were the results compared with the initial background means from the upgradient well(s) determined during the first year?	<u>✓</u>	_____	
(i) Was each well considered individually?	<u>✓</u>	_____	
(ii) Was the Student's t-test used (at the 0.01 level of significance)?	<u>✓</u>	_____	
2) Was a significant increase (or pH decrease as well) found in the:			
(i) Upgradient wells	<u>✓</u>	_____	
(ii) Downgradient wells	<u>✓</u>	_____	
If "Yes", Compliance Checklist A-2 must also be completed.			

12/83  
3/84  
6/84  
9/84

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
11. Have records been kept of analyses for parameters in 265.92(c) and (d)? 265.94(a)(1)	<u>✓</u>	<u>      </u>	<u>      </u>
12. Have records been kept of ground-water surface elevations taken at the time of sampling for each well? 265.94(a)(1)	<u>✓</u>	<u>      </u>	<u>      </u>
13. Have records been kept of required elevations in 265.93(b)? 265.94(a)(1)	<u>✓</u>	<u>      </u>	<u>      </u>
14. Have the following been submitted to the Regional Administrator 265.94(a)(2) :*			
a) Initial background concentrations of parameters listed in 265.92(b) within 15 days after completing each quarterly analysis required during the first year?	<u>✓</u>	<u>      </u>	<u>      </u>
b) For each well, have any parameters whose concentrations or values have exceeded the maximum contaminant levels allowed in drinking water supplies been separately identified?	<u>✓</u>	<u>      </u>	<u>      </u>
c) Annual reports including:			
1) Concentrations or values of parameters used as indicators of ground-water contamination for each well along with required evaluations under 265.93(b)?	<u>✓</u>	<u>      </u>	<u>      </u>
2) Any significant differences from initial background values in up-gradient wells separately identified?	<u>✓</u>	<u>      </u>	<u>      </u>
3) Results of the evaluation of ground-water surface elevations?	<u>✓</u>	<u>      </u>	<u>      </u>

latest one dated  
Jan 29, 1988  
to MONR

also send  
quarterly updates  
from asnd. monitoring

\*EPA will be proposing (Spring 1982) to replace this reporting requirement with an exception reporting system where reports will be submitted only where maximum contaminant levels or significant changes in the contamination indicators or other parameters are observed. EPA has delayed compliance stage for 14 a) above until August 1, 1982 (Federal Register, February 23, 1982, p.7841-7842) to be coupled with exception reporting in the interim.

APPENDIX A-2

INSPECTION COMPLIANCE FORM FOR A FACILITY WHICH  
MAY BE AFFECTING GROUND-WATER QUALITY

Company Name: Quannet; EPA I.D. Number: \_\_\_\_\_

Company Address: \_\_\_\_\_; Inspector's Name: D. Slattery

Company Contact/Official: \_\_\_\_\_; Branch/Organization: \_\_\_\_\_

Title: \_\_\_\_\_; Date of Inspection: 2/23/88

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
Type of facility: (Check appropriately)			
a) surface impoundment	<u>✓</u>	_____	_____
b) landfill	_____	<u>✓</u>	_____
c) land treatment facility	_____	<u>✓</u>	_____
d) disposal waste pile	_____	<u>✓</u>	_____
1. Have comparisons of ground-water contamination indicator parameters for the upgradient well(s) 265.93(b) shown a significant increase (or pH decrease as well) over initial background?	<u>✓</u>	_____	_____
a) If "Yes", has this information been submitted to the Regional Administrator according to 265.94(a)(2)(ii)?	<u>✓</u>	_____	_____
2. Have comparisons of indicator parameters for the downgradient wells 265.93(b) shown a significant increase (or pH decrease as well) over initial background?	<u>✓</u>	_____	_____
a) If "Yes", were additional ground-water samples taken for those downgradient wells where the significant difference was determined? 265.93(c)(2)	<u>✓</u>	_____	_____
1) Were samples split in two?	<u>✓</u>	_____	_____
2) Was the significant difference due to human (e.g., laboratory) error? (If "Yes", do not continue.)	_____	<u>✓</u>	_____

*Initial  
report by  
Kock  
6/5/85*

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
3. If significant differences were not due to error, was a written notice sent to the Regional Administrator within 7 days of confirmation?	<u>✓</u>	<u>      </u>	5/8/85 to EPA
4. Within 15 days of notification of the Regional Administrator was a certified ground-water quality assessment plan submitted? 265.93(d)(2)*	<u>      </u>	<u>✓</u>	6/5/85
a) Does the plan specify 265.93(d)(3) :	- updated April 1986 in response to N.O.D.		
1) well information (specifics)	<u>✓</u>	<u>      </u>	
(a) number?	<u>✓</u>	<u>      </u>	
(b) locations?	<u>✓</u>	<u>      </u>	
(c) depths?	<u>✓</u>	<u>      </u>	
2) sampling methods?	<u>✓</u>	<u>      </u>	
3) analytical methods?	<u>✓</u>	<u>      </u>	
4) evaluation methods?	<u>✓</u>	<u>      </u>	
5) schedule of implementation?	<u>✓</u>	<u>      </u>	
b) Does the plan allow for determination of 265.93(d)(4) :			
1) Rate and extent of migration of hazardous waste or hazardous waste constituents?	<u>✓</u>	<u>      </u>	
2) Concentrations of the hazardous waste or hazardous waste constituents?	<u>✓</u>	<u>      </u>	
c) Is it indicated that the first determination was made as soon as technically feasible? 265.93(d)(5)	<u>✓</u>	<u>      </u>	
1) Within 15 days after the first determination was a written report containing the assessment of ground-water quality submitted to the Regional Administrator?	<u>✓</u>	<u>      </u>	First report on accident sent to Joe Baker in letter dated 12-4-86
d) Was it determined that hazardous waste or hazardous waste constituents from the facility have entered the ground water?	<u>✓</u>	<u>      </u>	
1) If "No", was the original indicator evaluation program, required by 265.92 and 265.93(b), reinstated?	<u>      </u>	<u>      </u>	N.A.
(a) Was the Regional Administrator notified of the reinstatement of program within 15 days of the determination? 265.93(d)(6)	<u>      </u>	<u>      </u>	N.A.

- |   | <u>Yes</u>                          | <u>No</u>                | <u>Unknown</u>                            |
|---|-------------------------------------|--------------------------|---|
| e) If it was determined that hazardous waste or hazardous waste constituents have entered the ground water 265.93(d)(7) :   |                                     |                          |   |
| 1) For facilities where program was implemented prior to final closure, are determinations of hazardous waste or hazardous waste constituents continued on a quarterly basis?<br>(If program was implemented during the post-closure care period, determinations made in accordance with the ground-water quality assessment plan may cease after the first determination.) | <input checked="" type="checkbox"/> | <input type="checkbox"/> |   |
| (a) Were subsequent ground-water quality reports submitted to the Regional Administrator within 15 days of determination?   | <input checked="" type="checkbox"/> | <input type="checkbox"/> | To EPA, and now to DNR quarterly          |
| 2) Were records kept of the analyses and evaluations, specified in the ground-water quality assessment (throughout the active life of the facility)?<br>265.94(b)(1)  | <input checked="" type="checkbox"/> | <input type="checkbox"/> |   |
| (a) If a disposal facility, were(are) records kept throughout the post-closure period as well?  | <input checked="" type="checkbox"/> | <input type="checkbox"/> | N.A.                                      |
| f) Are annual reports submitted to the Regional Administrator containing the results of the ground-water quality assessment program?<br>265.94(b)(2)*   | <input checked="" type="checkbox"/> | <input type="checkbox"/> | - 1st one 1-29-87<br>dated 1-29-88 to DNR |
| 1) Do the reports include the calculated or measured rate of migration of hazardous waste or hazardous waste constituents during the reporting period?  | <input checked="" type="checkbox"/> | <input type="checkbox"/> |   |

\*See note Page 4-3

APPENDIX A-3

INSPECTION COMPLIANCE FORM FOR DEMONSTRATING  
A WAIVER OF INTERIM STATUS REQUIREMENTS

Company Name: \_\_\_\_\_; EPA I.D. Number: \_\_\_\_\_

Company Address: \_\_\_\_\_; Inspector's Name: \_\_\_\_\_

Company Contact: \_\_\_\_\_; Branch/Organization: \_\_\_\_\_

Title: \_\_\_\_\_; Date of Inspection: \_\_\_\_\_

	<u>Yes</u>	<u>No</u>	<u>Unknown</u>
1. Is a written waiver demonstration kept at the site?	_____	_____	
2. Is the demonstration certified by a qualified geologist or geotechnical engineer? 265.90(c)	_____	_____	
3. Does the waiver demonstration establish:			
a) The potential for migration of hazardous waste or hazardous waste constituents from the facility to the uppermost aquifer? 265.90(c)(1)	_____	_____	
b) An evaluation of a water balance including:			
1) Precipitation?	_____	_____	
2) Evapotranspiration?	_____	_____	
3) Runoff?	_____	_____	
4) Infiltration? (including any liquid in surface impoundments)	_____	_____	
c) Unsaturated zone characteristics?	_____	_____	
1) Geologic materials?	_____	_____	
2) Physical properties?	_____	_____	
3) Depth to ground water?	_____	_____	

APPENDIX -B

GROUND-WATER MONITORING AND ALTERNATE SYSTEM  
TECHNICAL INFORMATION FORM

APPENDIX B

GROUND-WATER MONITORING AND ALTERNATE SYSTEM  
TECHNICAL INFORMATION FORM

1.0 Background Data:

Company Name: Quanex; EPA I.D.#: MID 082 767 591

Company Address: 400 McMunn  
South Lyon, MI  
48178

Inspector's Name: DAVID SLAYTON; Date: 2/23/88

1.1 Type of facility (check appropriately):

- 1.1.1 surface impoundment ☒
- 1.1.2 landfill ☐
- 1.1.3 land treatment facility ☐
- 1.1.4 disposal waste pile ☐

*Refer to April 86  
Asst Plan and  
Jan 1986 Part B*

1.2 Has a ground-water monitoring system been established?

(Y/N) Y

1.2.1 Is a ground-water quality assessment program outlined or proposed?

(Y/N) Y

If Yes,

1.2.2 Was it reviewed prior to the site visit?

(Y/N) Y

1.3 Has a ground-water quality assessment program been implemented or proposed at the site?

(Y/N) Yes

If yes, Appendix C, Ground-Water Quality Assessment Program Technical Information Form must be utilized also.

2.0 Regional/Facility Map(s)

2.1 Is a regional map of the area, with the facility delineated, included?

(Y/N) Yes

If yes,

2.1.1 What is the origin and scale of the map? Various - top maps  
and site specific maps

2.1.2 Is the surficial geology adequately illustrated?

(Y/N) No



2.1.3 Are there any significant topographic or surficial features evident?

(Y/N) No

If yes, describe \_\_\_\_\_

2.1.4 Are there any streams, rivers, lakes, or wet lands near the facility?

(Y/N) Yes

If yes, indicate approximate distances from the facility

Yerkes Drain immediately  
south of plant 500-600'  
swamp 50' to west of S.I.

2.1.5 Are there any discharging or recharging wells near the facility?

(Y/N) Yes

If yes, indicate approximate distances from the facility.

Municipal well upgradient  
about 1/2 mile (to east) from S.I.  
closest domestic 1/2 mile to west

Refer to  
Assessment Plan  
April 1986

2.2 Is a regional hydrogeologic map of the area included?  
(This information may be shown on 2.1)

(Y/N) No

If yes:

2.2.1 Are major areas of recharge/dischARGE shown?

(Y/N) \_\_\_\_\_

If yes, describe. \_\_\_\_\_

2.2.2 Is the regional ground-water flow direction indicated?

(Y/N) \_\_\_\_\_

2.2.3 Are the potentiometric contours logical?  
If not, explain. \_\_\_\_\_

(Y/N) \_\_\_\_\_

2.3 Is a facility plot plan included?

(Y/N) Yes

2.3.1 Are facility components (landfill areas, impoundments, etc.) shown?

(Y/N) Yes

2.3.2 Are any seeps, springs, streams, ponds, or wetlands indicated?

(Y/N) Yes

2.3.3 Are the locations of any monitoring wells, soil borings, or test pits shown?

(Y/N) Y

2.3.4 Is the facility a multi-component facility?

(Y/N) No

If yes:

2.3.4.1 Are individual components adequately monitored?

(Y/N) Yes

2.3.4.2 Is a Waste Management Area delineated?

(Y/N) Yes

2.4 Is a site water table (potentiometric) contour map included?

(Y/N) Yes

If yes,

2.4.1 Do the potentiometric contours appear logical based on topography and presented data? (Consult water level data)

(Y/N) Yes

2.4.2 Are groundwater flowlines indicated?

(Y/N) Yes

2.4.3 Are static water levels shown?

(Y/N) Yes

2.2.4 May hydraulic gradients be estimated?

(Y/N) Yes

2.4.5 Is at least one monitoring well located hydraulically upgradient of the waste management area(s)?

(Y/N) Yes

2.4.6 Are at least three monitoring wells located hydraulically downgradient of the waste management area(s)?

(Y/N) Yes

2.4.7 By their location, do the upgradient wells appear capable of providing representative ambient groundwater quality data?

(Y/N) Yes - new well 1

If no, explain. - may install upgradient wells deeper in aquifer to assess whether arsenic is naturally occurring deeper in the aquifer

3.0 Soil Boring/Test Pit Details

3.1 Were soil borings/test pits made under the supervision of a qualified professional?

(Y/N) Yes

If yes,

3.1.1 Indicate the individual(s) and affiliation(s): well 1-9 ?  
well 11 16 by EOI  
(no well 10) -

3.1.2 Indicate the drilling/excavating contractor, if known EOI

3.2 If soil borings/test pits were made, indicate the method(s) of drilling/excavating:

- Auger (hollow or solid stem) ✓ hollow
- Mud rotary \_\_\_\_\_
- Air rotary \_\_\_\_\_
- Reverse rotary \_\_\_\_\_
- Cable tool \_\_\_\_\_
- Jetting \_\_\_\_\_
- Other, including excavation (explain) \_\_\_\_\_

3.3 List the number of soil borings/test pits made at the site

3.3.1 Pre-existing \_\_\_\_\_

3.3.2 For RCRA compliance 29

(includes Those That had wells installed. Detection + Assessment)

3.4 Indicate borehole diameters and depths (if different diameters and depths use TABLE B-1).

3.4.1 Diameter: see table

3.4.2 Depth: \_\_\_\_\_

3.5 Were lithologic samples collected during drilling?

(Y/N) Yes

If yes,

3.5.1 How were samples obtained? (Check method(s))

- Split spoon ✓
- Shelby tube, or similar \_\_\_\_\_
- Rock coring \_\_\_\_\_
- Ditch sampling \_\_\_\_\_
- Other (explain) \_\_\_\_\_

INFORMATION TABLE B-1

	BORING NO.	DEPTH	DIAMETER
Aug. 1983	SB-1	50'	4"
	SB-2	35'	"
	SB-3	25'	"
	SB-4	30'	"
	SB-5	30'	"
Oct. 1985	SB-18	20'	unknown
	SB-19	20'	
	SB-20	20'	
	SB-21	20'	
	SB-22	20'	
	SB-23	30'	
	SB-24	30'	
	SB-25	30'	
	SB-26	25'	
<u>no well logs</u>			
MW 1, 2, 3			
4, 5, 8, 9			
<u>monitor well</u>			
clusters - deepest boring			
	6	39'	
	7	75'	
	11	75'	
	12	75'	
	13	73'	
	14	30'	
	15	35'	
	16	30'	

3.5.2 At what interval were samples collected? 5'

3.5.3 Were the deposits or rock units penetrated described? (boring logs, etc.) (Y/N) Yes

3.6 If test pits were excavated at the site, describe procedures. None

#### 4.0 Well Completion Detail

4.1 Were the wells installed under the supervision of a qualified professional? (Y/N) Yes

If yes:

wells 11-16

4.1.1 Indicate the individual and affiliation, if known EDI  
Engineering & Science, Grand Rapids

4.1.2 Indicate the well construction contractor, if known EDI

4.2 List the number of wells at the site

4.2.1 Pre-existing

4.2.2 For RCRA Compliance

27

- not all used for monitoring

4.3 Well construction information (fill out INFORMATION TABLE B-2)

4.3.1 If PVC well screen or casing is used, are joints (couplings):

- Glued on
- Screwed on

☒

4.3.2 Are well screens sand/gravel packed? (Y/N)     

See page 37  
of Mon  
plan

Monitor well numbers

1, 2, 3, 4, 5, 6A, 6B,

7A, 7B, 8, 9, 11A, 11B,

11C, 11D, 12A, 12B, 12C, 13A, 13B, 13C,

14A, 14B, 15A, 15B, 16A, 16B

See page 39 of Asmnt Plan  
(April 1986)  
and 1987 Annual Report

INFORMATION TABLE B-2

Info. from → page 44 of Jan 86 Pat B

WELL NO.		MW1	MW2	MW3	MW4	MW5	ORIGINAL ALPHA WELLS MW1-4
GROUND ELEVATION ≈		918.6	918.4	912.2	904	905	
TOTAL DEPTH ≈		17.6	19.0	13'	9'	9.5'	
WELL CASING	TYPE MATERIAL	galvanized steel →					
	DIAMETER	2"	2"	2"	2"	2"	
	LENGTH ≈	17'	19'	13'	10'	11'	
	STICK-UP ≈	2.4'	3'	3'	4.2'	3.6'	
	TOP ELEVATION	921.01	921.42	915.22	908.21	909.41	
	BOTTOM ELEVATION	904.0	902.6	901.9	898.2	898.5	
WELL SCREEN	DEPTH TOP/BOTTOM	/	/	/	/	/	
	TYPE MATERIAL	stainless steel →					
	DIAMETER	2"	2"	2"	2"	2"	
	LENGTH	3'	3'	3'	3'	3'	
	SLOT SIZE	unknown →					
	TOP ELEVATION	904.0	902.6	901.9	898.2	898.5	
	BOTTOM ELEVATION	901.0	899.6	898.9	895.2	895.5	
OPEN HOLE OR SAND/GRAVEL PACK	DEPTH TOP/BOTTOM	/	/	/	/	/	
	DIAMETER						
	LENGTH						
	TOP ELEVATION						
	BOTTOM ELEVATION						

4.3.3 Are annular spaces sealed?

(Y/N) Yes

If yes, describe:

- bentonite slurry
- Cement grout
- Other (explain)

✓

- Thicknesses of seals from above screens to surface (bentonite slurry)

4.3.4 If "open hole" wells, are the cased portions sealed in place? (Y/N) NO

If yes, describe how:

4.3.5 Are there cement surface seals?

(Y/N) Yes

If yes,

- How thick? 1'

4.3.6 Are the wells capped?

(Y/N) Y

If yes,

- Do they lock?

(Y/N) Y

4.3.7 Are protective standpipes cemented in place?

(Y/N) Y (except 1-5)

4.3.8 Were wells developed?

(Y/N) Yes

If yes, check appropriate method(s):

- Air lift pumping
- Pumping and surging
- Jetting
- Bailing
- Other (explain)

(P)

unknown

## 5.0 Aquifer Characterization

5.1 Has the extent of the uppermost saturated zone (aquifer) in the facility area been defined?

(Y/N) Yes

If yes,

5.1.1 Are soil boring/test pit logs included?

(Y/N) Yes

5.1.2 Are geologic cross-sections included?

(Y/N) Yes

5.2 Is there evidence of confining (low permeability) layers beneath the site?

(Y/N) Yes

(northern portion only)

If yes,

5.2.1 Is the areal extent and continuity indicated?

(Y/N) Yes

5.2.2 Is there any potential for saturated conditions (perched water) to occur above the uppermost aquifer? (Y/N) NO

If yes, give details: \_\_\_\_\_

a) Should or is this perched zone being monitored?

(Y/N) N.A.

Explain \_\_\_\_\_

5.2.3 What is the lithology and texture of the uppermost saturated zone (aquifer)?

glacial outwash  
(fine sand to gravel)

5.2.4 What is the saturated thickness, if indicated?

15-30' in north  
70+ feet in south

5.3 Were static water levels measured?

(Y/N) Yes

If yes,

5.3.1 How were the water levels measured (check method(s)).

- Electric water sounder
- Wetted tape
- Air line
- Other (explain)

✓

5.3.2 Do fluctuations in static water levels occur?

(Y/N) yes

If yes,

5.3.2.1 Are they accounted for (e.g. seasonal, tidal, etc.)?

(Y/N) Yes

If yes, describe: \_\_\_\_\_

seasonal



(Y/N) NO

5.3.2.3 Will the effectiveness of the wells to detect contaminants be reduced?

(Y/N)

## Explain

5.3.2.4 Based on water level data, do any head differentials occur that may indicate a vertical flow component in the saturated zone? (

(Y/N) Yes

If yes, explain - downward near impoundments  
due to mounding away from  
SI (lateral and vertical) head is upward

5.4 Have aquifer hydraulic properties been determined?

(Y/N) Yes

5.4.1 Indicate method(s):

In situ sling tests on 4 wells

- Pumping tests
- Falling/constant head tests
- Laboratory tests (explain)

- see Staffer  
quarterly report

Cover-Rice Method

5.4.2 If determined, what are the values for:

- Transmissivity
- Storage coefficient
- Leakage
- Permeability
- Porosity
- Specific capacity

5.4.3 In cases where several tests were undertaken, were discrepancies in the results evident?

(Y/N) No

If yes, explain

5.4.4 Were horizontal ground-water flow velocities determined?

(Y/N) Yes

If yes, indicate rate of movement 1980 annual report (0.02 ft/day max)  
March 1987 report (0.14 ft/day max)

6.0 Well Performance

6.1 Are the monitoring wells screened in the uppermost aquifer? (Y/N) Yes

6.1.1 Is the full saturated thickness screened? (Y/N) No

6.1.2 For single completions, are the intake areas in the:  
(check appropriate levels)

- Upper portion of the aquifer
- Middle of the aquifer
- Lower portion of the aquifer

✓ ✓ ✓ (some wells have 4 clusters)

6.1.3 For well clusters, are the intake areas open to different portions of the aquifer? (Y/N) Yes

6.1.4 Do the intake levels of the monitoring wells appear to be justified due to possible contaminant density and groundwater flow velocity? (Y/N) Yes

7.0 Ground-Water Quality Sampling

7.1 Is a sampling (groundwater quality) program and schedule included? (Y/N) Yes

7.2 Are sample collection field procedures clearly outlined? (Y/N) Yes

7.2.1 How are samples obtained: (check method(s))

- Air lift pump
- Submersible pump
- Positive displacement pump
- Centrifugal pump
- Peristaltic or other suction-lift pump
- Bailer
- Other (describe)

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

✓ (stainless steel + teflon)

7.2.2 Are all wells sampled with the same equipment and procedures? (Y/N) Yes

If no, explain \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

7.2.3 Are adequate provisions included to clean equipment after sampling to prevent cross-contamination between wells? (Y/N) Yes

7.2.4 Are organic constituents to be sampled?

(Y/N) Yes

If yes,

7.2.4.1 Are samples collected with equipment to minimize absorption and volatilization?

(Y/N) Yes

If yes,

Describe equipment bailers, lowered slowly into well.

8.0 Sample Preservation and Handling

8.1 Have appropriate sample preservation and preparation procedures been followed (filtration and preservation where appropriate)?

(Y/N) Y

8.2 Are samples refrigerated?

(Y/N) Y

8.3 Are EPA recommended sample holding period requirements adhered to?

(Y/N) Y

8.4 Are suitable container types used?

(Y/N) Y

8.5 Are provisions made to store and ship samples under cold conditions (ice packs, etc.)?

(Y/N) Y

8.6 Is a chain of custody control procedure clearly defined?

(Y/N) Y

8.7 Is a specific chain of custody form illustrated?

(Y/N) Y

If yes,

8.7.1 Will this form provide an accurate record of sample possession from the moment the sample is taken until the time it is analyzed?

(Y/N) Y

9.0 Sample Analysis and Record Keeping

9.1 Is sample analysis performed by a qualified laboratory?

(Y/N) Y

Indicate lab EDI lab, Grand Rapids

9.2 Are analytical methods described in the records?

(Y/N) Y

9.2.1 Are analytical methods acceptable to EPA?

(Y/N) Y

9.3 Are the required drinking water suitability parameters tested for?

(Y/N) Y

9.4 Are the required groundwater quality parameters tested for?

(Y/N) Y

9.5 Are the required groundwater contamination indicator parameters tested for? (Y/N) Y

9.6 Are any analytical parameters determined in the field? (Y/N) Y

Identify:

- pH ✓
- Temperature ✓
- Specific conductance ✓
- Other (describe) \_\_\_\_\_

9.7 Is a plan included to record information about each sample collected during the groundwater monitoring program? (Y/N) Yes

9.7.1 Are field activity logs included? (Y/N) Yes

9.7.2 Are laboratory results included? (Y/N) Yes

9.7.3 Are field procedures recorded? (Y/N) Yes

9.7.4 Are field parameter determinations included? (Y/N) Yes

9.7.5 Are the names and affiliation of the field personnel included? (Y/N) Yes

9.8 Are statistical analyses planned or shown for all water quality results where necessary? (Y/N) Yes - under Asmt. Program

9.8.1 Is an analysis program set-up which adheres to EPA guidelines? (Y/N) Y

9.8.2 Is Student's t-test utilized? (Y/N) Y  
If other evaluation procedure used, identify with continuity correction

9.8.3 Are provisions made for submitting analysis reports to the Regional Administrator? (Y/N) Yes - done quarterly

#### 10.0 Site Verification

10.1 Plot Plan indicating the locations of various facility components, ground-water monitoring wells, and surface waters? (Y/N) Yes

10.1.1 Is the plot plan used for the inspection the same as in the monitoring program plan documentation? (Y/N) Yes

If not, explain \_\_\_\_\_

10.1.2 Are all of the components of the facility identified during the inspection addressed in the monitoring program documentation? (Y/N) Yes

If not, explain \_\_\_\_\_

10.1.3 Are there any streams, lakes or wetlands on or adjacent to the site? (Y/N) Yes

If yes, indicate distances from waste management areas \_\_\_\_\_

swamp to west, Yerkes Drain south  
of plant

10.1.4 Are there any signs of water quality degradation evident in the surface water bodies? (Y/N) No

If yes, explain \_\_\_\_\_

10.1.5 Is there any indication of distressed or dead vegetation on or adjacent to the site? (Y/N) No

If yes, explain \_\_\_\_\_

10.1.6 Are there any significant topographic or surficial features on or near the site (e.g., recharge or discharge areas)? (Y/N) No

If yes, explain \_\_\_\_\_

10.1.7 Are the monitor well locations and numbers in agreement with the monitoring program documentation? (Y/N) Yes

If no, explain \_\_\_\_\_

10.1.7.1 Were locations and elevations of the monitor wells surveyed into some known datum? (Y/N) Yes

If not, explain U.S.G.S.

was resurveyed  
to check 1987

10.1.7.2 Were the wells sounded to determine total depth below the surface?

(Y/N) Yes

If not, explain \_\_\_\_\_

10.1.7.3 Were discrepancies in total depth greater than two feet apparent in any well?

(Y/N) NO

If yes, explain \_\_\_\_\_

10.1.8 Was ground water encountered in all monitoring wells?

(Y/N) Yes

If not, indicate which well(s) were dry \_\_\_\_\_

10.1.9 Were water level elevations measured during the site visit?

(Y/N) Yes

If yes, indicate well number and water level elevation \_\_\_\_\_

If not, explain \_\_\_\_\_

Well #	steel tape consultant EDT	electronic meter DNR measure	(Both on 2/10/88) Depth (DNR) measured	well log or measured in ft. (Point B) Depth	
MW 1	11.82 <sup>+0.1</sup>	11.93	19.0'	17.6' (2.4' stickup)	OK
MW 11A	14.63 <sup>+0.28</sup>	14.71	27.5'	24.5' (2.6' stickup)	OK
MW 11B	15.07 <sup>+0.22</sup>	15.29	37'	33.8' (2.5' stickup)	OK
MW 13A	9.84 <sup>+0.0</sup>	9.94	22'	18.8' (3' " )	OK
MW 13B	13.95 <sup>+0.05</sup>	14.00	53'	49.6' (2.7' " )	OK
MW 14A	7.84 <sup>+0.09</sup>	7.91	15'	12.3' (2.6' " )	OK

STATICS

DNR Readings  
consistently  
higher than  
EDT

from  
top of  
casing  
Depth

from  
ground  
surface



APPENDIX - C

GROUND-WATER QUALITY ASSESSMENT PROGRAM  
INFORMATION FORM





APPENDIX C

GROUND-WATER QUALITY ASSESSMENT PROGRAM  
INFORMATION FORM

Company Name: Quamex; EPA I.D.#: M10 082 767 591

Company Address: 400 McMunn  
South Lyons, MI  
48178

Inspector's Name: David Slayton; Date: 2/23/88

1.0 Background

1.1 List the constituents (contaminants) originating from the waste management area: (use separate sheet if necessary) triggered on pH, spec. conductance, TOC, TOX  
- now concentrating on Arsenic + 1,1 Dichloroethane  
in next plan

1.2 Have the concentrations of the hazardous waste or hazardous waste constituents shown significant increases in:

- upgradient monitoring wells
- downgradient monitoring wells

(Y/N)

(Y/N) ☒

(Arsenic  
1,1 Dichloro-  
ethane)

1.2.1 List or indicate on a map, the wells which have shown significant increases: (use separate sheet if necessary) 11B, 11D, 12B, 13B, 14A

1.3 Were the significant increases in contaminant concentration determined through the use of the student's t-Test?

(Y/N) Yes

If no,

with continuity  
correction

1.3.1 Explain procedure used \_\_\_\_\_

1.4 Has the possibility of error (e.g., laboratory) been eliminated? (Y/N) Yes

1.4.1 Explain \_\_\_\_\_

## 2.0 Contaminant Characteristics

2.1 If available, list the chemical and physical properties of the contaminants which have been detected in the ground water: (density, solubility, etc.). Include on a separate sheet if list is extensive Arsenic, 1,1 dichloroethane

### 3.0 Implementation of the Assessment Program

3.1 Has the extent of the migration of hazardous waste or hazardous waste constituents been determined?

(Y/N) No -  
study ongoing;  
some work is done.

If yes,

3.1.1 Indicate how: (check appropriate method(s))

- additional ground-water monitoring wells
- geophysical methods
- computer simulation
- other, explain.

3.2 Were monitoring wells installed?

(Y/N) Yes

If yes,

3.2.1 Record monitoring well/peizometer completion data on INFORMATION TABLE C-1.

3.2.2 Were well clusters (nests) used or were wells with multiple intake areas constructed? Give details yes - clusters at 11, 12, 13, 14, 15, 16

3.2.3 Show the numbers and locations of the additional wells/peizometers on a site map.

3.2.4 Are the locations of the wells/piezometers justified in view of the water table or potentiometric surface map?  
Give details

(Y/N) Yes

C-1  
INFORMATION TABLE

ALL WELLS INSTALLED NOV. 1985  
INFO FROM JAN 1986 PART B, p. 44

WELL NO.		11A	11B	11C	11D	12A	12B
GROUND ELEVATION		918.7	918.8	918.7	918.6	916.3	916.2
TOTAL DEPTH ≈		24.5	34'	59.5'	70.3'	14'	41.5
WELL CASING	TYPE MATERIAL	PVC	PVC	galv. steel	PVC	PVC	PVC
	DIAMETER	2"	2"	2"	2"	2"	2"
	LENGTH ≈	22.1	31.3	59'	69.8'	11.1	38.7
	STICK-UP ≈	2.6'	2.5'	2.6'	2.5'	2.1	2.2
	TOP ELEVATION	921.29	921.34	921.31	921.07	918.45	918.44
	BOTTOM ELEVATION	899.2	890.0	862.3	853.3	907.3	879.7
WELL SCREEN	DEPTH TOP/BOTTOM	19.5 24.5	28.8 33.8	56.4 59.4	65.3 70.3	9.0 14.0	36.5 41.5
	TYPE MATERIAL	PVC	PVC	stainless steel	PVC	PVC	PVC
	DIAMETER	2"	2"	2"	2"	2"	2"
	LENGTH	5'	5'	3'	5'	5'	5'
	SLOT SIZE	#10	#10	#7	#10	#10	#10
	TOP ELEVATION	899.2	890.0	862.3	853.3	907.3	879.7
	BOTTOM ELEVATION	894.2	885.0	859.3	848.3	902.3	874.7
OPEN HOLE OR SAND/GRAVEL PACK	DEPTH TOP/BOTTOM						
	DIAMETER						
	LENGTH						
	TOP ELEVATION						
	BOTTOM ELEVATION						



C-1  
INFORMATION TABLE

WELL NO.		12C	13A	13B	13C	14A	14B
GROUND ELEVATION		916.3	917.8	917.9	918.0	911.6	911.7
TOTAL DEPTH ≈		62'	19'	50'	72'	12'	29'
WELL CASING	TYPE MATERIAL	PVC	PVC	PVC	PVC	PVC	PVC
	DIAMETER	2"	2"	2"	2"	2"	2"
	LENGTH ≈	59.1	16.8	47.3	69.5'	9.9'	27.1
	STICK-UP ≈	2.3'	3'	2.7'	2.4'	2.6'	2.8'
	TOP ELEVATION	918.66	920.81	920.61	920.39	914.21	914.54
	BOTTOM ELEVATION	859.5	904.0	873.3	850.9	904.3	887.4
WELL SCREEN	DEPTH TOP/BOTTOM	56.8 61.8	13.8 18.8	44.6 49.6	69.1 72.1	7.3 12.3	24.3 29.3
	TYPE MATERIAL	PVC	PVC	PVC	PVC	PVC	PVC
	DIAMETER	2"	2"	2"	2"	2"	2"
	LENGTH	5'	5'	5'	5'	5'	5'
	SLOT SIZE	#10	#10	#10	#10	#10	#10
	TOP ELEVATION	859.5	904.0	873.3	850.9	904.3	887.4
	BOTTOM ELEVATION	854.5	899.0	868.3	845.9	899.3	882.4
OPEN HOLE OR SAND/GRAVEL PACK	DEPTH TOP/BOTTOM						
	DIAMETER						
	LENGTH						
	TOP ELEVATION						
	BOTTOM ELEVATION						



INFORMATION TABLE C-1

WELL NO.		15A	15B	16A	16B		
GROUND ELEVATION		910.9	910.8	913.0	912.8		
TOTAL DEPTH ≈		9.3'	32'	12.1'	28.8'		
WELL CASING	TYPE MATERIAL	PVC	PVC	PVC	PVC		
	DIAMETER	2"	2"	2"	2"		
	LENGTH ≈	7.1	29.8	9.7	26.3		
	STICK-UP ≈	2.8	2.8	2.6	2.5		
	TOP ELEVATION	913.66	913.59	915.62	915.35		
	BOTTOM ELEVATION	906.6	883.8	905.9	889.0		-
WELL SCREEN	DEPTH TOP/BOTTOM	4.3 9.3	29.0 32.0	7.1 12.1	23.8 28.8		
	TYPE MATERIAL	PVC	PVC	PVC	PVC		
	DIAMETER	2"	2"	2"	2"		
	LENGTH	5'	5'	5'	5'		
	SLOT SIZE	#10	#10	#10	#10		
	TOP ELEVATION	906.6	883.8	905.9	889.0		
	BOTTOM ELEVATION	901.6	878.8	900.9	884.0		
OPEN HOLE OR SAND/GRAVEL PACK	DEPTH TOP/BOTTOM						
	DIAMETER						
	LENGTH						
	TOP ELEVATION						
	BOTTOM ELEVATION						



3.2.5 Are the depths of the monitoring wells/  
piezometers justified due to the relative  
characteristics (e.g., densities) of the contaminants? (Y/N) Yes  
Give details - have multiple levels

3.2.6 List any other methods (e.g., soil sample analysis)  
used to document the extent of the contamination.  
(use separate sheet if necessary) None

3.3 Has the rate of contaminant migration been determined? (Y/N) Yes

If yes, what is it and how was it determined? see 1987 annual report  
- calculations based on permeability (measured) and  
gradients.

3.3.1 Does the rate of migration differ for various  
contaminants? (Y/N) unknown  
Give details \_\_\_\_\_

3.3.2 If known, what is the cause (reason) of (for) this  
differential in migration rates? \_\_\_\_\_

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

INTEROFFICE COMMUNICATION

March 17, 1988

TO: Lynne King, Northville District Office, WMD  
FROM: Liz Browne, HW Permits, WMD *Liz*  
SUBJECT: Quanex Corp., Michigan Seamless Tube Division  
South Lyons, MID 082 767 591

On February 10, 1988 I conducted a sampling inspection at this facility as part of a Comprehensive Monitoring Evaluation (CME). Although no violations of 40 CFR 265.92 [as referenced in Act 64 R299.11003(m)] were found at this time, concerns were noted and are mentioned within the following inspection summary.

EDI Engineering and Science of Grand Rapids conducts all field and laboratory work for the facility. The Ground Water Quality Assessment Program, dated April, 1986, authored by EDI, contained the Sampling and Analysis Plan (SAP) that was used for this review.

Static water level readings are taken with a steel tape to the nearest 0.01 foot. The readings are taken to the top of the casing, and not to the top of the locking cap. Although this is stated in the plan, it should be emphasized to field staff should personnel change. Measurements compared reasonably well with those obtained with the DNR meter.

Purging is accomplished using either stainless steel or teflon bottom filling bailers and polypropylene rope. A new bailer, steam cleaned prior to the site visit, with new rope attached at the time of purging is used. Three casing volumes are purged prior to sampling. The purge water is directed into a graduated bucket to enable a volume measurement, and to facilitate the disposal of the water away from the well. The methods used to determine purge volume needed, method of measuring purge volume removed, and the disposal of the purge water should all be addressed in the plan.

Samples are obtained using the same equipment as, and immediately after, purging, where recovery allows. The plan states that the wells should be sampled within 24 hours of purging. Sampling immediately after purging is the preferable method. If this is not possible, recovery rates should be determined for each well, and sampling done as soon as sufficient volume exists.

Field measured parameters include pH and specific conductance. The meters are calibrated at the beginning of the day. The plan only mentions pH as a field parameter, and does not address the meter calibration. The plan should be updated to reflect field conditions. Other

field work includes the filtering of the metals sample immediately upon collection, prior to preservation. These are all excellent field methods to attempt to maintain the integrity of unstable parameters.

Field QA/QC procedures include the use of clean bailers and new line as already mentioned. Additionally, trip and equipment blanks and sample replicates are used to evaluate the sampling program. These are all good measures to help to assure that representative samples are taken. One item of concern noted during the sampling was the handling of the bailer during volatile organic sampling. The bailer should be lowered carefully for all sample collection, to reduce aeration, but especially for the volatile organics. A note to emphasize this may be appropriate in the plan. Other items of potential concern were not noted during this inspection. The sampling crew appeared to be familiar with the plan, worked carefully, and kept adequate field notes.

Chain of custody appears to be well documented. Field notes, bottle labels, a chain of custody form and an Analytical Services Project Sheet are used to track all samples. Copies of all forms have been included in the plan. Good control can be maintained since sample requests, bottle orders, sampling and analysis are all handled by EDI.

A list of sample parameters with sample container, preservation, holding time, minimum sample size and method references is included in the plan. A table indicating the detection limit attainable by EDI's laboratory is needed to complete this set of information. Also, the method references for some parameters appear to be in error. The Standard Methods reference should be 421, not 412 for dissolved oxygen. Nitrate-nitrite should be method 353 for reference 3, not 201. Reference 3 method 415 should be cited for organic carbon, not 236. All references should be rechecked. The latest editions of the references (SW-846 3rd edition and Standard Methods 16th edition) should be used. Specific methods should be cited, rather than items 200-289 for metals analysis.

A quality assurance/quality control program for EDI's laboratory is needed. Items such as the use of spikes, duplicate samples and standards should be included. The plan does indicate that lab notebooks are kept, and discusses some of the items to be included. This additional information is needed to assure that the careful practices that were evidenced in the field are maintained through the sample preparation and analysis steps.

In summary, both the written plan and the field work were acceptable in most areas. The plan needs to be updated to include details on purging and lab QA/QC. It should also be changed to better reflect the field measurement information, measuring both pH and specific conductance at the time of sampling, as well as the method and schedule of meter calibration. More information on the methods used to filter the samples, and to decontaminate this equipment should be included. Clarification on the time elapsed between purging and sampling should be made, and a note on the care needed for volatile organic sampling should be added. Finally, Table 13 should include detection limits, and the method references need to be checked and updated to reflect newer editions of the references, where applicable.

This concludes the sampling and analysis portion of the CME inspection. A final summary document (including a hydrogeo evaluation, statistical review, ground water contours, etc.) will be forthcoming.

Please call if you have any questions regarding this review.

cc Mr. D. Slayton  
Mr. J. Bohunsky  
Mr. D. Drake  
C&E File  
CME Reports ✓  
Ms. M. Sabadaszka, U.S. EPA-Region V

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Monitor Well/Groundwater Sampling Form

Facility: Quonex Location: S. Lyons  
Type of Facility: mfg of seamless steel tubing  
Contact: Don Confort Phone: ( )

WELL INFORMATION

Name/Number: MW1 Cap Locked: Yes ☒ No ☐  
Depth: 19 Casing Material: gal steel  
Diameter: 2" Screen Slot Size: unknown  
Casing Height Above Ground:            Screen Length: 3 ft.  
Top of Casing Elevation: 921.01 Screen Material: stainless steel  
Protective Barriers: Yes ☐ No ☒ Screen Packed: Yes ☐ No ☐

SAMPLING INFORMATION

Initial Static Water Level: 11.82 / 11.93  
Method: EDI steel tape 11.93 / electric meter 11.93  
Measured By: EDI / DNR  
Purge Method: teflon barker Vol Purged: 3.5 gal Recovery Rate:             
Stabilized pH: 6.5 Stabilized Conductance: 750  
Temperature:            Appearance: clear  
Staff Present: Brown / Slayton Date: 2/10/92

Notes: measured to top of casing, not locking cap screwed on top.  
Newly steam cleaned barker w/ polypropylene cap attached to the well  
Purge water poured into a graduated bucket for measurement

Large truck passed on road during (DNR) aerial filling - smells

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Monitor Well/Groundwater Sampling Form

Facility: Quonex Location: S. Lyon  
Type of Facility: mfg of stainless steel tubing  
Contact: Don Comfort Phone: ( )

WELL INFORMATION

Name/Number: 114 Cap Locked: Yes ☒ No ☐  
Depth: 227.5 Casing Material: PVC  
Diameter: 2" Screen Slot Size: 0.01"  
Casing Height Above Ground:        Screen Length: 5 ft.  
Top of Casing Elevation: 921.29 Screen Material: PVC  
Protective Barriers: Yes ☒ No ☐ Screen Packed: Yes ☐ No ☒

SAMPLING INFORMATION

Initial Static Water Level: 14.63 / 14.71  
Method: steel, chalked tape 14.63 / electric meter 14.71  
Measured By: EDI / MDNR  
Purge Method: SS boiler Vol Purged: 7 gals Recovery Rate: good  
Stabilized pH: 6.8 Stabilized Conductance: 1720  
Temperature:        Appearance: very rusty -> cloudy  
Staff Present: Browne / Slayton Date: 2-10-88

Notes:

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Monitor Well/Groundwater Sampling Form

Facility: Quonex Location: S. Lyons  
Type of Facility: mfg of seamless steel tubing  
Contact: Don Comfort Phone: ( )

WELL INFORMATION

Name/Number: 11B Cap Locked: Yes ☒ No ☐  
Depth: 37 Casing Material: PVC  
Diameter: 2" Screen Slot Size: 0.01"  
Casing Height Above Ground:            Screen Length: 5 ft.  
Top of Casing Elevation: 921.34 Screen Material: PVC  
Protective Barriers: Yes ☒ No ☐ Screen Packed: Yes ☐ No ☒

SAMPLING INFORMATION

Initial Static Water Level: 15.07 / 15.29  
Method: steel chalked tape 15.07 / electric meter 15.29  
Measured By: EDI / MDNR  
Purge Method: tetlon boiler Vol Purged: 11 gal Recovery Rate: good  
Stabilized pH: 6.8 Stabilized Conductance: 1680  
Temperature:            Appearance: very rusty ->  
Staff Present: Browne/Slayton Date: 2-10-88

Notes:

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Monitor Well/Groundwater Sampling Form

Facility: Quarx Location: S. Lyons  
Type of Facility: mfg. of seamless steel tubing  
Contact: Don Comfort Phone: ( )

WELL INFORMATION

Name/Number: MW 13A Cap Locked: Yes ☒ No ☐  
Depth: ~ 22' Casing Material: PVC  
Diameter: 2" Screen Slot Size: 0.01"  
Casing Height Above Ground:            Screen Length: 5 ft.  
Top of Casing Elevation: 920.81 Screen Material: PVC  
Protective Barriers: Yes ☒ No ☒ Screen Packed: Yes ☐ No ☒  
casing

SAMPLING INFORMATION

Initial Static Water Level: 9.84 / 9.94  
Method: steel, chalked tap 9.84 / electric meter 9.94  
Measured By: EDI / MDNR  
Purge Method: as barker Vol Purged: 2 1/3 gal Recovery Rate: good  
Stabilized pH:            Stabilized Conductance:             
Temperature:            Appearance: silty  
Staff Present: Browne / Stayton Date: 2-10-88

Notes:



MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Monitor Well/Groundwater Sampling Form

Facility: Quonex Location: S. Lyons  
Type of Facility: mfg of <sup>seamless</sup> steel tubing  
Contact: Don Comfort Phone: ( )

WELL INFORMATION

Name/Number: MW 13B Cap Locked: Yes ☒ No ☐  
Depth: 53' Casing Material: PVC  
Diameter: 2" Screen Slot Size: 0.01"  
Casing Height Above Ground:            Screen Length: 5 ft.  
Top of Casing Elevation: 920.61 Screen Material: PVC  
Protective Barriers: Yes ☒ No ☒ Screen Packed: Yes ☐ No ☒

SAMPLING INFORMATION

Initial Static Water Level: 13.95 / 14.00  
Method: Steel, chalked tap / electric meter  
Measured By: EDI / MDNR  
Purge Method: 4000 bbl Vol Purged: 20 gal Recovery Rate: 90%  
Stabilized pH:            Stabilized Conductance:             
Temperature:            Appearance: silt on bottom, water clear  
Staff Present: Brown / Clayton Date: 2-10-88

Notes:

MW13C-13.17

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Monitor Well/Groundwater Sampling Form

Facility: Quonlex Location: S. Lyons  
Type of Facility: \_\_\_\_\_  
Contact: Don Comfort Phone: ( ) \_\_\_\_\_

WELL INFORMATION

Name/Number: MW 14A Cap Locked: Yes ☒ No ☐  
Depth: 15' Casing Material: PVC  
Diameter: 3" Screen Slot Size: 0.01"  
Casing Height Above Ground: \_\_\_\_\_ Screen Length: 5 ft.  
Top of Casing Elevation: 914.21 Screen Material: PVC  
Protective Barriers: Yes ☒ No ☐ Screen Packed: Yes ☐ No ☒

SAMPLING INFORMATION

Initial Static Water Level: 7.84 / 7.91  
Method: EDI / electric meter  
Measured By: steel chalked tape / \_\_\_\_\_  
Purge Method: S.S. Diver Vol Purged: 3.5 gal Recovery Rate: good  
Stabilized pH: 6.6 Stabilized Conductance: 1660  
Temperature: \_\_\_\_\_ Appearance: very silty  
Staff Present: Browne / Slayton Date: 2-10-88

Notes:

EDI vehicle running during this well sampling - parked ~ 25' from well, weren't directly upwind

DNR sampling staff: Browne / Clayton

Facility sampling staff: EDI - Gary Bauwens / Don Johnson

(if purging and/or sampling methods differ, report facility method/DNR method)

Monitor Well#	MW1	MW3A	MW3B	MW14A	MW11A	MW11B
SWL (and method used)	11.82 / 11.93	9.84 / 9.94	13.95 / 14.00	7.84 / 7.91	14.63 / 14.71	15.07 / 15.29
Sounding ft	19	64.22	53'	15	27.5	37
Volume Purged gal	3.5	6 1/3	20	3.5	7	11
Purging Method	ref. bailer	ss bailer	teflon bailer	ss bailer	ss bailer	ref. bailer
Sampling Method	" "	" "	" "	ss bailer	ss bailer	ref. bailer
Lysimeter#						
Volume Purged						
Sampling Method						
Surface Water#						
Description						
Sampling Method						
Detection System#						
Sampling Method						
Private Well #						
Location Sampled						
Length of Time Purged						

Facility Sampling Notes:

Potential External Sources of Contamination: other than light truck traffic none noted

Precautions Taken: none noted

Field Measurements Taken: pH + spec cond - calibrated first

Handling/Preservation: as appropriate - field filter, then preserve

Sampling Bottles Used: as appropriate

Replicates and/or Blanks Taken: various replicates + 2 field blank

Decontamination Procedures: new bailer / well - changed rope

Additional Notes: turning metals & volatiles only (pH + spec in field) - GW Assessment should lower bailer more carefully for volatiles

MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Hazardous Waste Division

Geotechnical Subunit

Sampling Data Sheet

FACILITY: Quanex LOCATION: South Lyons  
CONTACT: Don Comfort

Sample#		MW1	MW13A	MW13B	MW14A	MW11A	MW11B	FB
Date		2-10-88	2-10-88	2-10-88	2-10-88	2-10-88	2-10-88	2-10-88
Time		1145	1230	1235	1255	1325	1335	1340
pH (field)		6.5	6.6	6.8	6.6	6.8	6.8	-
Conductivity (field)		1880	2200	1645	1660	1720	1680	-
PO	1	✓	✓	✓	✓	✓	✓	✓
PO	2	✓	✓	✓	✓	✓	✓	✓
OBN	3,4,6,7,9							
OA	8							
OG	oil & grease							
MA/D	basic 6/Fe	✓	✓	✓	✓	✓	✓	✓
	Ca/Mg/Na/K	✓	✓	✓	✓	✓	✓	✓
	Mn/As/Sr/Sr Ba	✓	✓	✓	✓	✓	✓	✓
MN	Cl/SO <sub>4</sub> /Alk	✓	✓	✓	✓	✓	✓	✓
	HCO <sub>3</sub> /CO <sub>3</sub>	✓	✓	✓	✓	✓	✓	✓
	Fluoride/Cr <sup>+6</sup>							
GA	COD/TOC							
	NO <sub>3</sub> NO <sub>2</sub> /NH <sub>3</sub>							
	Kjel N/TotP							
	Phenols							
GB	Total/Free Cn							
					dk brown			
Sample Appearance		clear	↑ silt	clear	very silty	cloudy	very cloudy	-

Additional Notes: \_\_\_\_\_

EL 070  
4/87  
MATRIX = WATER

MICHIGAN DEPT OF NATURAL RESOURCES  
ENVIRONMENTAL LABORATORY  
ANALYSIS REQUEST SHEET

Page 1 of 2  
Not Expected  
SAFETY WARNING  
YES / NO - INFO ON BACK

LAB ORDER# 8802-041 PROJ CODE PRIORITY II RECEIVED AT LAB BY JLV DATE 2/11/88 9:45 AM

SUBMITTER DIVISION WMD DISTRICT OR OFFICE HW Permits CONTACT PERSON FOR QUESTIONS Liz Browne PHONE (517) - 373-2130

LOCATION Quonex, South Lyons COLLECTED BY Browne/Slayton TRANS TO

COST CENTER 90026 SEND RESULTS TO ATTENTION OF Liz Browne AT ADDRESS WMD - HW Permits

SAMPLE REMARKS please enter field data on to SAM (if different than above office) S. Ottawa Tower Lansing

SAMPLE NUMBER	FIELD ID OR DESCRIPTION	SAMPLE COLLECTED		SAMPLE INFORMATION	
		YY/MM/DD	HH:MM	pH	spec conc
01	MW 1	880210	1145	6.5	1880
02	MW 11A	880210	1325	6.8	1720
03	MW 11B	880210	1335	6.8	1680
04	MW 13A	880210	1230	6.6	2200
05	MW 13B	880210	1235	6.8	1645

GENERAL CHEMISTRY		ORGANICS		INORGANIC	
DO	Diss Oxygen ... 1 2 3 4 5	PO1	#1 Halocarbons 1 2 3 4 5	MA	Total Metals ..... 1 2 3 4 5
BN	α-Phos NO2- ... 1 2 3 4 5	PO2	#2 Aromatic HC 1 2 3 4 5	MAD	Diss-Field Filtered .. 1 2 3 4 5
	Residue SS .... 1 2 3 4 5		ON #3 Chloro HC +	MD	Diss-Lab Filtered .... 1 2 3 4 5
	Residue TDS ... 1 2 3 4 5		Pest & PCB .. 1 2 3 4 5		Ca Mg Na K ..... 1 2 3 4 5
	BOD Tot 5 day 1 2 3 4 5		DB GC/MS Base Neut 1 2 3 4 5		Cd Cr Cu Ni Pb Zn ... 1 2 3 4 5
	BOD Carb 5 day 1 2 3 4 5		OA #8 Phenols .... 1 2 3 4 5		Fe Co Li Mn ..... 1 2 3 4 5
	..... 1 2 3 4 5		OB Oil & Grease .. 1 2 3 4 5		Al Ba Be Mo Ti V .... 1 2 3 4 5
BA	COD ..... 1 2 3 4 5				Hg - Mercury ..... 1 2 3 4 5
	TOC ..... 1 2 3 4 5				As - Arsenic ..... 1 2 3 4 5
	NO3+NO2, NH3 . 1 2 3 4 5				Se - Selenium ..... 1 2 3 4 5
	KJEL N, Tot P . 1 2 3 4 5				Sb - Antimony ..... 1 2 3 4 5
	..... 1 2 3 4 5				..... 1 2 3 4 5
BB	Phenolics ..... 1 2 3 4 5				LOW LEVEL Ag ..... 1 2 3 4 5
					" " Cd ..... 1 2 3 4 5
BB	Total CN ..... 1 2 3 4 5				" " Cr Cu Ni Pb .. 1 2 3 4 5
	Free CN ..... 1 2 3 4 5				..... 1 2 3 4 5
BC	Fecal Coli .... 1 2 3 4 5				
	Total Coli .... 1 2 3 4 5				MN pH, Conductance ..... 1 2 3 4 5
					Cl, SO4, Total Alk ... 1 2 3 4 5
CA	Chlorophyll .... 1 2 3 4 5				HCO3- CO3- ..... 1 2 3 4 5
					CR+6 ..... 1 2 3 4 5
					Fluoride ..... 1 2 3 4 5
					..... 1 2 3 4 5

EL 070  
4/87  
MATRIX = WATER

MICHIGAN DEPT OF NATURAL RESOURCES  
ENVIRONMENTAL LABORATORY  
ANALYSIS REQUEST SHEET

Not Expected  
#### SAFETY WARNING ####  
YES / (NO) - INFO ON BACK

LAB ORDER# 8802-041 PROJ CODE \_\_\_\_\_ PRIORITY II RECEIVED AT LAB BY NW DATE TIME 2, 11, 88 9:45 AM PM

SUBMITTER: WMD DISTRICT: HW Permits CONTACT PERSON: Liz Browne PHONE: (517) - 373-2730  
DIVISION: OR OFFICE: FOR QUESTIONS:

LOCATION Quarx South Lyons COLLECTED BY Browne/Slayton TRANS TO

COST CENTER	90026	SEND RESULTS TO ATTENTION OF	Liz Browne	AT ADDRESS	WMD- HW Permits
SAMPLE REMARKS	Please enter field data on to SAM			(if different than above office)	S. Ottawa Tower Lansing

SAMPLE NUMBER	FIELD ID OR DESCRIPTION	SAMPLE COLLECTED		SAMPLE INFORMATION	
		YY/MM/DD	HH:MM	PH	spec cond.
06	MW 14A	880210	1255	6.6	1660
07	FB Field Blank	880210	1340	-	-
03					
04					
05					

## GENERAL CHEMISTRY

DO	Diss Oxygen	...	1	2	3	4	5	1	1
6N	a-Phos NO2-	...	1	2	3	4	5	1	6N1
	Residue SS	....	1	2	3	4	5	1	
	Residue TDS	...	1	2	3	4	5	1	
	.....		1	2	3	4	5	1	
	BOD Tot 5 day		1	2	3	4	5	1	
	BOD Carb 5 day		1	2	3	4	5	1	
	.....		1	2	3	4	5	1	
6A	COD	.....	1	2	3	4	5	1	
	TOC	.....	1	2	3	4	5	1	
	NO3+NO2, NH3	..	1	2	3	4	5	1	6A2
	KJEL N, Tot P		1	2	3	4	5	1	
	.....		1	2	3	4	5	1	
6B	Phenolics	.....	1	2	3	4	5	1	
6B	Total CN	.....	1	2	3	4	5	1	
	Free CN	.....	1	2	3	4	5	1	
BC	Fecal Coli	.....	1	2	3	4	5	1	
	Total Coli	.....	1	2	3	4	5	1	
CA	Chlorophyll	.....	1	2	3	4	5	1	

## ORGANICS

		1	2	3	4	5	6
PO1	#1 Halocarbons	1	2	3	4	5	6
PO2	#2 Aromatic HC	1	2	3	4	5	6
		1	2	3	4	5	6
ON	#3 Chloro HC + Pest & PCB	1	2	3	4	5	6
		1	2	3	4	5	6
OB	GC/MS Base Neut	1	2	3	4	5	6
		1	2	3	4	5	6
OA	#8 Phenols ....	1	2	3	4	5	6
		1	2	3	4	5	6
OG	Oil & Grease ..	1	2	3	4	5	6

\* \* \* \* SPECIAL REQUESTS \* \* \* \*

## INORGANIC

=X=									
MA	Total Metals	.....	1	2	3	4	5	1	1
MAD	Diss-Field Filtered	...	1	2	3	4	5	1	1
MD	Diss-Lab Filtered	.....	1	2	3	4	5	1	1
	Ca Mg Na K	.....	1	2	3	4	5	1	MA1
	Cd Cr Cu Ni Pb Zn	.....	1	2	3	4	5	1	MA2
	Fe Co Li Mn	.....	1	2	3	4	5	1	MA3
	Al Ba Be Mo Ti V	.....	1	2	3	4	5	1	MA4
	Hg - Mercury	.....	1	2	3	4	5	1	1
	As - Arsenic	.....	1	2	3	4	5	1	1
	Se - Selenium	.....	1	2	3	4	5	1	1
	Sb - Antimony	.....	1	2	3	4	5	1	1
	LOW LEVEL Ag	.....	1	2	3	4	5	1	1
	" " Cd	.....	1	2	3	4	5	1	1
	" " Cr Cu Ni Pb	..	1	2	3	4	5	1	MF1
-----Y-----									
MN	pH, Conductance	.....	1	2	3	4	5	1	MN1
	Cl, SO4, Total Alk	...	1	2	3	4	5	1	MN2
	HCO3- CO3=	.....	1	2	3	4	5	1	MN3
	CR+6	.....	1	2	3	4	5	1	1
	Fluoride	.....	1	2	3	4	5	1	1

MINNESOTA DEPARTMENT OF NATURAL RESOURCES  
ENVIRONMENTAL LABORATORY

REPORT Waste Management Division

TO Office Building

Location: W. 4000

ATTEN: L. B. G. W. E.

LABORATORY WORK ORDER # 82-02-041

WORK TO QUANEX - SOUTH AVENUE

P.O. # 80000

COST # 1115.00

RECEIVED 02/11/88 CLIENT NM

REPORTED

NUMBER OF SAMPLES 7

LAB CONTACT ON 12

NATURAL WATER

TEST	NW 1	NW 11A	NW 11B	NW 13A
UNITS				
Alkalinity of Water	103	136	120	308
mg CaCO <sub>3</sub> /l				
Carbonate Alkalinity	K 5	K 5	K 5	K 5
mg CaCO <sub>3</sub> /l				
Bicarbonate Alkalinity	103	136	120	308
mg CaCO <sub>3</sub> /l				
Chloride in Water	47	74	78	44
mg/l				
Arsenic - Dissolved	K 2.0	3.4	4.0	K 2.0
ug/l (Diss)				
Barium - Dissolved	34.0	72.0	22.0	125
ug/l (Diss)				
Calcium - Dissolved	365	374	334	497
mg/l (Diss)				
Cadmium - Dissolved	K 20	K 20	K 20	K 20
ug/l (Diss)				
Chromium - Dissolved	K 50	K 50	K 50	K 50
ug/l (Diss)				
Copper - Dissolved	K 20	K 20	K 20	K 20
ug/l (Diss)				
Iron - Dissolved	3300	5950	3100	3500
ug/l (Diss)				
Potassium - Dissolved	7.6	10.6	5.14	2.45
mg/l (Diss)				
Magnesium - Dissolved	32.2	34.2	37.5	78
mg/l (Diss)				
Manganese - Dissolved	995	885	450	900
ug/l (Diss)				
Sodium - Dissolved	84.1	61.3	61.9	61.1
mg/l (Diss)				
Nickel - Dissolved	K 50	K 50	K 50	K 50
ug/l (Diss)				
Lead - Dissolved	K 50	K 50	K 50	K 50
ug/l (Diss)				
Zinc - Dissolved	970	K 50	K 50	K 50
ug/l (Diss)				
FIELD - Conductivity	1880	1720	1680	2200
uohm/cm				

RECEIVED

APR 15 1988

Waste Management  
Division

TEST	MW 1	MW 11A	MW 11B	MW 13A
UNITS				
FIELD - pH of Water	6.5	6.8	6.3	6.6
pH				
Sulfate in Water	1070	910	812	1120
mg/l				

TEST	MW 13B	MW 14A	FIELD BLANK
UNITS			
Alkalinity of Water	142	350	K 5.0
mg CaCO <sub>3</sub> /l			
Carbonate Alkalinity	K 5	K 5	K 5
mg CaCO <sub>3</sub> /l			
Bicarbonate Alkalinity	142	350	K 5
mg CaCO <sub>3</sub> /l			
Chloride in Water	50	170	K 1.0
mg/l			
Arsenic - Dissolved	4.0	6.6	K 2.0
mg/l (Diss)			
Barium - Dissolved	26.0	118	K 10.0
mg/l (Diss)			
Calcium - Dissolved	391	306	K 1
mg/l (Diss)			
Cadmium - Dissolved	K 20	K 20	K 20
ug/l (Diss)			
Chromium - Dissolved	K 50	K 50	K 50
ug/l (Diss)			
Copper - Dissolved	K 20	K 20	K 20
ug/l (Diss)			
Iron - Dissolved	6350	12500	K 100
ug/l (Diss)			
Potassium - Dissolved	5.2	3.4	K .1
mg/l (Diss)			
Magnesium - Dissolved	53	19.7	K 1
mg/l (Diss)			
Manganese - Dissolved	360	170	K 20
ug/l (Diss)			
Sodium - Dissolved	54.6	73	K 1
mg/l (Diss)			
Nickel - Dissolved	K 50	K 50	K 50
ug/l (Diss)			
Lead - Dissolved	K 50	K 50	K 50
ug/l (Diss)			
Zinc - Dissolved	K 50	480	K 50
ug/l (Diss)			
FIELD - Conductivity	1645	1660	
uMho/cm			
FIELD - pH of Water	6.8	6.6	
pH			
Sulfate in Water	1050	330	K 2.0
mg/l			

Report prepared by: *D. Hartig 4-14-88*



SAMPLE ID XW 1 FRACTION OIA TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 02/10/89 11:45:00 Category

ANALYST KAJIYA  
ANALYZED 03/01/89  
SOLUTION 1

UNIT ug/L pbb

CAS#	COMPOUND	DETECTION	
		RESULT	REMARK
			LIMIT
75-01-4	Vinyl chloride	ND	5.0
74-85-9	*Bromomethane	ND	5.0
75-00-3	*Chloroethane	ND	5.0
75-69-4	*Trichlorofluoromethane	ND	5.0
75-35-4	1,1-Dichloroethane	ND	1.0
75-09-2	*Methylene chloride	ND	5.0
186-60-5	trans-1,2-Dichloroethane	ND	1.0
75-34-3	*1,1-Dichloroethane	ND	1.0
186-29-1	cis-1,2-Dichloroethane	ND	1.0
67-66-3	*Chloroform	ND	1.0
71-55-6	*1,1,1-Trichloroethane	ND	1.0
56-23-5	*Carbon tetrachloride	ND	1.0
107-06-2	*1,2-Dichloroethane	ND	1.0
79-01-6	Trichloroethene	ND	1.0
78-37-5	*1,2-Dichloropropane	ND	1.0
75-27-4	*Bromodichloromethane	ND	1.0
10061-01-5	cis-1,3-Dichloropropene	ND	1.0
10061-02-6	trans-1,3-Dichloropropene	ND	1.0
79-00-5	*1,1,2-Trichloroethane	ND	1.0
127-18-4	Tetrachloroethane	ND	1.0
124-48-1	*Dibromochloromethane	ND	1.0
108-90-7	Chlorobenzene	ND	5.0
75-25-2	*Bromoform	ND	1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND	1.0

COMMENTS HT

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 4  
Received: 02/11/88

DNR Laboratory  
Results by Sample

Work Order # 88-02-041

SAMPLE ID MM 1 FRACTION Q1A TEST DATE 88 2 NAME Scap 2 Water  
Date & Time Collected 02/10/88 11:45:00 Category

ANALYST KAJIYA  
ANALYSED 03/01/88  
DILUTION 1

UNITS ug/L ppb

CASE	COMPOUND	DETECTION	
		RESULT	REMARK
71-43-1	Benzene	ND	1.0
103-82-3	Toluene	ND	1.0
100-41-4	Ethylbenzene	ND	1.0
108-75-3	Xylene Isomers	ND	1.0

COMMENTS NT

ND = not detected at the specified detection limit.

SAMPLE TO MW 11A FRACTION 02A TEST CODE 80 1 NAME Scan 1 Water  
Date & Time Collected 02/10/88 13:25:00 Category

ANALYST KAJIYA  
ANALYSED 03/01/88  
SOLUTION 1

UNITS ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION LIMIT
75-01-4	Vinyl chloride	ND		5.0
75-23-9	*Bromooethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-69-4	*Trichlorofluoroethane	ND		5.0
75-35-4	1,1-Dichloroethane	ND		1.0
75-09-2	*Methylene chloride	ND		5.0
156-40-5	trans-1,2-Dichloroethane	ND		1.0
75-34-3	*1,1-Dichloroethane	ND		1.0
156-59-2	cis-1,2-Dichloroethane	ND		1.0
67-66-3	*Chloroform	ND		1.0
71-55-6	*1,1,1-Trichloroethane	ND		1.0
56-23-5	*Carbon tetrachloride	ND		1.0
107-06-2	*1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethane	ND		1.0
73-87-5	*1,2-Dichloropropane	ND		1.0
75-27-4	*Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	*1,1,2-Trichloroethane	ND		1.0
127-15-4	Tetrachloroethane	ND		1.0
124-48-1	*Dibromochloroethane	ND		1.0
108-90-7	Chlorobenzene	ND		5.0
75-25-2	*Bromoform	ND		1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 6  
Received: 02/11/88

DNR Laboratory  
Results by Sample

REPORT

Work Order # 88-02-041

SAMPLE ID HW 11A FRACTION 02A TEST TYPE GC 2 NAME Scan 2 Water  
Date & Time Collected 02/10/88 13:25:00 Category

ANALYST KAJIYA

ANALYZED 03/01/88

DILUTION 1

UNITS ug/L ppb

CASE	COMPOUND	RESULT	REMARK	DETECTION LIMIT
71-43-2	Benzene	ND		1.0
108-88-3	Toluene	ND		1.0
100-41-4	Ethylbenzene	ND		1.0
106-35-3	Xylene Isomers	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.

SAMPLE ID: WW 118 FRACTION: Q3A TEST CODE: SC 1 NAME: Gran. 1 Water  
Date & Time Collected: 02/10/88 13:35:00 Category: \_\_\_\_\_

ANALYST: KAJIYA  
ANALYZED: 03/01/88  
DILUTION: 1

UNITS: ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION
				LIMIT
75-01-4	Vinyl chloride	ND		5.0
74-07-9	*Bromomethane	ND		5.0
75-09-3	*Chloroethane	ND		5.0
75-19-4	*Trichlorofluoromethane	ND		5.0
75-25-4	1,1-Dichloroethene	ND		1.0
75-09-2	*Methylene chloride	ND		5.0
156-40-5	trans-1,2-Dichloroethene	ND		1.0
75-34-3	*1,1-Dichloroethane	4.0		1.0
156-59-2	cis-1,2-Dichloroethene	ND		1.0
67-66-3	*Chloroform	ND		1.0
71-55-6	*1,1,1-Trichloroethane	ND		1.0
56-23-5	*Carbon tetrachloride	ND		1.0
107-06-2	*1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethene	ND		1.0
78-87-5	*1,2-Dichloropropane	ND		1.0
75-27-4	*Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-09-5	*1,1,2-Trichloroethane	ND		1.0
127-10-4	Tetrachloroethene	ND		1.0
124-48-1	*Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		5.0
75-25-2	*Bromoform	ND		1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS: HT

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 8  
Received: 02/11/88

DNR Laboratory  
Results by Sample

REPORT

Work Order # 88-02-041

SAMPLE ID MM 11B FRACTION 03A TEST CODE SC 2 NAME Scan 2 Water  
Date & Time Collected 02/10/88 13:33:00 Category

ANALYST KAJIYA  
ANALYSED 03/01/88  
DILUTION 1

UNITS ug/L ppb

<u>CASE</u>	<u>COMPOUND</u>	<u>RESULT</u>	<u>REMARK</u>	<u>DETECTION</u> <u>LIMIT</u>
71-43-1	Benzene	ND		1.0
108-88-7	Toluene	1.1	UC	1.0
100-41-4	Ethylbenzene	ND		1.0
108-38-3	Xylene isomers	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.

SAMPLE ID MW 13A FRACTION 04A TEST CODE SC 1 NAME Scan 1 Meter  
Date & Time Collected 02/10/88 12:30:00 Category

ANALYST KAJIYA  
ANALYZED 03/01/88  
DILUTION 1

UNITS ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION LIMIT
75-01-4	Vinyl chloride	ND		5.0
74-87-7	*Bromomethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-49-4	*Trichlorofluoromethane	ND		5.0
75-35-4	1,1-Dichloroethane	ND		1.0
75-09-1	*Methylene chloride	ND		5.0
154-60-5	trans-1,2-Dichloroethane	ND		1.0
75-34-3	*1,1-Dichloroethane	ND		1.0
154-59-2	cis-1,2-Dichloroethane	ND		1.0
67-66-3	*Chloroform	ND		1.0
71-55-6	*1,1,1-Trichloroethane	ND		1.0
54-27-9	*Carbon tetrachloride	ND		1.0
107-06-2	*1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethane	ND		1.0
75-87-5	*1,2-Dichloropropane	ND		1.0
75-27-4	*Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-8	*1,1,2-Trichloroethane	ND		1.0
127-18-4	Tetrachloroethane	ND		1.0
124-48-1	*Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		5.0
75-25-1	*Bromoform	ND		1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 10  
Received: 02/11/88

DNR Laboratory  
Results by Sample

Work Order # 88-02-041

SAMPLE ID WH 13A FRACTION 04A TEST CODE SD 2 NAME Scan 2 Water  
Date & Time Collected 02/10/88 12:30:00 Category

ANALYST KAJIYA  
ANALYZED 03/01/88  
DILUTION 1

UNITS ug/L ppb

CASE	COMPOUND	RESULT	REMARK	DETECTION LIMIT
71-43-1	Benzene	ND		1.0
108-38-7	Toluene	ND		1.0
100-41-4	Ethylbenzene	ND		1.0
106-38-7	Xylene isomers	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.



SAMPLE ID NW 13B FRACTION 05A TEST CODE SC 1 NAME Scan 1 Water  
Date & Time Collected 02/10/88 12:35:00 Category \_\_\_\_\_

ANALYST KALIYA  
ANALYSED 03/01/88  
DILUTION 1

UNITS ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION
				LIMIT
75-01-4	Vinyl chloride	ND		5.0
75-23-9	*Bromomethane	ND		5.0
75-00-1	*Chloroethane	ND		5.0
75-69-4	*Trichlorofluoromethane	ND		5.0
75-35-4	1,1-Dichloroethane	ND		1.0
75-09-2	*Methylene chloride	ND		5.0
156-60-5	trans-1,2-Dichloroethane	ND		1.0
75-34-3	*1,1-Dichloroethane	ND		1.0
156-57-2	cis-1,2-Dichloroethane	ND		1.0
67-66-3	*Chloroform	ND		1.0
71-55-6	*1,1,1-Trichloroethane	ND		1.0
56-23-5	*Carbon tetrachloride	ND		1.0
107-06-2	*1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethane	ND		1.0
78-87-5	*1,2-Dichloropropane	ND		1.0
75-27-4	*Bromodichloromethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	*1,1,2-Trichloroethane	ND		1.0
127-13-4	Tetrachloroethane	ND		1.0
124-48-1	*Dibromochloromethane	ND		1.0
108-90-7	Chlorobenzene	ND		5.0
75-28-2	*Bromoform	ND		1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 12  
Received: 02/11/88

AWR Laboratory REPORT  
Results by Sample

Work Order # 88-02-041

SAMPLE ID: 24173

STATION: 05A TEST DATE: 88-2 NAME: 2nd Water  
Date & Time Collected: 02/10/88 12:35:00 Category:

ANALYST: KAJIYA  
ANALYZED: 02/01/88  
DILUTION: 1

UNITS: ug/L O&B

CASE#	COMPOUND	RESULT	REMARK	DETECTION LIMIT
75-02-0	Benzene	ND		1.0
02-00-0	Toluene	ND		1.0
00-01-0	Ethylbenzene	ND		1.0
00-02-0	Xylene Isomers	ND		1.0

COMMENTS: RT

ND = not detected at the specified detection limit.

SAMPLE ID NW 14A FRACTION 06A TEST CODE SC 1 NAME Scrap 1 Water  
Date & Time Collected 02/10/88 12:55:00 Category

ANALYST KAJIYA  
ANALYZED 03/01/88  
DILUTION 1

UNITS ug/L ppb

CAS#	COMPOUND	RESULT	REMARK	DETECTION
				LIMIT
75-01-4	Vinyl chloride	ND		5.0
74-87-3	*Bromooethane	ND		5.0
75-00-3	*Chloroethane	ND		5.0
75-59-4	*Trichlorofluoroethane	ND		5.0
75-75-4	1,1-Dichloroethane	ND		1.0
75-09-2	*Methylene chloride	ND		5.0
156-60-5	trans-1,2-Dichloroethane	ND		1.0
75-34-3	*1,1-Dichloroethane	ND		1.0
156-59-2	cis-1,2-Dichloroethane	ND		1.0
67-66-3	*Chloroform	ND		1.0
71-55-6	*1,1,1-Trichloroethane	ND		1.0
56-23-5	*Carbon tetrachloride	ND		1.0
107-06-2	*1,2-Dichloroethane	ND		1.0
79-01-6	Trichloroethane	ND		1.0
78-97-5	*1,2-Dichloropropane	ND		1.0
75-27-4	*Bromodichloroethane	ND		1.0
10061-01-5	cis-1,3-Dichloropropene	ND		1.0
10061-02-6	trans-1,3-Dichloropropene	ND		1.0
79-00-5	*1,1,2-Trichloroethane	ND		1.0
127-18-4	Tetrachloroethane	ND		1.0
124-48-1	*Dibromochloroethane	ND		1.0
109-90-7	Chlorobenzene	ND		5.0
75-28-2	*Bromoform	ND		1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 14  
Received: 02/11/88

DNR Laboratory REPORT  
Results by Sample

Work Order # 88-02-041

SAMPLE ID WN 144 FRACTION 06A TEST CODE SD 2 NAME San 2 Water  
Date & Time Collected 02/10/88 12:33:00 Category

ANALYST KAGIYA  
ANALYSED 03/01/88  
ELUTION 1

UNIT ug/L ppb

CASE#	COMPOUND	RESULT	REMARK	DETECTION
				LIMIT
71-43-1	Benzene	ND		1.0
105-EB-3	Toluene	ND		1.0
100-41-4	Ethylbenzene	ND		1.0
108-38-5	Xyle + isomers	ND		1.0

COMMENTS HT

ND = not detected at the specified detection limit.

SAMPLE NO FIELD BLANK

FRACTION 07A TEST CODE SD 1 NP-12 Scan 1 Water  
Date & Time Collected 02/10/88 13:40:00 Category

ANALYST KAJIYA  
ANALYZED 03/01/88  
DILUTION 1

UNITS ug/L app

CASE	COMPOUND	DETECTION	
		RESULT	REMARK LIMIT
75-01-4	Vinyl chloride	ND	5.0
75-01-9	*Bromomethane	ND	5.0
75-00-3	*Chloroethane	ND	5.0
75-01-4	*Trichlorofluoroethane	ND	5.0
75-35-4	1,1-Dichloroethane	ND	1.0
75-00-2	*Methylene chloride	ND	5.0
154-60-5	trans-1,2-Dichloroethane	ND	1.0
75-31-1	*1,1-Dichloroethane	ND	1.0
154-59-2	cis-1,2-Dichloroethane	ND	1.0
67-66-3	*Chloroform	ND	1.0
71-55-6	*1,1,1-Trichloroethane	ND	1.0
54-23-5	*Carbon tetrachloride	ND	1.0
107-06-2	*1,2-Dichloroethane	ND	1.0
79-01-6	Trichloroethane	ND	1.0
78-97-8	*1,2-Dichloropropane	ND	1.0
75-27-4	*Dibromodichloroethane	ND	1.0
10061-01-5	cis-1,3-Dichloropropene	ND	1.0
10061-02-6	trans-1,3-Dichloropropene	ND	1.0
75-00-5	*1,1,2-Trichloroethane	ND	1.0
127-18-4	Tetrachloroethane	ND	1.0
124-48-1	*Dibromochloroethane	ND	1.0
108-90-7	Chlorobenzene	ND	5.0
75-25-2	*Bromoform	ND	1.0
79-34-5	*1,1,2,2-Tetrachloroethane	ND	1.0

COMMENTS LAB WATER BLANK

ND = not detected at the specified detection limit.  
\* Compound identity not confirmed by second independent technique.

Page 16  
Received: 02/11/88

DNR Laboratory  
Results by Sample

REPORT

Work Order # 88-02-041

SAMPLE ID FIELD BLANK

FRACTION 07A TEST CODE SC 2 NAME Scan 2 Water

Date & Time Collected 02/10/88 13:40:00

Category

ANALYST KAJIYA

ANALYSED 03/01/88

DILUTION 1

UNITS ug/L g/g

CASE	COMPOUND	RESULT	REMARK	DETECTION LIMIT
71-43-2	Benzene	ND		1.0
108-88-3	Toluene	ND		1.0
100-41-4	Ethylbenzene	ND		1.0
102-75-3	Xylene isomers	ND		1.0

COMMENTS LAB WATER BLANK

ND = not detected at the specified detection limit.

Ruanex Corp., South Lyons MID 082 767 591

Parameter	mg/l unless noted	MW1	MW1A	MW1B	MW3A	MW3B	MW4A	Field Blank
Alkalinity		103	136	120	308	142	350	<5.0
Carbonate Alk		<5	<5	<5	<5	<5	<5	<5
Bicarbonate Alk		103	136	120	308	142	350	<5
Chloride		47	74	78	44	50	170	<1.0
Arsenic		<0.002	0.0034	0.004	<0.002	0.004	0.0066	<0.002
Barium		0.034	0.072	0.022	0.125	0.026	0.118	<0.01
Calcium		365	374	334	497	391	306	<1
Cadmium		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Chromium		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Copper		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Iron	dissolved	3.3	5.95	3.1	3.5	6.35	12.5	<0.1
Potassium		7.6	10.6	5.14	2.45	5.2	3.4	<0.1
Magnesium		32.2	34.2	37.5	78	53	19.7	<1
Manganese		0.995	0.885	0.45	0.9	0.36	0.17	<0.02
Sodium		84.1	61.3	61.9	61.1	54.6	73	<1
Nickel		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Lead		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Zinc		0.97	<0.05	<0.05	<0.05	<0.05	0.48	<0.05
Conductivity	umhos/cm	1880	1720	1680	2200	1645	1660	—
pH	su	6.5	6.8	6.8	6.6	6.8	6.6	—
Sulfate		1070	910	818	1120	1050	330	<2.0

	ug/l						
1,1 Dichloroethane	<1.0	<1.0	4.0	<1.0	<1.0	<1.0	<1.0
Others in Scan 1 *	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Toluene	<1.0	<1.0	1.1 UC	<1.0	<1.0	<1.0	<1.0
Others in Scan 2 *	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0

\* All volatile organic scan data coded HT  
 HT - The recommended maximum laboratory holding time was exceeded  
 before analysis.  
 See attached list for organic scan parameters and detection limits.

# SCAN 1 - PURGEABLE HALOCARBONS

<u>COMPOUND</u>	<u>DETECTION LIMIT (ug/l)</u>
Vinyl chloride	5.0
Bromomethane*	5.0
Chloroethane*	5.0
Trichlorofluoromethane*	5.0
1,1-Dichloroethene	1.0
Methylene chloride*	5.0
trans-1,2-Dichloroethene	1.0
1,1-Dichloroethane*	1.0
cis-1,2-Dichloroethene	1.0
Chloroform*	1.0
1,1,1-Trichloroethane*	1.0
Carbon tetrachloride*	1.0
1,2-Dichloroethane*	1.0
Trichloroethene	1.0
1,2-Dichloropropane*	1.0
Bromodichloromethane*	1.0
cis-1,3-Dichloropropene	1.0
trans-1,3-Dichloropropene	1.0
1,1,2-Trichloroethane*	1.0
Tetrachloroethene	1.0
Dibromochloromethane*	1.0
Chlorobenzene	5.0
Bromoform*	1.0
1,1,2,2-Tetrachloromethane*	1.0

\* Compound not confirmed by second independent technique.

# SCAN 2 - PURGEABLE AROMATIC HYDROCARBONS

<u>COMPOUND</u>	<u>DETECTION LIMIT (ug/l)</u>
Benzene	1.0
Toluene	1.0
Ethylbenzene	1.0
Xylene isomers	1.0